

Solicitation No.: DACW64-02-B-0009 Date Issued: 14 Jan 02 Date Opened: 13 Feb 02

Issuing Office: USAED-Galveston

Project Title: Sims Bayou, Houston, Channel Repairs, Lower Oxbow Slide Repairs in Harris County, Texas.

Number of Amendments Issued: None

Government Estimate (Without Profit) REVISED

ITEM NO.	DESCRIPTION	QUANTITY		UNIT PRICE	TOTAL
0001	Environmental Protection/EPA Storm Water Pollution Prevention Controls	1	LS	36120.00	36,120.00
0002	Clearing, Grubbing, and Removal of Debris	1	LS	3100.00	3,100.00
0003	Stripping	1	LS	3300.00	3,300.00
0004	Excavation, Site 1				
0004AA	Lines and Grades	1,960	C.Y.	5.50	
0004AB	Below Lines and Grades	500	C.Y.	5.50	13,530.00
0005	Exploratory Trench				
0005AC	Lines and Grades	1,000	C.Y.	17.50	
0005AD	Below Lines and Grades	250	C.Y.	5.50	18,875.00
0006	Excavation, Sites 2,3, and 4	1,000	C.Y.	6.25	6,250.00
0007	Compacted Fill, Site 1				
0007AE	Lines and Grades	2,290	C.Y.	5.50	
0007AF	Below Lines and Grades	500	C.Y.	7.50	16,345.00
0008	Compacted Fill, Sites 2, 3, and 4	805	C.Y.	8.00	6,440.00
0009	Soil Surface Erosion Control (Site No. 3)	1	L.S.	1400.00	1,400.00
0010	Geotextile	430	S.Y.	2.40	1,032.00
0011	Blanket Stone (1/4" - 4")	400	TONS	44.85	17,940.00
0012	Riprap (5-80 lbs)	40	TONS	44.00	1,760.00
0013	Riprap (40- 625 lbs)	700	TONS	48.00	33,600.00
0014	Turfing	1	L.S.	6750.00	6,750.00
0015	Tree Transplants	25	Each-	45.00	1,125.00
TOTAL SCHEDULE NO. 1					167,567.00

The apparent low bidder is 24.93% above the Government's Estimate

I CERTIFY THAT I HAVE OPENED, READ, AND RECORDED ON THIS ABSTRACT ALL OFFERS RECEIVED IN RESPONSE TO THIS SOLICITATION.

CURTIS COLE, JR.

Solicitation No.: DACW64-02-B-0009 Date Issued: 14 Jan 2002 Date Opened: 13 Feb 2002

Project Title: SIMS BAYOU, HOUSTON, TEXAS CHANNEL REPAIRS, LOWER OXBOX SLIDE REPAIRS

Offeror: LECON INC -4319 PINEMONT HOUSTON, TX 77018

Business Size: SMALL BUSINESS

ITEM NO.	DESCRIPTION	QUANTITY		UNIT PRICE	TOTAL
0001	Environmental Protection/EPA Storm Water Pollution Prevention Controls	1	L.S.	10000.00	10,000.00
0002	Clearing, Grubbing, and Removal of Debris	1	L.S.	31000.00	31,000.00
0003	Stripping	1	L.S.	3000.00	3,000.00
0004	Excavation, site 1				
0004AA	Lines and Grades	1,960	C.Y.	7.00	
0004AB	Below Lines and Grades	500	C.Y.	10.00	18,720.00
0005	Exploratory Trench				
0005AC	Lines and Grades	1,000	C.Y.	9.00	
0005AD	Below Lines and Grades	250	C.Y.	10.00	11,500.00
0006	Excavation, Sites 2, 3 and 4	1,000	C.Y.	8.00	8,000.00
0007	Compacted Fill, Site 1				
0007AE	Lines and Grades	2290	C.Y.	9.00	
0007AF	Below Lines and Grades	500	C.Y.	10.00	25,610.00
0008	Compacte Fill, sites 2, 3 and 4	805	C.Y.	13.00	10,465.00
0009	Soil Surface Erosion Control (Site No. 3)	1	L.S.	4000.00	4,000.00
0010	Geotextile	430	S.Y.	3.00	1,290.00
0011	Blanket Stone (1/4" - 4")	400	TONS	65.00	26,000.00
0012	Riprap (5-80 lbs)	40	TONS	75.00	3,000.00
0013	Riprap (40-625 lbs)	700	TONS	65.00	45,500.00
0014	Turfing	1	L.S.	5000.00	5,000.00
0015	Tree Transplants	25	Each	250.00	6,250.00
TOTAL SCHEDULE NO. 1					\$209,335.00

Solicitation No.: DACW64-02-B-0009 Date Issued: 14 Jan 2002 Date Opened: 13 Feb 2002

Project Title: SIMS BAYOU, HOUSTON, TEXAS CHANNEL REPAIRS, LOWER OXBOX SLIDE REPAIRS

Offeror: MIDWEST CONSTRUCTION COMPANY P. O. BOX 610 406 North 22 Street Nebraska City, NE 68410

Business Size: SMALL BUSINESS

ITEM NO.	DESCRIPTION	QUANTITY		UNIT PRICE	TOTAL
0001	Environmental Protection/EPA Storm Water Pollution Prevention Controls	1	L.S.	46656.77	46,656.77
0002	Clearing, Grubbing, and Removal of Debris	1	L.S.	13016.53	13,016.53
0003	Stripping	1	L.S.	22227.23	22,227.23
0004	Excavation, site 1				
0004AA	Lines and Grades	1,960	C.Y.	12.90	
0004AB	Below Lines and Grades	500	C.Y.	12.16	31,364.00
0005	Exploratory Trench				
0005AC	Lines and Grades	1,000	C.Y.	12.16	
0005AD	Below Lines and Grades	250	C.Y.	17.21	16,462.50
0006	Excavation, Sites 2, 3 and 4	1000	C.Y.	12.16	12,160.00
0007	Compacted Fill, Site 1				
0007AE	Lines and Grades	2290	C.Y.	14.36	
0007AF	Below Lines and Grades	500	C.Y.	15.91	40,839.40
0008	Compacted Fill, Site 2, 3, and 4	805	C.Y.	14.36	11,559.80
0009	Soil Surface Erosion Control (Site No.3)	1	L.S.	20200.39	20,200.39
0010	Geotextile	430	S.Y.	4.60	1,978.00
0011	Blanket Stone (1/4' - 4")	400	TONS	92.81	37,124.00
0012	Riprap (5- 80 lbs)	40	TONS	134.72	5,388.80
0013	Riprap (40- 625 lbs)	700	TONS	87.67	61,369.00
0014	Turfing	1	L.S.	8249.99	8,249.99
0015	Tree Transplants	25	Each	1858.27	46,456.75
TOTAL SCHEDULE NO. 1					\$375,053.16