

FY18 Scheduled Contracts FY19 Planned Contracts

Christopher Frabotta
Chief, Navigation Branch
Galveston District
U.S. Army Corps of Engineers
31 OCT 2017

“The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation.”



**US Army Corps
of Engineers**






GALVESTON DISTRICT FACTS


- ✓ Texas #2 in Nation in Maritime Commerce
- ✓ Texas Ports moved 552M+ tons in 2015
- ✓ Galveston District Ports National Rank
 - ✓ Houston (2)
 - ✓ Beaumont (5)
 - ✓ Corpus Christi (6)
 - ✓ Texas City (15)
 - ✓ Port Arthur (19)
 - ✓ Freeport (32)
 - ✓ Matagorda (46)
 - ✓ Galveston (51)
 - ✓ Brownsville (66)
 - ✓ Victoria (70)

- ✓ Gulf Intracoastal Waterway (3)
 - ✓ GIWW-TX 73M+ tons at \$43B in 2015
 - ✓ >600M tons of Commercial Cargo
 - ✓ 21.8% Nation's Total Tonnage
 - ✓ 25.4% of Nation's Imports
 - ✓ 28.6% of Nation's Exports



Coastal Navigation: Value to the Nation

USACE Southwestern Division Regional Priority




Texas is the number two state in the nation for **waterborne commerce**. Texas ports generate over **\$5 billion** in local and state tax revenue, and over **\$9 billion** in federal import tax revenue each year.

With the **Panama Canal Expansion** opening in **2017**, ports must expand their capacity via land-and-waterside improvements to accept these ships. The **Texas** navigation system has **post-Panamax** projects ready for construction and studies are completed for deepening Port Freeport, Corpus Christi Ship Channel and the Sabine-Neches Waterway to depths that would allow post-Panamax ships to call.



LEADING U.S. PORTS (2015 Tonnage)

- Houston #2** - 240.9 million tons
#1 Foreign Tonnage & #2 Total Tonnage
- Beaumont #5** - 87.2 m.tons
#1 Military Port in World
- Gulf Intracoastal Waterway (79 million tons - Texas portion)**
#3 Inland Waterway
- Corpus Christi #6** - 85.7 m.tons
America's Energy Gateway
- Texas City #15** - 42.9 m.tons
Services Largest Petrochemical Complex
- Port Arthur #19** - 35.8 m.tons
Vital Break-Bulk Port
- Freeport #32** - 21.1 m.tons
Connecting Global Services Via Caribbean Relay Port
- Matagorda to include Port of Port Lavaca and Port of Point Comfort #46** - 11.8 m. tons
Generates Annual Business Revenues of Nearly \$2 Billion
- Galveston #51** - 10.4 m.tons
#4 Cruise Ship Port
- Brownsville #66** - 7.7 m.tons
#1 Ship Recycling Port
- Victoria (#70)** - 6.7 m.tons
#2 Shallow-Draft Port for Domestic Crude Petroleum





GALVESTON NAVIGATION OM FUNDING

FY-17 Execution

President's Budget (less %1) \$106,737,000

FY-17 Allocation \$128,037,000

Carry-in \$ 13,727,000

Available to Obligate \$141,764,000

Obligated ~\$120,000,000

Percent Execution ~85%

FY-18 Funding Outlook

President's Budget \$109,442,000

Carry-in \$ 13,727,000

Total Anticipated \$121,542,000





FY-18 INITIATIVES

- **Continue Hydrographic Survey Webpage**
 - All six (6) Deep Draft Navigation Complexes & Gulf Intracoastal Waterway now online
 - <http://www.swg.usace.army.mil/Missions/Navigation.aspx>
- **Continue with TCOON Partnership with NOAA**
 - Add Matagorda Ship Channel current meter
- **Complete Re-Spacing & Deployment of new GIWW Mooring Buoys**
- **Construct non-Federal Placement Area Capacity**
 - Corpus Christi (PA-13)
 - Freeport Harbor (PA-1)
 - Sabine-Neches Waterway (PA-8)



Operations Managers



OPERATIONS MANAGERS

Belynda Kinman

Tricia Campbell

Aron Edwards

Steve Howard

Seth Jones

Ashton Burgin

Eric Russek



BUILDING STRONG®

Sabine-Neches Waterway

Belynda Kinman
Operations Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting

Custodians of the Texas Coast




®

US Army Corps of Engineers
BUILDING STRONG®





DEEP DRAFT FY18 CONTRACT SCHEDULES





Sabine-Neches Waterway





SABINE-NECHES WATERWAY – LOWER NECHES, PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU



Project:	Lower Neches, Port Arthur Canal, Turning Basin, Junction & Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 13 - 17
Distance to Place Area:	1 - 3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Start Date:	June 28, 2018
Est. Completion Date:	January 26, 2019





SABINE-NECHES WATERWAY – LOWER NECHES, PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU

2 of 2



Project:	Lower Neches, Port Arthur Canal, Turning Basin, Junction & Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 8 and PA 9
Distance to Place Area:	1.5 - 2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Start Date:	June 28, 2018
Est. Completion Date:	January 26, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



SABINE-NECHES WATERWAY OUTER BAR AND BANK CHANNEL



Project:	Sabine Neches Waterway Outer Bar and Bank Channel
Dredging Depth:	44 ft. Required Depth
Dredging Width:	800 ft.
Dredging Length:	Varies
Dredging Quantity:	3,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	Offshore
Distance to Placement Area:	3 Mile Avg.
Type of Equipment:	Hopper
Env. Window	NA
Reason for Window:	NA
Start Date:	July 11, 2018
Est. Completion Date:	November 10, 2018





SABINE-NECHES WATERWAY PLACEMENT AREA NO. 8 IMPROVEMENTS



Project:	Sabine Neches Waterway Placement Area No. 8 Improvements
Type of Work:	Containment Dike Raise
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	PA 8
Distance to Placement Area:	NA
Type of Equipment:	Excavators; Dozers; Marsh Buggy
Env. Window:	NA
Reason for Window:	NA
Start Date:	July 20, 2018
Est. Completion Date:	January 16, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



SHALLOW DRAFT – GIWW TRIBUTARIES CHOCOLATE BAYOU



US Army Corps
of Engineers®
Galveston District




Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



CHOCOLATE BAYOU



Project:	Chocolate Bayou
Dredging Depth:	15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	700,000 cubic yards
Material Type:	Silt/Sand
Placement Area:	BU / Upland Confined
Distance to Placement Area:	1.5 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	1 March – 31 August
Reason for Window:	Nesting birds at BU Site
Start Date:	June 11, 2018
Est. Completion Date:	February 6, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





SABINE-NECHES WATERWAY NECHES RIVER



Project:	Sabine-Neches Waterway Neches River
Dredging Depth:	42 ft. Required Depth
Dredging Width:	Varies
Dredging Length:	Varies
Dredging Quantity:	600,000 cubic yards
Material Type:	Silt
Placement Area:	Various Upland PAs
Distance to Placement Area:	1- 2 Miles
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	February 12, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



SABINE-NECHES WATERWAY PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU



Project:	Sabine-Neches Waterway Port Arthur Canal, Turning Basin, Junction Area and Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 8 and PA 9
Distance to Place Area:	1.5 - 2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	September 10, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Questions Comments?



For more information, contact:

Belynda Kinman
Operations Manager

Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-6323

Belynda.m.kinman@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Galveston Harbor and Channel & Houston Ship Channel

Tricia Campbell, P.E.
Operations Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting
Custodians of the Texas Coast



®

US Army Corps of Engineers
BUILDING STRONG®





DEEP DRAFT FY18 CONTRACT SCHEDULES





HOUSTON SHIP CHANNEL – GALVESTON HARBOR TEXAS CITY SHIP CHANNEL



US Army Corps
of Engineers®
Galveston District




Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GALVESTON HARBOR




Project:	Galveston Harbor Channel
Dredging Depth:	41 - 46 ft. Required Depth
Dredging Width:	Varies
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt
Placement Area:	Offshore
Distance to Place Area:	8 Miles Avg.
Type of Equipment:	Hopper Dredge
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 9, 2018
Est. Completion Date:	December 28, 2018





GALVESTON HARBOR – PELICAN ISLAND PLACEMENT AREA IMPROVEMENTS




Project:	Galveston Harbor – Pelican Island Placement Area Improvements
Type of Work:	Improvements
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Pelican Island
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019





GALVESTON HARBOR – SAN JACINTO PLACEMENT AREA IMPROVEMENTS




Project:	Galveston Harbor – San Jacinto Placement Area Improvements
Type of Work:	Improvements
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	San Jacinto
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019





HOUSTON SHIP CHANNEL – CARPENTERS BAYOU TO SIMS BAYOU EMERGENCY DREDGING



Project:	Houston Ship Channel Carpenters Bayou to Sims Bayou Emergency Dredging
Dredging Depth:	48 ft./43 ft. Required Depth
Dredging Width:	300 - 950 ft.
Dredging Length:	Varies
Dredging Quantity:	500,000 cubic yards
Material Type:	Silt
Placement Area:	Lost Lake & Rosa Allen
Distance to Place Area:	5 Miles
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	February 10, 2018
Est. Completion Date:	July 30, 2018

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL PLACEMENT AREA NO. 14 DEWATERING



Project:	Houston Ship Channel Placement Area No. 14 Dewatering
Type of Work:	Placement Area Dewatering
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	
Placement Area:	PA 14
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	August 31, 2018
Est. Completion Date:	February 27, 2019


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL – BAYPORT TO MORGANS AND BAYPORT



Project:	Houston Ship Channel Bayport Flare and Bayport to Morgan's Point
Dredging Depth:	48 ft. Required Depth
Dredging Width:	300 - 530 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt
Placement Area:	PA14 and 15; Marsh Cells
Distance to Place Area:	4 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	August 31, 2018
Est. Completion Date:	May 28, 2019


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL - PLACEMENT AREA NO. 15 SPILLBOX REPAIR & DEWATERING



Project:	Houston Ship Channel - Placement Area No. 15 Spillbox Repair & Dewatering
Type of Work:	Spillbox Repair/Dewatering
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	
Placement Area:	PA 15
Distance to Place Area:	NA
Type of Equipment:	Crane/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	October 11, 2018
Est. Completion Date:	April 9, 2019


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL – WEST CLINTON PLACEMENT AREA IMPROVEMENTS



Project:	Houston Ship Channel West Clinton Improvements
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	West Clinton
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	October 5, 2018
Est. Completion Date:	October 5, 2019





HOUSTON SHIP CHANNEL MORGAN'S POINT TO EXXON



Project:	Houston Ship Channel - Morgan's Point to Exxon
Dredging Depth:	48 ft. Required Depth
Dredging Width:	530 – 600 ft.
Dredging Length:	Varies
Dredging Quantity:	1,400,000 cubic yards
Material Type:	Silt
Placement Area:	Alexander Island
Distance to Place Area:	3 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Est. Start Date:	October 26, 2018
Est. Completion Date:	July 23, 2019


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL MID BAY PLACEMENT AREA IMPROVEMENTS




Project:	Houston Ship Channel Mid Bay PA Improvements
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Mid Bay
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	August 31-March 1 (open)
Reason for Window:	Migratory Birds
Est. Start Date:	November 3, 2018
Est. Completion Date:	August 30, 2019





HOUSTON SHIP CHANNEL LOST LAKE PA IMPROVEMENT



Project:	Houston Ship Channel Lost Lake PA Improvements
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	NA
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 12, 2018
Est. Completion Date:	November 7, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL ALEXANDER ISLAND PA IMPROVEMENTS



Project:	Houston Ship Channel Alexander Island Improvements
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Alexander Island PA
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®




DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





GALVESTON HARBOR - GALVESTON ENTRANCE CHANNEL AND HSC - BOLIVAR ROADS TO REDFISH



Project:	Galveston Harbor - Galveston Entrance Channel and Houston Ship Channel - Bolivar Roads to Redfish
Dredging Depth:	48 - 50 ft. Required Depth
Dredging Width:	530 – 1,000 ft.
Dredging Length:	17 miles
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand / Silt
Placement Area:	Offshore
Distance to Place Area:	1 - 15 Mile
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Award:	January 15, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL – PLACEMENT AREA NO. 14 & 15 DIKE RAISE




Project:	Houston Ship Channel Placement Area No. 14 & 15 Dike Raise
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	
Placement Area:	PA 14 & 15
Distance to Place Area:	NA
Type of Equipment:	Crane/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	October 15, 2018





HOUSTON SHIP CHANNEL – REDFISH TO BEACON 78 WITH BAYPORT FLARE




Project:	Houston Ship Channel Redfish to Beacon 78 with Bayport Flare
Dredging Depth:	48 ft. Required Depth
Dredging Width:	530 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand
Placement Area:	Offshore
Distance to Place Area:	Varies
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Award:	February 15, 2019





HOUSTON SHIP CHANNEL – BOGGY BAYOU TO GREENS BAYOU AND GREENS BAYOU



Project:	Houston Ship Channel Boggy Bayou to Greens Bayou and Greens Bayou
Dredging Depth:	38 - 43 ft. Required Depth
Dredging Width:	300 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Silt
Placement Area:	Lost Lake/Clinton
Distance to Place Area:	5 Miles
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	March 15, 2019





HOUSTON SHIP CHANNEL – EXXON TO BOGGY BAYOU AND JACINTOPORT



Project:	Houston Ship Channel Exxon to Boggy Bayou and Jacintoport
Dredging Depth:	48 ft. Required Depth
Dredging Width:	300 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Silt
Placement Area:	Lost Lake PA and Peggy Lake PA
Distance to Place Area:	3 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Award:	May 30, 2019





HOUSTON SHIP CHANNEL – SIMS BAYOU TO TURNING BASIN AND LIGHT DRAFT CHANNEL




Project:	Houston Ship Channel – Sims Bayou to Turning Basin and Light Draft Channel
Dredging Depth:	HSC 39 ft. Required Depth Light Draft 11 ft. Required
Dredging Width:	530 – 1,000 ft.
Dredging Length:	17 miles
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Sand / Silt
Placement Area:	House Tract
Distance to Place Area:	7 Miles
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 30, 2019





HOUSTON SHIP CHANNEL – SPILMAN ISLAND PA DEWATERING



Project:	Houston Ship Channel Spilman Island PA Dewatering
Type of Work:	Placement Area Dewatering
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Spilman Island
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	September 30, 2019



Questions Comments?



For more information, contact:

Tricia Campbell
Operations Manager

Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3153
tricia.c.campbell@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Freeport Harbor & Matagorda Ship Channel

Aron Edwards
Operations Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting

Custodians of the Texas Coast



®

US Army Corps of Engineers
BUILDING STRONG®





DEEP DRAFT FY18 CONTRACT SCHEDULES





Freeport Harbor





FREEPORT HARBOR PLACEMENT AREA #1 CONTAINMENT DIKE RAISE



Project:	Freeport Harbor, TX Placement Area #1 Containment Dike Raise
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Sand/Silt
Placement Area (PA):	PA 1
Distance to PA:	NA
Type of Equipment:	Dragline/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	January 1, 2018
Est. Completion Date:	January 12, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



FREEPORT HARBOR JETTY CHANNEL AND INSIDE CHANNEL



Project:	Freeport Harbor Jetty Channel and Inside Channel
Dredging Depth:	46 ft. Required Depth
Dredging Width:	280 - 1190 ft.
Dredging Length:	Varies
Dredging Quantity:	2,600,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Offshore
Distance to Place Area:	2.5 Mile Avg.
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 13, 2018
Est. Completion Date:	November 12, 2018


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



Matagorda Ship Channel




Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



MATAGORDA SHIP CHANNEL MATAGORDA PENINSULA TO POINT COMFORT



Project:	Matagorda Ship Channel Matagorda Peninsula to Point Comfort
Dredging Depth:	40 ft. Required Depth
Dredging Width:	200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open Water/Semi Confined
Distance to Place Area:	Varies
Type of Equipment:	Pipeline Dredge
Env. Window:	Sept 1 – Feb 28 (Open)
Reason for Window:	Nesting birds Sundown Is
Est. Start Date:	July 24, 2018
Est. Completion Date:	March 6, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





FREEPORT HARBOR JETTY CHANNEL AND INSIDE CHANNEL



Project:	Freeport Harbor Jetty Channel and Inside Channel
Dredging Depth:	48-49 ft. Required Depth
Dredging Width:	280 - 1190 ft.
Dredging Length:	Varies
Dredging Quantity:	2,600,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Offshore
Distance to Place Area:	2.5 Mile Avg.
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	June 14, 2019


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



MATAGORDA SHIP CHANNEL MATAGORDA PENINSULA TO POINT COMFORT



Project:	Matagorda Ship Channel Matagorda Peninsula to Point Comfort
Dredging Depth:	40 ft. Required Depth
Dredging Width:	200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open Water/Semi Confined
Distance to Place Area:	Varies
Type of Equipment:	Pipeline Dredge
Env. Window:	Sept 1 – Feb 28 (Open)
Reason for Window:	Nesting birds Sundown Is
Award:	September 16, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Questions Comments?



For more information, contact:

Aron Edwards
Operations Manager

Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3028
aron.s.edwards@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Corpus Christi Ship Channel

Steven Howard
Operations Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting
Custodians of the Texas Coast




®

US Army Corps of Engineers
BUILDING STRONG®






DEEP DRAFT FY18 CONTRACT SCHEDULES





Corpus Christi Ship Channel





CORPUS CHRISTI SHIP CHANNEL INNER BASIN TO VIOLA T.B. & LA QUINTA CHANNEL



Project:	Corpus Christi Ship Channel Inner Basin to Viola Turning Basin / La Quinta Channel
Dredging Depth:	49-ft. Required Depth
Dredging Width:	300-400ft.
Dredging Length:	Varies
Dredging Quantity:	2,900,000 cubic yards
Material Type:	Silt / Sand
Placement Area:	Open Water and Upland
Distance to Placement Area:	1-4 Miles
Type of Equipment:	Pipeline Dredge
Env. Window	Sep. – Feb. (Open)
Reason for Window:	Nesting Birds PA 7-8
Start Date:	July 16, 2018
Est. Completion Date:	February 15, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



CORPUS CHRISTI SHIP CHANNEL JETTY REPAIRS




Project:	Corpus Christi Ship Channel Jetty Repairs
Type of Work:	Jetty Repairs
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Distance to Placement Area:	NA
Type of Equipment:	Marine Construction
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 12, 2018
Est. Completion Date:	March 5, 2019





CORPUS CHRISTI SHIP CHANNEL PLACEMENT AREA NO. 10 (PA 10) IMPROVEMENTS




Project:	Corpus Christi Ship Channel PA 10 Improvements
Type of Work:	Containment Dike
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	PA 10
Distance to Placement Area:	NA
Type of Equipment:	Bull dozers; Excavators
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 20, 2018
Est. Completion Date:	August 10, 2019





CORPUS CHRISTI SHIP CHANNEL – SUNTIDE PLACEMENT AREA IMPROVEMENT




Project:	CCSC - Suntide Placement Area Improvement
Type of Work:	Levee
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	Suntide
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 15, 2018
Est. Completion Date:	March 16, 2019





CHANNEL TO VICTORIA AND CHANNEL TO SEADRIFT




Project:	GIWW, Ch to Victoria Lower Reach, Seadrift
Dredging Depth:	16-ft Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Silt/Sand
Placement Area (PA):	Upland Confined
Distance to PA:	2.0 Mile (avg.)
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 30, 2018
Est. Completion Date:	November 16, 2018






DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





CORPUS CHRISTI SHIP CHANNEL – TULE LAKE PLACEMENT AREA IMPROVEMENT



Project:	CCSC – Tule Lake Placement Area Improvement
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Tule Lake
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	April 15, 2019





CORPUS CHRISTI SHIP CHANNEL INNER BASIN TO VIOLA



Project:	Corpus Christi Ship Channel Inner Basin to Viola
Dredging Depth:	49-ft. Required Depth
Dredging Width:	300-400ft.
Dredging Length:	Varies
Dredging Quantity:	2,500,000 cubic yards
Material Type:	Silt / Sand
Placement Area:	Open Water and Upland
Distance to Placement Area:	1-4 Miles
Type of Equipment:	Pipeline Dredge
Env. Window	Sep. – Feb. (Open)
Reason for Window:	Nesting Birds PA 7-8
Award:	August 15, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Questions Comments?



For more information, contact:

Steven Howard

Operations Manager

409-766-3026

steven.b.howard@usace.army.mil

**Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston**

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Brazos Island Harbor (BIH) & Gulf Intracoastal Waterway

Seth Jones
Operation Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting

Custodians of the Texas Coast



®

US Army Corps of Engineers
BUILDING STRONG®





DEEP DRAFT FY18 CONTRACT SCHEDULES





Brazos Island Harbor (Brownsville Harbor)



US Army Corps
of Engineers®
Galveston District

Brazos Island Harbor (BIH) Brownsville Ship Channel





BRAZOS ISLAND HARBOR JETTY CHANNEL WITH BEACH PLACEMENT



Project:	Brazos Island Harbor Brownsville Jetty Channel
Dredging Depth:	46 ft. Required Depth
Dredging Width:	300 - 400 ft.
Dredging Length:	Varies
Dredging Quantity:	400,000 cubic yards
Material Type:	Sand
Placement Area:	Beach/BU
Distance to Place Area:	1-5 Miles Avg.
Type of Equipment:	Hopper/Pipeline
Env. Window:	1 Oct- 14Mar
Reason for Window:	Turtle/Tourism
Est. Start Date:	February 2, 2018; September 27, 2018
Est. Completion Date:	March 31, 2018 November 26, 2018

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



DEEP DRAFT FY19 CONTRACT SCHEDULES





BRAZOS ISLAND HARBOR MAIN CHANNEL



Project:	Brazos Island Harbor Brownsville Ship Channel
Dredging Depth:	44 ft. Required Depth
Dredging Width:	250 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Silt
Placement Area:	Upland
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	June 12, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



BRAZOS ISLAND HARBOR JETTY CHANNEL WITH BEACH PLACEMENT



Project:	Brazos Island Harbor Brownsville Jetty Channel
Dredging Depth:	46 ft. Required Depth
Dredging Width:	300 - 400 ft.
Dredging Length:	Varies
Dredging Quantity:	400,000 cubic yards
Material Type:	Sand
Placement Area:	Beach/BU
Distance to Place Area:	1-5 Miles Avg.
Type of Equipment:	Hopper/Pipeline
Env. Window:	1 Oct- 14Mar
Reason for Window:	Turtle/Tourism
Award:	September 17, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®




SHALLOW DRAFT FY18 CONTRACT SCHEDULES



U.S. Army Corps
of Engineers
Galveston District




O&M Project Map Book GIWW - Galveston District GIWW Tributaries



GULF OF MEXICO



GULF INTRACOASTAL WATERWAY CHANNEL ACROSS ARANSAS BAY



Project:	Gulf Intracoastal Waterway Channel Across Aransas Bay
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,200,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open / BU
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	April thru Oct
Reason for Window:	Whooping Crane/Nesting Birds
Est. Start Date:	March 3, 2018
Est. Completion Date:	October 14, 2018


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY – FREEPORT TO CANEY CREEK, BRAZOS RIVER CROSSING



Project:	Gulf Intracoastal Waterway Freeport to Caney Creek, Brazos River Crossing
Dredging Depth:	13-15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	600,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open / BU
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 29, 2018
Est. Completion Date:	September 29, 2018





GULF INTRACOASTAL WATERWAY PA 86 & 87 IMPROVEMENTS



Project:	Gulf Intracoastal Waterway PA 86 & 87 Containment Dike Raise
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	PA 86 & 87
Distance to Place Area:	NA
Type of Equipment:	Dragline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 29, 2018
Est. Completion Date:	July 5, 2019



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN




Project:	Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Est. Start Date:	July 29, 2018
Est. Completion Date:	February 28, 2019





GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



Project:	Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Est. Start Date:	July 29, 2018
Est. Completion Date:	February 28, 2019





GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



Project:	Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Upland
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Mar. – 31 Aug.
Reason for Window:	Nesting Birds
Est. Start Date:	July 29, 2018
Est. Completion Date:	February 28, 2019





GULF INTRACOASTAL WATERWAY - ROLLOVER PASS TO GALVESTON CAUSEWAY & BOLIVAR FLARE



Project:	Gulf Intracoastal Waterway Rollover to Causeway & Bolivar Flare
Dredging Depth:	15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	800,000 cubic yards
Material Type:	Fine Sand/Silt
Placement Area:	Upland/Open Water/BU
Distance to Place Area:	2.0 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	N/A
Reason for Window:	N/A
Est. Start Date:	September 19, 2018
Est. Completion Date:	January 16, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®




SHALLOW DRAFT FY19 PLANNED CONTRACT SCHEDULES



U.S. Army Corps
of Engineers
Galveston District



O&M Project Map Book GIWW - Galveston District GIWW Tributaries



GULF OF MEXICO



GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING



Project:	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019





GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING



Project:	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019





GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING




Project:	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	1 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019





GULF INTRACOASTAL WATERWAY – ACROSS SAN ANTONIO BAY; MATAGORDA BAY TO CORPUS CHRISTI; MSC INTERSECTION



Project:	GIWW - Across San Antonio Bay / Matagorda Bay to Corpus Christi; GIWW / MSC Intersection
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined/BU
Distance to Placement Area:	1 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 19, 2019



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN




Project:	Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Award:	August 15, 2019





GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



Project:	Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Award:	August 15, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



Project:	Channel to Harlingen
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Upland
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Mar. – 31 Aug.
Reason for Window:	Nesting Birds
Award:	August 15, 2019





GULF INTRACOASTAL WATERWAY – HIGH ISLAND TO ROLLOVER; BOLIVAR FLARE; CHANNEL TO PORT BOLIVAR



Project:	GIWW - High Island to Rollover; Bolivar Flare; Channel to Port Bolivar
Dredging Depth:	15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	800,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined/BU
Distance to Placement Area:	1 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	September 17, 2019



Questions Comments?



For more information, contact:

Seth Jones
Operations Manager

Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3068

Seth.w.jones@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Cedar Bayou

Ashton Burgin
Operations Manager
Navigation Branch
31 October 2017

Galveston District – Dredging Meeting

Custodians of the Texas Coast



®

US Army Corps of Engineers
BUILDING STRONG®






SHALLOW DRAFT TRIBUTARIES FY18 CONTRACT SCHEDULE



US Army Corps
of Engineers
Galveston District



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



HOUSTON SHIP CHANNEL TRIBUTARIES CEDAR BAYOU



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



CEDAR BAYOU



Project:	Cedar Bayou
Dredging Depth:	12 ft. Required Depth
Dredging Width:	100 ft.
Dredging Length:	Varies
Dredging Quantity:	680,000 cubic yards
Material Type:	Silt/Sand
Placement Area:	Open water
Distance to Placement Area:	4 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Reason for Window:	NA
Start Date:	November 1, 2018
Est. Completion Date:	February 12, 2019



Questions Comments?



For more information, contact:

Ashton Burgin
Operations Manager

Navigation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3958
ashton.burgin@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Brazos River Floodgates, Colorado River Locks & Mooring Buoy Maintenance

Eric Russek, P.E.

Operations Manager

Project Operations Br, Galveston

31 October 2017

Galveston District – Dredging Meeting

Custodians of the Texas Coast




®

US Army Corps of Engineers
BUILDING STRONG®





Navigation Project Facilities





Navigation Project Facilities



Brazos River Floodgates

- Minimize shoaling at river crossings
- Safety



Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

FY 2018 Contract Brazos River Floodgates And Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



Brazos River Flood Gates and Colorado River Locks	Consolidated Repairs
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Structural and Building Components
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 23, 2018
Est. Completion Date:	January 19, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

FY 2019 Contract Brazos River Floodgates And Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



Brazos River Floodgates




Colorado River Locks

Brazos River Flood Gates and Colorado River Locks	Consolidated Repairs
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Miscellaneous Facility Items
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	3 rd Quarter FY19
Est. Completion Date:	1st Quarter FY20



Galveston District Mooring Basins



- Port Arthur
- Bolivar Peninsula
- Pelican Island
- Chocolate Bayou
- Brazos River Flood Gates
- Colorado River Locks
- Oyster Lake
- Channel to Victoria
- Aransas National Wildlife Refuge
- Arroyo Colorado

Mooring Buoy Update

GIWW

- Buoy Procurement
 - Twenty of 50 buoys from last Contract have been received and will be deployed in buoy re-spacing project. Anticipate the remaining 30 buoys delivered within the next 60-120 days
- Buoy Re-Spacing
 - USACE Wilmington District marine crew (*M/V Snell*) re-spacing and installing buoys at 5 priority basins: BRFG, CRL, Pelican Island, Bolivar Peninsula and Port Arthur. BRFG and CRL are complete.
 - M/V Snell and crew performing additional marine work within Galveston District boundaries
- Truston Buoy Repairs
 - Forensic investigation of buoys was performed at contractor's facility and resulted in problem identification
 - Contractor and USACE have determined a solution, design, and share in the cost for retrofitting the buoys such that they can be safely deployed
- Buoy Maintenance Service Contract
 - Task Orders awarded in August 2017 under a Blanket Purchase Agreement
 - React faster to buoy needs and provide for ability to address multiple basins concurrently



Brazos River Flood Gates Freeport, Texas



A total of 36 buoys have been re-spaced to 150' on center and installed at BRFG – 9 buoys per bank

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Colorado River Locks Matagorda, Texas



A total of 40 buoys have been re-spaced to 150' on center and installed at CRL – 10 buoys per bank



Brazos and Colorado Rivers

US Geological Survey Pile Clusters for Data Collection Platforms



Two six-pile clusters were installed for the USGS Data Collection Platforms (DCPs) in the Brazos and Colorado Rivers. A total of five, three-pile clusters were installed in front of the Brazos DCP to deflect debris travelling down river.



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Colorado River Locks Guidewall Repairs



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Brazos River Flood Gates Boathouse Dredging



Over 1,500 CY of dredged material (approximately 6' thick)
and 3 tons of debris were removed from the BRFG boathouse

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



US Fish and Wildlife Service Port O'Connor, Texas

A total of fifteen, 40' long pilings were installed at the USFWS boat basin after removing existing, deteriorated pilings



Questions Comments?



For more information, contact:

Eric Russek
Operations Manager

Project Operation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3007
eric.g.russek@usace.army.mil


Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



Navigation Project Facilities





Navigation Project Facilities



Brazos River Floodgates

- Minimize shoaling at river crossings
- Safety



Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

FY 2018 Contract Brazos River Floodgates And Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



Brazos River Flood Gates and Colorado River Locks	Consolidated Repairs
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Structural and Building Components
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 23, 2018
Est. Completion Date:	January 19, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

FY 2019 Contract Brazos River Floodgates And Colorado River Locks

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



Brazos River Floodgates




Colorado River Locks

Brazos River Flood Gates and Colorado River Locks	Consolidated Repairs
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Miscellaneous Facility Items
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	3 rd Quarter FY19
Est. Completion Date:	1st Quarter FY20



Galveston District Mooring Basins



- Port Arthur
- Bolivar Peninsula
- Pelican Island
- Chocolate Bayou
- Brazos River Flood Gates
- Colorado River Locks
- Oyster Lake
- Channel to Victoria
- Aransas National Wildlife Refuge
- Arroyo Colorado

Mooring Buoy Update

GIWW

- Buoy Procurement
 - Twenty of 50 buoys from last Contract have been received and will be deployed in buoy re-spacing project. Anticipate the remaining 30 buoys delivered within the next 60-120 days
- Buoy Re-Spacing
 - USACE Wilmington District marine crew (*M/V Snell*) re-spacing and installing buoys at 5 priority basins: BRFG, CRL, Pelican Island, Bolivar Peninsula and Port Arthur. BRFG and CRL are complete.
 - M/V Snell and crew performing additional marine work within Galveston District boundaries
- Truston Buoy Repairs
 - Forensic investigation of buoys was performed at contractor's facility and resulted in problem identification
 - Contractor and USACE have determined a solution, design, and share in the cost for retrofitting the buoys such that they can be safely deployed
- Buoy Maintenance Service Contract
 - Task Orders awarded in August 2017 under a Blanket Purchase Agreement
 - React faster to buoy needs and provide for ability to address multiple basins concurrently



Brazos River Flood Gates Freeport, Texas



A total of 36 buoys have been re-spaced to 150' on center and installed at BRFG – 9 buoys per bank

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Colorado River Locks Matagorda, Texas



A total of 40 buoys have been re-spaced to 150' on center and installed at CRL – 10 buoys per bank



Brazos and Colorado Rivers

US Geological Survey Pile Clusters for Data Collection Platforms



Two six-pile clusters were installed for the USGS Data Collection Platforms (DCPs) in the Brazos and Colorado Rivers. A total of five, three-pile clusters were installed in front of the Brazos DCP to deflect debris travelling down river.



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Colorado River Locks Guidewall Repairs



Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®

Brazos River Flood Gates Boathouse Dredging



Over 1,500 CY of dredged material (approximately 6' thick)
and 3 tons of debris were removed from the BRFG boathouse

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



US Fish and Wildlife Service Port O'Connor, Texas

A total of fifteen, 40' long pilings were installed at the USFWS boat basin after removing existing, deteriorated pilings



Questions Comments?



For more information, contact:

Eric Russek
Operations Manager

Project Operation Branch, Operations Division
U.S. Army Corps of Engineers, Galveston
409-766-3007
eric.g.russek@usace.army.mil

Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®