

UNITS LAND USE **ACRES** Single Family Lots

Beachside 2-Story Condos (Casicas)

DATE: 2/11/2008

45' Lots	270	31.81
55' Lots	291	43.14
65' Lots	602	116.98
80' Lots	176	45.33
Estate Lots	34	26.77

55' Lors	291	43.14
65' Lots	602	116.98
80' Lots	176	45.33
Escate Lots	34	26.77
Attached SF Units	1,148	64.30
Mid-Rise Candos	829	9,69
Tall Building	550	30.41

LAND USE	UNITS	ACRES
Commercial		5.90
Common Area/Parks		197.13
Preserve Area		360.75
Internal Right-of-Way		119.15
TOTAL	*3,948	1,053.01
Total Maximum Tall Building Hotel Units	800	

Marquette Galveston Investments Sheet 2 of 10

SWG-2007-01956 (Marina)

PERMITTING AGENT:

Environmental Services, Inc. 1507 S. IH-35; AUSTIN, TEXAS 78741 Ph; 512-328-2430

APPLICANT: MARQUETTE GALVESTON INVESTMENTS PROJECT NAME: THE MARINA AT WEST BEACH


COUNTY: GALVESTON COUNTY, TEXAS REV. DATE: 10/24/08


DATUM: N/A


1.65


SWG-2007-01956


SHEET 2 of 10

















EACH OF THESE ARE DISCUSSED BELOW

7. CONTINGENCY RESPONSE

D.O. MONITORING PLAN: PERMITEE WILL MONITOR D.O. TEMPERATURE AND SALINITY WITHIN THE MARINA BASIN AND ADJACENT AREAS AT THE LOCATIONS SHOWN, DURING THE WARM MONTHS OF - SEPT. MONITORING WILL BE DONE TWICE DAILY; 0.5 HOURS AFTER SUNRISE AND D.5 HOURS BEFORE SUNSET, STATIONS 1, 2, 4, AND 5 SHALL COMMENCE OPERATIONS SIX MONTHS PRIOR TO INITIATION OF EXCAVATION FOR THE MARINA AND SHALL CONTINUE FOR THREE YEARS AFTER EXCAVATION IS COMPLETE. STATION 3, (WHICH IS TO BE LOCATED WITHIN THE YET TO BE DREDGED

BASIN) SHALL BE INSTALLED WHEN THE MARINA BASIN IS APPROXIMATELY 90% DONE AND SHALL BE MAINTAINED FOR THREE YEARS AFTER COMPLETION ON THE BASIN. EXCAVATION PLAN: THE MARINA BASIN SHALL BE MECHANICALLY EXCAVATED WITH THE MATERIAL BEING PLACED ON ADJACENT UPLANDS WHERE IT WILL BE USED AS FILL BASIN EXCANTION SHALL BE COMPLETED BEFORE THE ACCESS AND CIRCULATION CHANNELS ARE BUILT. ONCE THE BASIN IS COMPLETE, THE ACCESS AND CIRCULATION AND CHANNELS SHALL BE MECHANICALLY EXCANATED WITH ALL MATERIAL BEING PLACED ON ADJACENT UPLANDS AND USED FOR FILL PERMITEE SHALL PROVIDE MONITORING RESULTS TO THE USACE WITHIN 15 WORKING DAYS. IF THE D.O. DROPS BELOW 4.0 PPM AT EITHER STATION 1, 2, OR 3 (AND THE REFERENCE STATIONS 4 AND 5 REMAIN ABOVE 4.0), THEN AERATION SHALL BE REQUIRED AS DESCRIBED BELOW, AERATION SHALL BE DONE AT TWO LOCATIONS

INDICATED: A AND 8 J. DIVERSION OF RUNOFF; ALL RUNOFF FROM ADJACENT DEVELOPED AREAS SHALL BE DIVERTED AWAY FROM THE MARINA BASIN

4. NO WASTEWATER DISCHARGE NO TREATED WASTEWATER FROM AN ENDPOINT SOURCE SHALL BE DISCHARGED INTO THE BASIN OR ACCESS CHANNELS. ALL WASTEWATER SHALL BE REMOVED FROM THE MARINA AREA AND DISPOSED OF VIA A TOEQ APPROVED WWTP.

OF ADVANCE MAINTENANCE DREDGING SHALL BE ALLOWED IN THE ACCESS CHANNEL 7. MECHANICAL AERATION SHALL BE DONE AT APPROXIMATE LOCATIONS A AND B. AIR RELEASE SHALL BE VIA A DIFFUSER LOCATED WITHIN I.D. FT. OF BOTTOM. SPECIFIC DESIGN SHALL BE COORDINATED WITH THE AGENCIES.

VESSELS, PRIVATE DOCKS, ETC.)

5. NO FISH CLEANING: THERE SHALL BE NO FISH CLEANING RESIDUE

DUMPED INTO THE MARINA FROM ANY SOURCE, (I.E. CLEANING STANDS,

6. MINIMUM DEPTH FOR PROJECTED VESSELS: THE BASIN AND APPROACH CHANNEL SHALL BE EXCAVATED TO THE MINIMUM DEPTH FOR THE

PROJECTED FLEET, WHICH IS ANTICIPATED TO BE -6'MLT ONE FOOT

Sheet 9 of 10

SWG-2007-01956 (Marina) Marquette Galveston Investments

APPLICANT: MARQUETTE GALVESTON INVESTMENTS PERMITTING AGENT: PROJECT NAME: THE MARINA AT WEST BEACH

Environmental Services, Inc. 1507 S. IH-35; AUSTIN, TEXAS 78741 Ph: 512-328-2430

COUNTY: GALVESTON COUNTY, TEXAS DATE: 2/11/2008 REV. DATE: 10/24/08 SWG-2007-01956 SHEET 9 of 10 DATUM: N/A

