

# FY18 Scheduled Contracts FY19 Planned Contracts

Christopher Frabotta  
Chief, Navigation Branch  
Galveston District  
U.S. Army Corps of Engineers  
31 OCT 2017

*“The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation.”*




**US Army Corps  
of Engineers**






# GALVESTON DISTRICT FACTS

- ✓ Texas #2 in Nation in Maritime Commerce
- ✓ Texas Ports moved 552M+ tons in 2015
- ✓ Galveston District Ports            National Rank
  - ✓ Houston                                    (2)
  - ✓ Beaumont                                 (5)
  - ✓ Corpus Christi                            (6)
  - ✓ Texas City                                 (15)
  - ✓ Port Arthur                               (19)
  - ✓ Freeport                                  (32)
  - ✓ Matagorda                                (46)
  - ✓ Galveston                                 (51)
  - ✓ Brownsville                              (66)
  - ✓ Victoria                                    (70)
- ✓ Gulf Intracoastal Waterway            (3)
- ✓ GIWW-TX 73M+ tons at \$43B in 2015
- ✓ >600M tons of Commercial Cargo
- ✓ 21.8% Nation's Total Tonnage
- ✓ 25.4% of Nation's Imports
- ✓ 28.6% of Nation's Exports



**Coastal Navigation:  
Value to the Nation**

**USACE Southwestern Division Regional Priority**



Texas is the number two state in the nation for **waterborne commerce**. Texas ports generate over \$5 billion in local and state tax revenue, and over \$9 billion in federal import tax revenue each year.

With the **Panama Canal Expansion** opening in 2017, ports must expand their capacity via land-and-waterside improvements to accept these ships. The **Texas** navigation system has **post-Panamax** projects ready for construction and studies are completed for deepening Port Freeport, Corpus Christi Ship Channel and the Sabine-Neches Waterway to depths that would allow post -Panamax ships to call.

**LEADING U.S. PORTS**  
(2015 Tonnage)

**Houston #2** - 240.9 million tons  
#1 Foreign Tonnage & #2 Total Tonnage

**Beaumont #5** - 87.2 m.tons  
#1 Military Port in World

**Gulf Intracoastal Waterway (79 million tons - Texas portion)**  
#3 Inland Waterway

**Corpus Christi #6** - 85.7 m.tons  
America's Energy Gateway

**Texas City #15** - 42.9 m.tons  
Services Largest Petrochemical Complex

**Port Arthur #19** - 35.8 m.tons  
Vital Break-Bulk Port


**Freeport #32** - 21.1 m.tons  
Connecting Global Services Via Caribbean Relay Port

**Matagorda to include Port of Port Lavaca and Port of Point Comfort #46** - 11.8 m. tons  
Generates Annual Business Revenues of Nearly \$2 Billion

**Galveston #51** - 10.4 m.tons  
#4 Cruise Ship Port

**Brownsville #66** - 7.7 m.tons  
#1 Ship Recycling Port

**Victoria (#70)** - 6.7 m.tons  
#2 Shallow-Draft Port for Domestic Crude Petroleum





# GALVESTON NAVIGATION OM FUNDING

## FY-17 Execution

President's Budget (less %1) \$106,737,000

FY-17 Allocation \$128,037,000

Carry-in \$ 13,727,000

Available to Obligate \$141,764,000

Obligated ~\$120,000,000

Percent Execution ~85%

## FY-18 Funding Outlook

President's Budget \$109,442,000

Carry-in \$ 13,727,000

Total Anticipated \$121,542,000





# FY-18 INITIATIVES

- **Continue Hydrographic Survey Webpage**
  - All six (6) Deep Draft Navigation Complexes & Gulf Intracoastal Waterway now online
  - <http://www.swg.usace.army.mil/Missions/Navigation.aspx>
- **Continue with TCOON Partnership with NOAA**
  - Add Matagorda Ship Channel current meter
- **Complete Re-Spacing & Deployment of new GIWW Mooring Buoys**
- **Construct non-Federal Placement Area Capacity**
  - Corpus Christi (PA-13)
  - Freeport Harbor (PA-1)
  - Sabine-Neches Waterway (PA-8)



# Operations Managers



## OPERATIONS MANAGERS

Belynda Kinman  
Tricia Campbell  
Aron Edwards  
Steve Howard  
Seth Jones  
Ashton Burgin  
Eric Russek



# Sabine-Neches Waterway

**Belynda Kinman**  
*Operations Manager*  
*Navigation Branch*  
31 October 2017

*Galveston District – Dredging Meeting*  
*Custodians of the Texas Coast*




®

US Army Corps of Engineers  
**BUILDING STRONG**®





# DEEP DRAFT FY18 CONTRACT SCHEDULES







# Sabine-Neches Waterway





# SABINE-NECHES WATERWAY – LOWER NECHES, PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU

1 of 2



<b>Project:</b>	Lower Neches, Port Arthur Canal, Turning Basin, Junction & Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 13 - 17
Distance to Place Area:	1 - 3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Start Date:	June 28, 2018
Est. Completion Date:	January 26, 2019





# SABINE-NECHES WATERWAY – LOWER NECHES, PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU

2 of 2



<b>Project:</b>	Lower Neches, Port Arthur Canal, Turning Basin, Junction & Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 8 and PA 9
Distance to Place Area:	1.5 - 2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Start Date:	June 28, 2018
Est. Completion Date:	January 26, 2019





# SABINE-NECHES WATERWAY OUTER BAR AND BANK CHANNEL



<b>Project:</b>	<b>Sabine Neches Waterway Outer Bar and Bank Channel</b>
Dredging Depth:	44 ft. Required Depth
Dredging Width:	800 ft.
Dredging Length:	Varies
Dredging Quantity:	3,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	Offshore
Distance to Placement Area:	3 Mile Avg.
Type of Equipment:	Hopper
Env. Window	NA
Reason for Window:	NA
Start Date:	July 11, 2018
Est. Completion Date:	November 10, 2018

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# SABINE-NECHES WATERWAY PLACEMENT AREA NO. 8 IMPROVEMENTS



<b>Project:</b>	Sabine Neches Waterway Placement Area No. 8 Improvements
Type of Work:	Containment Dike Raise
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	PA 8
Distance to Placement Area:	NA
Type of Equipment:	Excavators; Dozers; Marsh Buggy
Env. Window:	NA
Reason for Window:	NA
Start Date:	July 20, 2018
Est. Completion Date:	January 16, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# SHALLOW DRAFT – GIWW TRIBUTARIES CHOCOLATE BAYOU



US Army Corps  
of Engineers®  
Galveston District



**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# CHOCOLATE BAYOU




<b>Project:</b>	<b>Chocolate Bayou</b>
Dredging Depth:	15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	700,000 cubic yards
Material Type:	Silt/Sand
Placement Area:	BU / Upland Confined
Distance to Placement Area:	1.5 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	1 March – 31 August
Reason for Window:	Nesting birds at BU Site
Start Date:	June 11, 2018
Est. Completion Date:	February 6, 2019






# DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES







# SABINE-NECHES WATERWAY NECHES RIVER



<b>Project:</b>	<b>Sabine-Neches Waterway Neches River</b>
Dredging Depth:	42 ft. Required Depth
Dredging Width:	Varies
Dredging Length:	Varies
Dredging Quantity:	600,000 cubic yards
Material Type:	Silt
Placement Area:	Various Upland PAs
Distance to Placement Area:	1- 2 Miles
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	February 12, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# SABINE-NECHES WATERWAY PORT ARTHUR CANAL, TURNING BASIN, JUNCTION AREA AND TAYLORS BAYOU




<b>Project:</b>	Sabine-Neches Waterway Port Arthur Canal, Turning Basin, Junction Area and Taylors Bayou
Dredging Depth:	42 ft. Required Depth
Dredging Width:	400 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt/Clay
Placement Area:	PA 8 and PA 9
Distance to Place Area:	1.5 - 2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	September 10, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# Questions Comments?



For more information, contact:

**Belynda Kinman**  
Operations Manager

Navigation Branch, Operations Division  
U.S. Army Corps of Engineers, Galveston  
409-766-6323

[Belynda.m.kinman@usace.army.mil](mailto:Belynda.m.kinman@usace.army.mil)

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# Galveston Harbor and Channel & Houston Ship Channel

**Tricia Campbell, P.E.**  
*Operations Manager*  
*Navigation Branch*  
31 October 2017

***Galveston District – Dredging Meeting***  
***Custodians of the Texas Coast***




®

US Army Corps of Engineers  
**BUILDING STRONG**®





# DEEP DRAFT FY18 CONTRACT SCHEDULES






# HOUSTON SHIP CHANNEL – GALVESTON HARBOR TEXAS CITY SHIP CHANNEL



US Army Corps  
of Engineers®  
Galveston District




**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GALVESTON HARBOR




<b>Project:</b>	<b>Galveston Harbor Channel</b>
Dredging Depth:	41 - 46 ft. Required Depth
Dredging Width:	Varies
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt
Placement Area:	Offshore
Distance to Place Area:	8 Miles Avg.
Type of Equipment:	Hopper Dredge
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 9, 2018
Est. Completion Date:	December 28, 2018





# GALVESTON HARBOR – PELICAN ISLAND PLACEMENT AREA IMPROVEMENTS




<b>Project:</b>	<b>Galveston Harbor – Pelican Island Placement Area Improvements</b>
Type of Work:	Improvements
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Pelican Island
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019







# GALVESTON HARBOR – SAN JACINTO PLACEMENT AREA IMPROVEMENTS



<b>Project:</b>	<b>Galveston Harbor – San Jacinto Placement Area Improvements</b>
Type of Work:	Improvements
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	San Jacinto
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019





# HOUSTON SHIP CHANNEL – CARPENTERS BAYOU TO SIMS BAYOU EMERGENCY DREDGING



<b>Project:</b>	<b>Houston Ship Channel Carpenters Bayou to Sims Bayou Emergency Dredging</b>
<b>Dredging Depth:</b>	48 ft./43 ft. Required Depth
<b>Dredging Width:</b>	300 - 950 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	500,000 cubic yards
<b>Material Type:</b>	Silt
<b>Placement Area:</b>	Lost Lake & Rosa Allen
<b>Distance to Place Area:</b>	5 Miles
<b>Type of Equipment:</b>	Pipeline Dredge
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Est. Start Date:</b>	February 10, 2018
<b>Est. Completion Date:</b>	July 30, 2018


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL PLACEMENT AREA NO. 14 DEWATERING



<b>Project:</b>	<b>Houston Ship Channel Placement Area No. 14 Dewatering</b>
<b>Type of Work:</b>	Placement Area Dewatering
<b>Dredging Width:</b>	NA
<b>Dredging Length:</b>	NA
<b>Dredging Quantity:</b>	NA
<b>Material Type:</b>	
<b>Placement Area:</b>	PA 14
<b>Distance to Place Area:</b>	NA
<b>Type of Equipment:</b>	Marsh Buggy/Earthmoving Equipment
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Est. Start Date:</b>	August 31, 2018
<b>Est. Completion Date:</b>	February 27, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL – BAYPORT TO MORGANS AND BAYPORT



<b>Project:</b>	<b>Houston Ship Channel Bayport Flare and Bayport to Morgan's Point</b>
Dredging Depth:	48 ft. Required Depth
Dredging Width:	300 - 530 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Silt
Placement Area:	PA14 and 15; Marsh Cells
Distance to Place Area:	4 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	August 31, 2018
Est. Completion Date:	May 28, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL - PLACEMENT AREA NO. 15 SPILLBOX REPAIR & DEWATERING



Project:	Houston Ship Channel - Placement Area No. 15 Spillbox Repair & Dewatering
Type of Work:	Spillbox Repair/Dewatering
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	
Placement Area:	PA 15
Distance to Place Area:	NA
Type of Equipment:	Crane/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	October 11, 2018
Est. Completion Date:	April 9, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL – WEST CLINTON PLACEMENT AREA IMPROVEMENTS




<b>Project:</b>	<b>Houston Ship Channel West Clinton Improvements</b>
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	West Clinton
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	October 5, 2018
Est. Completion Date:	October 5, 2019





# HOUSTON SHIP CHANNEL MORGAN'S POINT TO EXXON




<b>Project:</b>	<b>Houston Ship Channel - Morgan's Point to Exxon</b>
Dredging Depth:	48 ft. Required Depth
Dredging Width:	530 – 600 ft.
Dredging Length:	Varies
Dredging Quantity:	1,400,000 cubic yards
Material Type:	Silt
Placement Area:	Alexander Island
Distance to Place Area:	3 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Est. Start Date:	October 26, 2018
Est. Completion Date:	July 23, 2019





# HOUSTON SHIP CHANNEL MID BAY PLACEMENT AREA IMPROVEMENTS



<b>Project:</b>	<b>Houston Ship Channel Mid Bay PA Improvements</b>
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Mid Bay
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	August 31-March 1 (open)
Reason for Window:	Migratory Birds
Est. Start Date:	November 3, 2018
Est. Completion Date:	August 30, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**





# HOUSTON SHIP CHANNEL LOST LAKE PA IMPROVEMENT



<b>Project:</b>	<b>Houston Ship Channel Lost Lake PA Improvements</b>
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	NA
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 12, 2018
Est. Completion Date:	November 7, 2019





# HOUSTON SHIP CHANNEL ALEXANDER ISLAND PA IMPROVEMENTS



<b>Project:</b>	<b>Houston Ship Channel Alexander Island Improvements</b>
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Alexander Island PA
Distance to Place Area:	NA
Type of Equipment:	Marsh Buggy/ Excavation Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	November 15, 2018
Est. Completion Date:	September 11, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**




# DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





# GALVESTON HARBOR - GALVESTON ENTRANCE CHANNEL AND HSC - BOLIVAR ROADS TO REDFISH



<b>Project:</b>	<b>Galveston Harbor - Galveston Entrance Channel and Houston Ship Channel - Bolivar Roads to Redfish</b>
Dredging Depth:	48 - 50 ft. Required Depth
Dredging Width:	530 – 1,000 ft.
Dredging Length:	17 miles
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand / Silt
Placement Area:	Offshore
Distance to Place Area:	1 - 15 Mile
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Award:	January 15, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL – PLACEMENT AREA NO. 14 & 15 DIKE RAISE




<b>Project:</b>	<b>Houston Ship Channel Placement Area No. 14 &amp; 15 Dike Raise</b>
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	
Placement Area:	PA 14 & 15
Distance to Place Area:	NA
Type of Equipment:	Crane/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	October 15, 2018





# HOUSTON SHIP CHANNEL – REDFISH TO BEACON 78 WITH BAYPORT FLARE



<b>Project:</b>	<b>Houston Ship Channel Redfish to Beacon 78 with Bayport Flare</b>
Dredging Depth:	48 ft. Required Depth
Dredging Width:	530 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand
Placement Area:	Offshore
Distance to Place Area:	Varies
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Award:	February 15, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL – BOGGY BAYOU TO GREENS BAYOU AND GREENS BAYOU




<b>Project:</b>	<b>Houston Ship Channel Boggy Bayou to Greens Bayou and Greens Bayou</b>
<b>Dredging Depth:</b>	38 - 43 ft. Required Depth
<b>Dredging Width:</b>	300 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	1,000,000 cubic yards
<b>Material Type:</b>	Silt
<b>Placement Area:</b>	Lost Lake/Clinton
<b>Distance to Place Area:</b>	5 Miles
<b>Type of Equipment:</b>	Pipeline
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Est. Start Date:</b>	March 15, 2019





# HOUSTON SHIP CHANNEL – EXXON TO BOGGY BAYOU AND JACINTOPORT



Project:	Houston Ship Channel Exxon to Boggy Bayou and Jacintoport
Dredging Depth:	48 ft. Required Depth
Dredging Width:	300 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Silt
Placement Area:	Lost Lake PA and Peggy Lake PA
Distance to Place Area:	3 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Award:	May 30, 2019







# HOUSTON SHIP CHANNEL – SIMS BAYOU TO TURNING BASIN AND LIGHT DRAFT CHANNEL




<b>Project:</b>	<b>Houston Ship Channel – Sims Bayou to Turning Basin and Light Draft Channel</b>
Dredging Depth:	HSC 39 ft. Required Depth Light Draft 11 ft. Required
Dredging Width:	530 – 1,000 ft.
Dredging Length:	17 miles
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Sand / Silt
Placement Area:	House Tract
Distance to Place Area:	7 Miles
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 30, 2019






# HOUSTON SHIP CHANNEL – SPILMAN ISLAND PA DEWATERING



<b>Project:</b>	<b>Houston Ship Channel Spilman Island PA Dewatering</b>
Type of Work:	Placement Area Dewatering
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Spilman Island
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	September 30, 2019



# Questions Comments?



For more information, contact:

**Tricia Campbell**  
**Operations Manager**

**Navigation Branch, Operations Division**  
**U.S. Army Corps of Engineers, Galveston**  
**409-766-3153**  
**[tricia.c.campbell@usace.army.mil](mailto:tricia.c.campbell@usace.army.mil)**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***



**BUILDING STRONG®**

# Freeport Harbor & Matagorda Ship Channel

**Aron Edwards**  
*Operations Manager*  
*Navigation Branch*  
*31 October 2017*

*Galveston District – Dredging Meeting*  
*Custodians of the Texas Coast*




®

US Army Corps of Engineers  
**BUILDING STRONG**®






# DEEP DRAFT FY18 CONTRACT SCHEDULES






# Freeport Harbor





# FREEPORT HARBOR PLACEMENT AREA #1 CONTAINMENT DIKE RAISE



<b>Project:</b>	<b>Freeport Harbor, TX Placement Area #1 Containment Dike Raise</b>
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Clay/Silt
Placement Area (PA):	PA 1
Distance to PA:	NA
Type of Equipment:	Dragline/Earthmoving Equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	January 1, 2018
Est. Completion Date:	January 12, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# FREEPORT HARBOR JETTY CHANNEL AND INSIDE CHANNEL



<b>Project:</b>	<b>Freeport Harbor Jetty Channel and Inside Channel</b>
Dredging Depth:	46 ft. Required Depth
Dredging Width:	280 - 1190 ft.
Dredging Length:	Varies
Dredging Quantity:	2,600,000 cubic yards
Material Type:	Clay/Silt
Placement Area:	Offshore
Distance to Place Area:	2.5 Mile Avg.
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 13, 2018
Est. Completion Date:	November 12, 2018

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**




**BUILDING STRONG®**





# Matagorda Ship Channel




Galveston District – Dredging Meeting - Custodians of the Texas Coast



BUILDING STRONG®



# MATAGORDA SHIP CHANNEL MATAGORDA PENINSULA TO POINT COMFORT



<b>Project:</b>	<b>Matagorda Ship Channel Matagorda Peninsula to Point Comfort</b>
Dredging Depth:	40 ft. Required Depth
Dredging Width:	200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open Water/Semi Confined
Distance to Place Area:	Varies
Type of Equipment:	Pipeline Dredge
Env. Window:	Sept 1 – Feb 28 (Open)
Reason for Window:	Nesting birds Sundown Is
Est. Start Date:	July 24, 2018
Est. Completion Date:	March 6, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





# FREEPORT HARBOR JETTY CHANNEL AND INSIDE CHANNEL



Project:	Freeport Harbor Jetty Channel and Inside Channel
Dredging Depth:	48-49 ft. Required Depth
Dredging Width:	280 - 1190 ft.
Dredging Length:	Varies
Dredging Quantity:	2,600,000 cubic yards
Material Type:	Clay/Silt
Placement Area:	Offshore
Distance to Place Area:	2.5 Mile Avg.
Type of Equipment:	Hopper
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	June 14, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# MATAGORDA SHIP CHANNEL MATAGORDA PENINSULA TO POINT COMFORT




<b>Project:</b>	Matagorda Ship Channel Matagorda Peninsula to Point Comfort
Dredging Depth:	40 ft. Required Depth
Dredging Width:	200 ft.
Dredging Length:	Varies
Dredging Quantity:	2,000,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open Water/Semi Confined
Distance to Place Area:	Varies
Type of Equipment:	Pipeline Dredge
Env. Window:	Sept 1 – Feb 28 (Open)
Reason for Window:	Nesting birds Sundown Is
Award:	September 16, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



**BUILDING STRONG®**

# Questions Comments?



For more information, contact:

**Aron Edwards**  
**Operations Manager**

**Navigation Branch, Operations Division**  
**U.S. Army Corps of Engineers, Galveston**  
**409-766-3028**  
**[aron.s.edwards@usace.army.mil](mailto:aron.s.edwards@usace.army.mil)**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***



**BUILDING STRONG®**

# Corpus Christi Ship Channel

**Steven Howard**  
*Operations Manager*  
*Navigation Branch*  
31 October 2017

*Galveston District – Dredging Meeting*  
*Custodians of the Texas Coast*




®

US Army Corps of Engineers  
**BUILDING STRONG**®






# DEEP DRAFT FY18 CONTRACT SCHEDULES








# Corpus Christi Ship Channel





# CORPUS CHRISTI SHIP CHANNEL INNER BASIN TO VIOLA T.B. & LA QUINTA CHANNEL




<b>Project:</b>	Corpus Christi Ship Channel Inner Basin to Viola Turning Basin / La Quinta Channel
Dredging Depth:	49-ft. Required Depth
Dredging Width:	300-400ft.
Dredging Length:	Varies
Dredging Quantity:	2,900,000 cubic yards
Material Type:	Silt / Sand
Placement Area:	Open Water and Upland
Distance to Placement Area:	1-4 Miles
Type of Equipment:	Pipeline Dredge
Env. Window	Sep. – Feb. (Open)
Reason for Window:	Nesting Birds PA 7-8
Start Date:	July 16, 2018
Est. Completion Date:	February 15, 2019





# CORPUS CHRISTI SHIP CHANNEL JETTY REPAIRS



<b>Project:</b>	Corpus Christi Ship Channel Jetty Repairs
Type of Work:	Jetty Repairs
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Distance to Placement Area:	NA
Type of Equipment:	Marine Construction
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 12, 2018
Est. Completion Date:	March 5, 2019





# CORPUS CHRISTI SHIP CHANNEL PLACEMENT AREA NO. 10 (PA 10) IMPROVEMENTS



<b>Project:</b>	Corpus Christi Ship Channel PA 10 Improvements
<b>Type of Work:</b>	Containment Dike
<b>Dredging Width:</b>	NA
<b>Dredging Length:</b>	NA
<b>Dredging Quantity:</b>	NA
<b>Material Type:</b>	NA
<b>Placement Area:</b>	PA 10
<b>Distance to Placement Area:</b>	NA
<b>Type of Equipment:</b>	Bull dozers; Excavators
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Est. Start Date:</b>	September 20, 2018
<b>Est. Completion Date:</b>	August 10, 2019


**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# CORPUS CHRISTI SHIP CHANNEL – SUNTIDE PLACEMENT AREA IMPROVEMENT




<b>Project:</b>	<b>CCSC - Suntide Placement Area Improvement</b>
Type of Work:	Levee
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	Suntide
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	September 15, 2018
Est. Completion Date:	March 16, 2019





# CHANNEL TO VICTORIA AND CHANNEL TO SEADRIFT




<b>Project:</b>	<b>GIWW, Ch to Victoria Lower Reach, Seadrift</b>
Dredging Depth:	16-ft Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Silt/Sand
Placement Area (PA):	Upland Confined
Distance to PA:	2.0 Mile (avg.)
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 30, 2018
Est. Completion Date:	November 16, 2018






# DEEP DRAFT FY19 PLANNED CONTRACT SCHEDULES





# CORPUS CHRISTI SHIP CHANNEL – TULE LAKE PLACEMENT AREA IMPROVEMENT



<b>Project:</b>	<b>CCSC – Tule Lake Placement Area Improvement</b>
Type of Work:	Containment Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	Tule Lake
Distance to Place Area:	NA
Type of Equipment:	Dragline/Earthmoving equipment
Env. Window:	NA
Reason for Window:	NA
Award:	April 15, 2019







# CORPUS CHRISTI SHIP CHANNEL INNER BASIN TO VIOLA




<b>Project:</b>	<b>Corpus Christi Ship Channel Inner Basin to Viola</b>
Dredging Depth:	49-ft. Required Depth
Dredging Width:	300-400ft.
Dredging Length:	Varies
Dredging Quantity:	2,500,000 cubic yards
Material Type:	Silt / Sand
Placement Area:	Open Water and Upland
Distance to Placement Area:	1-4 Miles
Type of Equipment:	Pipeline Dredge
Env. Window	Sep. – Feb. (Open)
Reason for Window:	Nesting Birds PA 7-8
Award:	August 15, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# Questions Comments?



For more information, contact:

**Steven Howard**

**Operations Manager**

**409-766-3026**

**[steven.b.howard@usace.army.mil](mailto:steven.b.howard@usace.army.mil)**

**Navigation Branch, Operations Division  
U.S. Army Corps of Engineers, Galveston**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***



**BUILDING STRONG®**

# Brazos Island Harbor (BIH) & Gulf Intracoastal Waterway

**Seth Jones**  
*Operation Manager*  
*Navigation Branch*  
*31 October 2017*

***Galveston District – Dredging Meeting***

***Custodians of the Texas Coast***




®

US Army Corps of Engineers  
**BUILDING STRONG**®





# DEEP DRAFT FY18 CONTRACT SCHEDULES






# Brazos Island Harbor (Brownsville Harbor)



US Army Corps  
of Engineers®  
Galveston District

## Brazos Island Harbor (BIH) Brownsville Ship Channel





# BRAZOS ISLAND HARBOR JETTY CHANNEL WITH BEACH PLACEMENT




<b>Project:</b>	<b>Brazos Island Harbor Brownsville Jetty Channel</b>
Dredging Depth:	46 ft. Required Depth
Dredging Width:	300 - 400 ft.
Dredging Length:	Varies
Dredging Quantity:	400,000 cubic yards
Material Type:	Sand
Placement Area:	Beach/BU
Distance to Place Area:	1-5 Miles Avg.
Type of Equipment:	Hopper/Pipeline
Env. Window:	1 Oct- 14Mar
Reason for Window:	Turtle/Tourism
Est. Start Date:	February 2, 2018; September 27, 2018
Est. Completion Date:	March 31, 2018 November 26, 2018





# DEEP DRAFT FY19 CONTRACT SCHEDULES





# BRAZOS ISLAND HARBOR MAIN CHANNEL



<b>Project:</b>	<b>Brazos Island Harbor Brownsville Ship Channel</b>
Dredging Depth:	44 ft. Required Depth
Dredging Width:	250 - 1200 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Silt
Placement Area:	Upland
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	June 12, 2019







# BRAZOS ISLAND HARBOR JETTY CHANNEL WITH BEACH PLACEMENT



<b>Project:</b>	<b>Brazos Island Harbor Brownsville Jetty Channel</b>
Dredging Depth:	46 ft. Required Depth
Dredging Width:	300 - 400 ft.
Dredging Length:	Varies
Dredging Quantity:	400,000 cubic yards
Material Type:	Sand
Placement Area:	Beach/BU
Distance to Place Area:	1-5 Miles Avg.
Type of Equipment:	Hopper/Pipeline
Env. Window:	1 Oct- 14Mar
Reason for Window:	Turtle/Tourism
Award:	September 17, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**




# SHALLOW DRAFT FY18 CONTRACT SCHEDULES



U.S. Army Corps  
of Engineers®  
Galveston District



## O&M Project Map Book GIWW - Galveston District GIWW Tributaries



Offatts Bayou

Chocolate Bayou

Colorado River (Channel to Bay City)

AO-N & AO-S boundary

Channel to Palacios

Victoria Barge Canal (Channel to Victoria)

Lydia Ann Channel to Port Aransas & Channel to Aransas Pass

Packery Channel

Channel to Port Mansfield


Arroyo Colorado (Channel to Harlingen)

Port Isabel small Boat Harbor & Side Channels

GULF OF MEXICO



# GULF INTRACOASTAL WATERWAY CHANNEL ACROSS ARANSAS BAY



<b>Project:</b>	<b>Gulf Intracoastal Waterway Channel Across Aransas Bay</b>
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,200,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open / BU
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	April thru Oct
Reason for Window:	Whooping Crane/Nesting Birds
Est. Start Date:	March 3, 2018
Est. Completion Date:	October 14, 2018

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY – FREEPORT TO CANEY CREEK, BRAZOS RIVER CROSSING



<b>Project:</b>	<b>Gulf Intracoastal Waterway Freeport to Caney Creek, Brazos River Crossing</b>
Dredging Depth:	13-15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	600,000 cubic yards
Material Type:	Sand/Silt
Placement Area:	Open / BU
Distance to Place Area:	1 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 29, 2018
Est. Completion Date:	September 29, 2018

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY PA 86 & 87 IMPROVEMENTS



<b>Project:</b>	<b>Gulf Intracoastal Waterway PA 86 &amp; 87 Containment Dike Raise</b>
Type of Work:	Dike Raising
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	Silt/Clay
Placement Area:	PA 86 & 87
Distance to Place Area:	NA
Type of Equipment:	Dragline
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	May 29, 2018
Est. Completion Date:	July 5, 2019



**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN




<b>Project:</b>	<b>Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen</b>
<b>Dredging Depth:</b>	14 ft. Required Depth
<b>Dredging Width:</b>	125 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	1,500,000 cubic yards
<b>Material Type:</b>	Fine Silt/Sand
<b>Placement Area:</b>	Open/BU Sites
<b>Distance to Placement Area:</b>	3 Miles Avg.
<b>Type of Equipment:</b>	Pipeline
<b>Env. Window:</b>	1 Nov. - 28 Feb.
<b>Reason for Window:</b>	Seagrass
<b>Est. Start Date:</b>	July 29, 2018
<b>Est. Completion Date:</b>	February 28, 2019





# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



<b>Project:</b>	<b>Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen</b>
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Est. Start Date:	July 29, 2018
Est. Completion Date:	February 28, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



<b>Project:</b>	<b>Channel to Harlingen</b>
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Upland
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Mar. – 31 Aug.
Reason for Window:	Nesting Birds
Est. Start Date:	July 29, 2018
Est. Completion Date:	February 28, 2019







# GULF INTRACOASTAL WATERWAY - ROLLOVER PASS TO GALVESTON CAUSEWAY & BOLIVAR FLARE



<b>Project:</b>	<b>Gulf Intracoastal Waterway Rollover to Causeway &amp; Bolivar Flare</b>
Dredging Depth:	15 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	800,000 cubic yards
Material Type:	Fine Sand/Silt
Placement Area:	Upland/Open Water/BU
Distance to Place Area:	2.0 Mile Avg.
Type of Equipment:	Pipeline
Env. Window:	N/A
Reason for Window:	N/A
Est. Start Date:	September 19, 2018
Est. Completion Date:	January 16, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**




# SHALLOW DRAFT FY19 PLANNED CONTRACT SCHEDULES



U.S. Army Corps  
of Engineers®  
Galveston District



## O&M Project Map Book GIWW - Galveston District GIWW Tributaries



GULF OF MEXICO



# GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING



<b>Project:</b>	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019

Galveston District – Dredging Meeting - Custodians of the Texas Coast



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING



<b>Project:</b>	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	14-16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	2 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019





# GULF INTRACOASTAL WATERWAY – CRANEY CREEK TO UPPER MATAGORDA BAY; BRAZOS RIVER CROSSING




<b>Project:</b>	Gulf Intracoastal Waterway Caney Creek to Upper Matagorda Bay; Brazos River Crossing
Dredging Depth:	16 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,000,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/Upland Confined
Distance to Placement Area:	1 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	NA
Reason for Window:	NA
Award:	March 1, 2019





# GULF INTRACOASTAL WATERWAY – ACROSS SAN ANTONIO BAY; MATAGORDA BAY TO CORPUS CHRISTI; MSC INTERSECTION



<b>Project:</b>	GIWW - Across San Antonio Bay / Matagorda Bay to Corpus Christi; GIWW / MSC Intersection
<b>Dredging Depth:</b>	14-16 ft. Required Depth
<b>Dredging Width:</b>	125 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	1,000,000 cubic yards
<b>Material Type:</b>	Fine Silt/Sand
<b>Placement Area:</b>	Open/Upland Confined/BU
<b>Distance to Placement Area:</b>	1 Miles Avg.
<b>Type of Equipment:</b>	Pipeline
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Award:</b>	March 19, 2019



**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN




<b>Project:</b>	<b>Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen</b>
<b>Dredging Depth:</b>	14 ft. Required Depth
<b>Dredging Width:</b>	125 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	1,500,000 cubic yards
<b>Material Type:</b>	Fine Silt/Sand
<b>Placement Area:</b>	Open/BU Sites
<b>Distance to Placement Area:</b>	3 Miles Avg.
<b>Type of Equipment:</b>	Pipeline
<b>Env. Window:</b>	1 Nov. - 28 Feb.
<b>Reason for Window:</b>	Seagrass
<b>Award:</b>	August 15, 2019





# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



<b>Project:</b>	<b>Gulf Intracoastal Waterway Corpus Christi to Port Isabel/ Channel to Harlingen</b>
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Open/BU Sites
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Nov. - 28 Feb.
Reason for Window:	Seagrass
Award:	August 15, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**





# GULF INTRACOASTAL WATERWAY CORPUS CHRISTI TO PORT ISABEL/ CHANNEL TO HARLINGEN



<b>Project:</b>	<b>Channel to Harlingen</b>
Dredging Depth:	14 ft. Required Depth
Dredging Width:	125 ft.
Dredging Length:	Varies
Dredging Quantity:	1,500,000 cubic yards
Material Type:	Fine Silt/Sand
Placement Area:	Upland
Distance to Placement Area:	3 Miles Avg.
Type of Equipment:	Pipeline
Env. Window:	1 Mar. – 31 Aug.
Reason for Window:	Nesting Birds
Award:	August 15, 2019






# GULF INTRACOASTAL WATERWAY – HIGH ISLAND TO ROLLOVER; BOLIVAR FLARE; CHANNEL TO PORT BOLIVAR



<b>Project:</b>	GIWW - High Island to Rollover; Bolivar Flare; Channel to Port Bolivar
<b>Dredging Depth:</b>	15 ft. Required Depth
<b>Dredging Width:</b>	125 ft.
<b>Dredging Length:</b>	Varies
<b>Dredging Quantity:</b>	800,000 cubic yards
<b>Material Type:</b>	Fine Silt/Sand
<b>Placement Area:</b>	Open/Upland Confined/BU
<b>Distance to Placement Area:</b>	1 Miles Avg.
<b>Type of Equipment:</b>	Pipeline
<b>Env. Window:</b>	NA
<b>Reason for Window:</b>	NA
<b>Award:</b>	September 17, 2019



# Questions Comments?



For more information, contact:

**Seth Jones**  
Operations Manager

Navigation Branch, Operations Division  
U.S. Army Corps of Engineers, Galveston  
409-766-3068  
[Seth.w.jones@usace.army.mil](mailto:Seth.w.jones@usace.army.mil)

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# Cedar Bayou

**Ashton Burgin**  
*Operations Manager*  
*Navigation Branch*  
31 October 2017

***Galveston District – Dredging Meeting***  
***Custodians of the Texas Coast***



US Army Corps of Engineers  
**BUILDING STRONG**<sup>®</sup>





# SHALLOW DRAFT TRIBUTARIES FY18 CONTRACT SCHEDULE



US Army Corps  
of Engineers  
Galveston District



**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**



# HOUSTON SHIP CHANNEL TRIBUTARIES CEDAR BAYOU



**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**




# CEDAR BAYOU



<b>Project:</b>	<b>Cedar Bayou</b>
Dredging Depth:	12 ft. Required Depth
Dredging Width:	100 ft.
Dredging Length:	Varies
Dredging Quantity:	680,000 cubic yards
Material Type:	Silt/Sand
Placement Area:	Open water
Distance to Placement Area:	4 Mile Avg.
Type of Equipment:	Pipeline Dredge
Env. Window:	NA
Reason for Window:	NA
Start Date:	November 1, 2018
Est. Completion Date:	February 12, 2019



# Questions Comments?



For more information, contact:

**Ashton Burgin**  
**Operations Manager**

**Navigation Branch, Operations Division**  
**U.S. Army Corps of Engineers, Galveston**  
**409-766-3958**  
**[ashton.burgin@usace.army.mil](mailto:ashton.burgin@usace.army.mil)**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***



**BUILDING STRONG®**



# Brazos River Floodgates, Colorado River Locks & Mooring Buoy Maintenance

**Eric Russek, P.E.**

*Operations Manager*

*Project Operations Br, Galveston*

*31 October 2017*

***Galveston District – Dredging Meeting***

***Custodians of the Texas Coast***




®

US Army Corps of Engineers  
**BUILDING STRONG**®





# Navigation Project Facilities





# Navigation Project Facilities



- **Minimize shoaling at river crossings**
- **Safety**



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# **FY 2018 Contract Brazos River Floodgates And Colorado River Locks**

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



<b>Brazos River Flood Gates and Colorado River Locks</b>	<b>Consolidated Repairs</b>
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Structural and Building Components
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 23, 2018
Est. Completion Date:	January 19, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# **FY 2019 Contract Brazos River Floodgates And Colorado River Locks**

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



**Brazos River Floodgates**



**Colorado River Locks**


<b>Brazos River Flood Gates and Colorado River Locks</b>	<b>Consolidated Repairs</b>
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Miscellaneous Facility Items
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	3 <sup>rd</sup> Quarter FY19
Est. Completion Date:	1st Quarter FY20

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# Galveston District Mooring Basins



- Port Arthur
- Bolivar Peninsula
- Pelican Island
- Chocolate Bayou
- Brazos River Flood Gates
- Colorado River Locks
- Oyster Lake
- Channel to Victoria
- Aransas National Wildlife Refuge
- Arroyo Colorado



# Mooring Buoy Update

## GIWW

- Buoy Procurement
  - Twenty of 50 buoys from last Contract have been received and will be deployed in buoy re-spacing project. Anticipate the remaining 30 buoys delivered within the next 60-120 days
- Buoy Re-Spacing
  - USACE Wilmington District marine crew (*M/V Snell*) re-spacing and installing buoys at 5 priority basins: BRFG, CRL, Pelican Island, Bolivar Peninsula and Port Arthur. BRFG and CRL are complete.
  - M/V Snell and crew performing additional marine work within Galveston District boundaries
- Truston Buoy Repairs
  - Forensic investigation of buoys was performed at contractor's facility and resulted in problem identification
  - Contractor and USACE have determined a solution, design, and share in the cost for retrofitting the buoys such that they can be safely deployed
- Buoy Maintenance Service Contract
  - Task Orders awarded in August 2017 under a Blanket Purchase Agreement
  - React faster to buoy needs and provide for ability to address multiple basins concurrently



# Brazos River Flood Gates Freeport, Texas



A total of 36 buoys have been re-spaced to 150' on center and installed at BRFG – 9 buoys per bank

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Colorado River Locks Matagorda, Texas



A total of 40 buoys have been re-spaced to 150' on center and installed at CRL – 10 buoys per bank



# Brazos and Colorado Rivers

## US Geological Survey Pile Clusters for Data Collection Platforms



Two six-pile clusters were installed for the USGS Data Collection Platforms (DCPs) in the Brazos and Colorado Rivers. A total of five, three-pile clusters were installed in front of the Brazos DCP to deflect debris travelling down river.



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Colorado River Locks Guidewall Repairs



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Brazos River Flood Gates Boathouse Dredging



Over 1,500 CY of dredged material (approximately 6' thick)  
and 3 tons of debris were removed from the BRFG boathouse

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**



# US Fish and Wildlife Service Port O'Connor, Texas

A total of fifteen, 40' long pilings were installed at the USFWS boat basin after removing existing, deteriorated pilings



# Questions Comments?



For more information, contact:

**Eric Russek**  
Operations Manager

**Project Operation Branch, Operations Division**  
**U.S. Army Corps of Engineers, Galveston**  
**409-766-3007**  
**[eric.g.russek@usace.army.mil](mailto:eric.g.russek@usace.army.mil)**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***




**BUILDING STRONG®**





# Navigation Project Facilities





# Navigation Project Facilities



- **Minimize shoaling at river crossings**
- **Safety**



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# **FY 2018 Contract Brazos River Floodgates And Colorado River Locks**

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



<b>Brazos River Flood Gates and Colorado River Locks</b>	<b>Consolidated Repairs</b>
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Structural and Building Components
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	July 23, 2018
Est. Completion Date:	January 19, 2019

**Galveston District – Dredging Meeting - Custodians of the Texas Coast**



**BUILDING STRONG®**

# **FY 2019 Contract Brazos River Floodgates And Colorado River Locks**

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*




**BUILDING STRONG®**



# GULF INTRACOASTAL WATERWAY BRFG & CRL Consolidated Repairs



**Brazos River Floodgates**




**Colorado River Locks**

<b>Brazos River Flood Gates and Colorado River Locks</b>	<b>Consolidated Repairs</b>
Dredging Depth:	NA
Dredging Width:	NA
Dredging Length:	NA
Dredging Quantity:	NA
Material Type:	NA
Placement Area:	NA
Type of Equipment:	Miscellaneous Facility Items
Env. Window:	NA
Reason for Window:	NA
Est. Start Date:	3 <sup>rd</sup> Quarter FY19
Est. Completion Date:	1st Quarter FY20



# Galveston District Mooring Basins



- Port Arthur
- Bolivar Peninsula
- Pelican Island
- Chocolate Bayou
- Brazos River Flood Gates
- Colorado River Locks
- Oyster Lake
- Channel to Victoria
- Aransas National Wildlife Refuge
- Arroyo Colorado

# Mooring Buoy Update

## GIWW

- Buoy Procurement
  - Twenty of 50 buoys from last Contract have been received and will be deployed in buoy re-spacing project. Anticipate the remaining 30 buoys delivered within the next 60-120 days
- Buoy Re-Spacing
  - USACE Wilmington District marine crew (*M/V Snell*) re-spacing and installing buoys at 5 priority basins: BRFG, CRL, Pelican Island, Bolivar Peninsula and Port Arthur. BRFG and CRL are complete.
  - M/V Snell and crew performing additional marine work within Galveston District boundaries
- Truston Buoy Repairs
  - Forensic investigation of buoys was performed at contractor's facility and resulted in problem identification
  - Contractor and USACE have determined a solution, design, and share in the cost for retrofitting the buoys such that they can be safely deployed
- Buoy Maintenance Service Contract
  - Task Orders awarded in August 2017 under a Blanket Purchase Agreement
  - React faster to buoy needs and provide for ability to address multiple basins concurrently





# Brazos River Flood Gates Freeport, Texas



A total of 36 buoys have been re-spaced to 150' on center and installed at BRFG – 9 buoys per bank

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Colorado River Locks Matagorda, Texas



A total of 40 buoys have been re-spaced to 150' on center and installed at CRL – 10 buoys per bank



# Brazos and Colorado Rivers

## US Geological Survey Pile Clusters for Data Collection Platforms



Two six-pile clusters were installed for the USGS Data Collection Platforms (DCPs) in the Brazos and Colorado Rivers. A total of five, three-pile clusters were installed in front of the Brazos DCP to deflect debris travelling down river.



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Colorado River Locks Guidewall Repairs



*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**

# Brazos River Flood Gates Boathouse Dredging



Over 1,500 CY of dredged material (approximately 6' thick)  
and 3 tons of debris were removed from the BRFG boathouse

*Galveston District – Dredging Meeting - Custodians of the Texas Coast*



**BUILDING STRONG®**




# US Fish and Wildlife Service Port O'Connor, Texas

A total of fifteen, 40' long pilings were installed at the USFWS boat basin after removing existing, deteriorated pilings



# Questions Comments?



For more information, contact:

**Eric Russek**  
Operations Manager

**Project Operation Branch, Operations Division**  
**U.S. Army Corps of Engineers, Galveston**  
**409-766-3007**  
**[eric.g.russek@usace.army.mil](mailto:eric.g.russek@usace.army.mil)**

***Galveston District – Dredging Meeting - Custodians of the Texas Coast***



**BUILDING STRONG®**