



U.S. Army Corps
of Engineers
Galveston District

**ADDICKS AND BARKER RESERVOIRS
BUFFALO BAYOU AND TRIBUTARIES
SAN JACINTO RIVER BASIN, TX**

WATER CONTROL MANUAL

NOVEMBER 2012


ADDICKS AND BARKER RESERVOIRS
BUFFALO BAYOU AND TRIBUTARIES
SAN JACINTO RIVER BASIN, TEXAS

WATER CONTROL MANUAL
SAN JACINTO RIVER BASIN
PREVIOUS EDITION – APRIL 1962
REVISED EDITION - NOVEMBER 2012

Department of the Army
Corps of Engineers
Galveston District



ADDICKS RESERVOIR – OUTLET WORKS



BARKER RESERVOIR – AERIAL VIEW



BARKER RESERVOIR – OUTLET WORKS

NOTICE TO USERS OF THIS MANUAL

Regulations specify that this Water Control Manual be used in looseleaf form, and only those sections, or parts thereof, requiring changes will be revised and printed. Therefore, this copy should be preserved in good condition so that inserts can be made to keep the manual current. Changes to individual pages must carry the date of revision, which is Division's approval date. All elevations referred to in this manual, unless noted otherwise, are in feet, NAVD 1988 (North American Vertical Datum 1988, Epoch 2001)

EMERGENCY REGULATION ASSISTANCE PROCEDURES

In the event that unusual conditions arise during duty hours and at various hours during weekends and holidays, contact can be made by telephone to the Hydrology/Water Control (H&H/WC) Branch, Galveston District Office, at (409) 766-3113. If the above office cannot be contacted, assistance can be achieved by contacting, in the order listed, one of the persons shown below. Chapter 7 of this manual contains detailed instructions for emergency regulation. All project personnel associated with regulation of the projects must be thoroughly familiar with this and the procedure outlined in Exhibit B.

EMERGENCY PERSONNEL ROSTER

ADDICKS FIELD OFFICE PHONE NUMBERS	
Addicks Field Office Main Line	281-497-0740
Addicks Field Office Fax Line	281-497-0864

SWG		OFFICE	HOME
WATER CONTROL			
	[REDACTED]	[REDACTED]	[REDACTED]
	[REDACTED]	[REDACTED]	[REDACTED]
OPERATIONS DIVISION			
	[REDACTED]	[REDACTED]	[REDACTED]
	[REDACTED]	[REDACTED]	[REDACTED]
	[REDACTED]	[REDACTED]	[REDACTED]
DAM SAFETY			
	[REDACTED]	[REDACTED]	[REDACTED]
	[REDACTED]	[REDACTED]	[REDACTED]
EMERGENCY OPERATIONS			
	Emergency Operations Center		409-762-6300
	[REDACTED]	[REDACTED]	[REDACTED]

TABLE OF CONTENTS

Addicks and Barker Reservoirs
Water Control Manual
Buffalo Bayou and Tributaries
San Jacinto River Basin, Texas

TITLE PAGE.....	i
PHOTOGRAPHS.....	ii
NOTICE TO USERS OF THIS MANUAL.....	vi
EMERGENCY REGULATION ASSISTANCE PROCEDURES	vii
TABLE OF CONTENTS.....	viii
PERTINENT DATA.....	xiv

I - Introduction

1-01. Authorization.....	1-1
1-02. Purpose and Scope	1-1
1-03. Related Manuals and Reports	1-1
1-04. Project Owner	1-1
1-05. Operating Agency	1-1
1-06. Regulating Agencies	1-2

II - Description of Project

2-01. Location	2-1
2-02. Purpose	2-1
2-03. Physical Components	2-1
a. Addicks Dam	2-1
b. Addicks Outlet Works.....	2-1
c. Barker Dam.....	2-2
d. Barker Outlet Works.....	2-2
2-04. Related Control Facilities	2-2
2-05. Real Estate Acquisition	2-2
2-06. Public Facilities	2-2

III - History of Project

3-01. Authorization.....	3-1
3-02. Planning and Design.....	3-1
3-03. Construction.....	3-1
3-04. Related Projects	3-2
3-05. Modifications to Regulations	3-3
3-06. Principal Regulation Problems	3-5

TABLE OF CONTENTS

IV - Watershed Characteristics

4-01.	General Characteristics	4-1
a.	Buffalo Bayou Watershed	4-1
b.	Barker Reservoir Watershed	4-1
c.	Addicks Reservoir Watershed	4-1
d.	Cypress Creek Watershed	4-1
4-02.	Topography	4-1
4-03.	Geology and Soils	4-1
a.	Addicks Dam	4-2
b.	Barker Dam	4-3
c.	Groundwater Conditions	4-4
d.	Subsidence	4-4
4-04.	Sediment	4-4
4-05.	Climate	4-5
a.	General	4-5
b.	Temperature	4-5
c.	Precipitation	4-5
d.	Evaporation	4-6
e.	Wind	4-6
4-06.	Storms and Floods	4-6
4-07.	Runoff Characteristics	4-7
4-08.	Water Quality	4-7
4-09.	Channel and Floodway Characteristics	4-7
4-10.	Upstream Structures	4-8
4-11.	Downstream Structures	4-8
4-12.	Economic Data	4-8
a.	Population	4-8
b.	Agriculture	4-8
c.	Industry	4-8
d.	Recreation	4-8
e.	Flood Damages	4-9

V - Data Collection and Communication Network

5-01.	Hydrometeorological Stations	5-1
a.	Facilities	5-1
b.	Reporting	5-2
c.	Maintenance	5-2
5-02.	Water Quality Stations	5-3
a.	Facilities	5-3
5-03.	Sediment Stations	5-3
5-04.	Recording Hydrologic Data	5-3

TABLE OF CONTENTS

a.	Project Data	5-3
b.	Stream Gage Data	5-4
c.	Precipitation Data	5-4
5-05.	Communication Network	5-4
5-06.	Communication with Project	5-4
a.	Regulating Office with Project Office	5-4
b.	Between Project Office and Others	5-4
5-07.	Project Reporting Instructions	5-5
5-08.	Warnings	5-5
a.	Local Warnings	5-5
b.	Flood Emergency Plan	5-6
5.09.	Routine Information for Public Release	5-6

VI - Hydrologic Forecasts

6-01.	General	6-1
a.	Role of the Corps	6-1
b.	Role of Other Agencies	6-1
6-02.	Flood Condition Forecasts	6-2
a.	Requirements	6-2
b.	Methods	6-2
6-03.	Long-Range Forecasts	6-3
6-04.	Drought Forecast	6-3

VII - Water Control Plan

7-01.	General Objectives	7-1
7-02.	Constraints	7-1
a.	Spillway Design Flood Impacts	7-1
b.	Upstream Reservoir Impacts	7-1
c.	Reservoir Release Restrictions	7-2
7-03.	Overall Plan for Water Control	7-2
7-04.	Standing Instructions to Dam Tender	7-2
a.	Normal Operation	7-2
b.	Emergency Operations	7-3
7-05.	Flood Control	7-4
a.	Normal Flood Control Regulation	7-4
b.	Induced Surcharge Flood Control Regulation	7-5
c.	Constraints Regarding Flood Control Operation	7-5
7-06.	Recreation	7-5
a.	Land Usage	7-5
b.	Reservoir Regulation For Special Events	7-6
7-07.	Water Quality	7-6
7-08.	Fish and Wildlife	7-6

TABLE OF CONTENTS

7-09. Water Supply	7-6
7-10. Hydroelectric Power	7-6
7-11. Navigation	7-7
7-12. Drought Contingency Plans.....	7-7
7-13. Flood Emergency Action Plan	7-7
7-14. Other	7-7
7-15. Deviation from Normal Regulation.....	7-7
a. Emergencies.....	7-7
b. Unplanned Minor Deviations.....	7-8
c. Planned Deviations	7-8
d. Unplanned Major Deviations.....	7-8
7-16. Rate of Release Change	7-8
7-17. Operation Curves and Tables.....	7-9

VIII - Effect of Water Control Plan

8-01. General.....	8-1
8-02. Flood Control.....	8-1
a. Spillway Design Flood.....	8-1
b. Standard Project Flood	8-2
c. Other Floods	8-3
8-03. Recreation	8-4
8-04. Water Quality.....	8-4
8-05. Fish and Wildlife	8-4
8-06. Water Supply.....	8-4
8-07. Hydroelectric Power	8-5
8-08. Navigation	8-5
8-09. Drought Contingency Plans.....	8-5
8-10. Flood Emergency Action Plans	8-5
8-11. Frequencies.....	8-5
a. Peak Inflow Probability.....	8-5
b. Pool Elevation Duration and Frequency.....	8-6
c. Key Control Points	8-6
8-12. Other Studies	8-6
a. Examples of Regulation	8-6
b. Channel and Floodway Improvement	8-6

IX - Water Control Management

9-01. Responsibilities and Organization.....	9-1
a. Corps of Engineers	9-1
b. Other Federal Agencies	9-1
c. State and County Agencies.....	9-1

TABLE OF CONTENTS

d.	Private Organizations	9-2
9-02.	Interagency Coordination	9-2
a.	National Weather Service	9-2
b.	U.S. Geological Survey	9-2
9-03.	Interagency Agreements	9-2
9-04.	Commissions, River Authorities, Compacts and Committees	9-2
9-05.	Non-Federal Hydropower	9-2
9-06.	Reports	9-2
a.	Daily Reservoir Report	9-2
b.	Monthly Reservoir Report	9-2
c.	Flood Damage Report	9-3
d.	Post Flood Report	9-3
e.	Annual Report	9-3
f.	Summary of Reports	9-3

TABLE INDEX

<u>Table</u>	<u>Title</u>	<u>Page</u>
1-01	Pertinent Manuals and Reports for Addicks and Barker Reservoirs	1-2
3-01	History of Construction Activities	3-2
4-01	Temperature Data	4-5
4-02	Average Monthly and Annual Rainfall	4-6
4-03	Average Inflow Volumes at Addicks and Barker Reservoirs	4-7
4-04	Population of Counties in the Vicinity of Addicks and Barker Reservoirs	4-8
4-05	Damages Prevented by Addicks and Barker Reservoirs	4-10
5-01	Stream Gaging Stations Pertinent to Addicks and Barker Reservoirs	5-1
8-01	Addicks Reservoir - Other Significant Flood Events	8-3
8-02	Barker Reservoir - Other Significant Flood Events	8-4
8-03	Rainfall Frequency and Peak Inflow	8-6
9-01	Tabulation of Reports	9-4

SUPPLEMENTARY TABLES

<u>Table</u>	<u>Title</u>	<u>Page</u>
7-01	Elevation-Area/Capacity Table - Addicks Reservoir	T7-01-1
7-02	Elevation-Area/Capacity Table - Barker Reservoir	T7-02-1

EXHIBIT INDEX

- EXHIBIT A: Supplementary Pertinent Data
 EXHIBIT B: Standing Instructions to Dam Tender

TABLE OF CONTENTS

PLATE INDEX

<u>Plate</u>	<u>Title</u>
2-01	Vicinity Map
2-02	Addicks Reservoir Vicinity Map
2-03	Barker Reservoir Vicinity Map
2-04	Dam and Spillway Typical Sections – Addicks Reservoir
2-05	Dam and Spillway Typical Sections – Barker Reservoir
2-06	Outlet Works Plan and Profile - Addicks Reservoir
2-07	Outlet Works Plan and Profile - Barker Reservoir
2-08	Public Facilities – Addicks Reservoir
2-09	Public Facilities – Barker Reservoir
3-01	Water Surface Profiles and Floor Elevations Buffalo Bayou
3-02	Water Surface Profiles and Floor Elevations Buffalo Bayou
4-01	Drainage Area Map
4-02	Discharge Rating Curve - Buffalo Bayou at Piney Point, TX
5-01	Stream Gage Locations
5-02	Inundation Maps
5-03	Inundation Maps
5-04	Inundation Maps
5-05	Inundation Maps
5-06	Inundation Maps
5-07	Inundation Maps
5-08	Inundation Maps
5-09	Inundation Maps
7-01	Area-Capacity Curves - Addicks Reservoir
7-02	Area-Capacity Curves - Barker Reservoir
7-03	Induced Surcharge Operation Schedule - Addicks Reservoir
7-04	Induced Surcharge Operation Schedule - Barker Reservoir
7-05	Outlet Works Rating Curves - Addicks Reservoir
7-06	Outlet Works Rating Curves - Barker Reservoir
8-01	Spillway Design Flood - Addicks Reservoir 1977
8-02	Spillway Design Flood - Barker Reservoir 1977
8-03	Standard Project Flood - Addicks Reservoir 1977
8-04	Standard Project Flood - Barker Reservoir 1977
8-05	Pool Elevation-Frequency Curve - Addicks Reservoir
8-06	Pool Elevation-Frequency Curve - Barker Reservoir
8-07	Pool Elevation-Duration Curve - Addicks Reservoir
8-08	Pool Elevation-Duration Curve - Barker Reservoir
9-01	Organization and Communication Chart for Water Management

PERTINENT DATA
ADDICKS AND BARKER RESERVOIRS

ITEM	ADDICKS RESERVOIR	BARKER RESERVOIR		
DRAINAGE AREA	136 square miles	130 square miles		
DAMS				
Type	Rolled earth embankment	Rolled earth embankment		
Length	61,166 feet	71,900 feet		
Height (above stream bed)	48.5 feet	36.5 feet		
RESERVOIR	<u>Elevation</u> <u>feet (NGVD) (1)</u>	<u>Storage</u> <u>Capacity</u> <u>acre-feet</u>	<u>Elevation</u> <u>feet (NGVD) (1)</u>	<u>Storage</u> <u>Capacity</u> <u>acre-feet</u>
Conduit Invert	67.5	0	70.2	0
Limits of Government Land	103.0	127,591	95.0	82,921
100-Year Flood	100.3	94,500	97.0	107, 489
Standard Project Flood	107.6	193,956	98.3	125,061
Natural ground at end of dam	108.0	199,643	104.0	209,600
Top of dam	121.0	-	113.1	-
CONDUITS	5 gated concrete box culvert conduits, 8' wide x 6' high x 252' long each		5 gated concrete box culvert conduits, 9' wide x 7' high x 190.5' long each	
STILLING BASIN	43.5' convex spillway; 40' long 60' wide longitudinal stilling basin; 150' of rip-rap lined outlet channel		55.5' convex spillway; 50' long 60' wide longitudinal stilling basin; 160' of rip-rap lined outlet channel	

(1) Elevations based on North American Vertical Datum 1988 Epoch 2001

I - INTRODUCTION

1-01. Authorization. This manual is submitted as required by ER 1110-2-240 "Water Control Management", 8 October 1982; and prepared in accordance with EM 1110-2-3600 "Management of Water Control Systems", 30 November 1997 and EM 1110-2-8156 "Preparation of Water Control Manuals", 31 August 1995.

1-02. Purpose and Scope. The purpose of this manual is to document the Addicks and Barker Reservoir regulation plans, to present detailed information to higher authority, and to give guidance to personnel concerned with or responsible for the regulation of Addicks and Barker Reservoirs during the life of the projects. This manual includes data and information pertinent to the regulation of Addicks and Barker Reservoirs.

This manual consolidates the regulatory conditions published in "Hydrology, Buffalo Bayou and Tributaries, Texas, Addicks and Barker Reservoirs, August 1977" with Reservoir Regulation Schedules published in "Reservoir Regulation Manual for Addicks and Barker Reservoirs, April 1962". The reference vertical datum for the Reservoir Regulation Schedules and Dam project features has been updated to NAVD 1988 Epoch 2001. Additional pertinent manuals and reports are also incorporated into this manual, and are listed in Table 1-01.

1-03. Related Manuals and Reports. Reports and manuals pertinent to Addicks and Barker Reservoirs are listed in Table 1-01.

1-04. Project Owner. Addicks and Barker Reservoirs are owned by the United States Government.

1-05. Operating Agency. The U.S. Army Corps of Engineers is the operating agency for Addicks and Barker Reservoirs. The Project Operations Branch, Galveston District office has the responsibility for operation of Addicks and Barker Reservoirs. The Dam Tender (Acting Natural Resource Manager) for Addicks and Barker Reservoirs has the responsibility for the specific operations of Addicks and Barker Reservoirs. The project is manned and operated from 0730 hours to 1600 hours on weekdays throughout the year, and manned operation can vary up to 24 hours a day depending on the status of the reservoirs. 24-hr manned operation of Addicks Reservoir begins when the pool elevation reaches 99.9 feet NAVD 1988. 24-hr manned operation of Barker Reservoir begins when the pool elevation reaches 94.7 feet NAVD 1988. The operators work under the supervision of the Dam Tender. Gate operations are manually controlled by the operator from the outlet structures using electrically controlled sluice gates. The Hydrology and Hydraulics/Water Control (H&H/WC) Branch is responsible for regulating the conduit gates. The Dam Tender provides the Chief, Hydrology and Hydraulics/Water Control (H&H/WC) Branch an updated list of project operations

personnel, giving their office and home telephone numbers and addresses.

1-06. Regulating Agencies. The U.S. Army Corps of Engineers is the regulating agency for Addicks and Barker Reservoirs. The Hydrology and Hydraulics/Water Control (H&H/WC) Branch in the Galveston District Office is responsible for establishing pool limits, setting water control criteria and objectives, making hydrologic forecasts and coordinating overall water management operations. The plans and objectives for water control purposes are executed on a real-time basis by the project operating personnel.

TABLE 1-01
PERTINENT MANUALS AND REPORTS
FOR ADDICKS AND BARKER RESERVOIRS

Title	Date
Definite Project Report, Buffalo Bayou, Texas	June 1940
Preliminary Report on Operation of Reservoir, Barker Dam	July 1942
Analysis of Design, Addicks Dam	September 1945
Analysis of Design for Installation of Additional Sluice Gates, Addicks and Barker Reservoirs	October 1947
Report on Feasibility of Gating the Uncontrolled Conduits at Barker and Addicks Dams	September 1960
Reservoir Regulation Manual for Addicks and Barker Reservoirs	April 1962
Design Memorandum No. 1, Rehabilitation of Addicks and Barker Dams - Buffalo Bayou, Texas	February 1963
Design Memorandum No. 2, Master Plan for Barker Dam and Reservoir and Addicks Dam and Reservoir, Buffalo Bayou, Texas	August 1963
Summary Report on Review of Design Features of Existing Dams Under Jurisdiction of Galveston District	March 1967
Inspection Report, Buffalo Bayou and Tributaries, Addicks and Barker Dams, Texas	June 1969
Inspection Report No. 2, Buffalo Bayou and Tributaries, Addicks Dam, Texas	June 1974
Inspection Report No. 2, Buffalo Bayou and Tributaries, Barker Dam, Texas	July 1974
Letter Report for Emergency Seepage Control, Buffalo Bayou and Tributaries, Addicks Dam, Texas	May 1977
GDR 500-1-5, Emergency Operation Plan, Addicks and Barker Reservoirs, Emergency Employment of Army Resources	June 1977
Hydrology, Buffalo Bayou and Tributaries, Texas, Addicks and Barker Reservoirs	August 1977
Reconnaissance Report, Buffalo Bayou and Tributaries, Texas, Major Rehabilitation of Addicks and Barker Dams	October 1977
Emergency Seepage Control Construction Completion Report, Buffalo Bayou and Tributaries, Addicks and Barker Dams, Texas	March 1983

Dam Safety Assurance General Design Memorandum, Buffalo Bayou and Tributaries, Texas, Addicks and Barker Dams	August 1984
Dam Safety Assurance; Supplement No. 1 to General Design Memorandum, Buffalo Bayou and Tributaries, Texas, Addicks and Barker Dams	December 1985
Design Memorandum No. 3 - Master Plan Update, Addicks And Barker Reservoirs, Buffalo Bayou Watershed, Houston, Texas	August 1986
Reconnaissance Report, Section 216 Study, Addicks and Barker Reservoirs, Buffalo Bayou and Tributaries, Houston, Texas	October 1995
Galveston District Emergency Operations Plan, Annex I Addicks & Barker Emergency Action Plan	August 2006
2009 Master Plan Addicks And Barker Reservoirs, Buffalo Bayou And Tributaries, Fort Bend and Harris Counties, Texas	August 2009
Addicks and Barker Pool Probability Analysis, US Army Corps Of Engineers, Galveston District	October 2011

II - DESCRIPTION OF PROJECT

2-01. Location. The Buffalo Bayou watershed is within the San Jacinto River Basin, and lies primarily in Harris and Fort Bend Counties in southeast Texas. Barker Dam is located on Buffalo Bayou, and Addicks Dam is located on South Mayde Creek, a tributary of Buffalo Bayou. Both dams are located on the northwestern boundaries of the city limits of Houston, Texas. The top of dam at the outlet works of Addicks Reservoir are located at approximate latitude 29.790614° and longitude -95.623792°. The top of dam at the outlet of Barker Reservoir is located at approximate latitude 29.769717° and longitude -95.646587°. An overall vicinity map is shown on Plate 2-01.

2-02. Purpose. Addicks and Barker Reservoirs contribute to the overall purposes of authorized Buffalo Bayou flood risk management projects, which include the flood risk management protection provided to the City of Houston from flood damages, and prevention of excessive velocities and silt deposits in the Houston Ship Channel Turning Basin. The two reservoirs provide floodwater detention for flood risk management on the Buffalo Bayou watershed, and except during periods of rainfall, do not normally impound significant water.

2-03. Physical Components. Addicks and Barker Reservoirs are similar structures, consisting of long earthen embankments, with each dam having five conduits discharging flood waters into downstream channels. Subsidence has occurred along the dams and at the outlet works since construction to varying degrees. All elevations unless otherwise noted are NAVD 1988. The following paragraphs describe the physical components of the reservoir projects:

- a. Addicks Dam. The reservoir is formed by an earthen dam about 61,000 feet long constructed with 1 on 3 side slopes with a maximum height above stream bed of 48.5 feet. Both slopes are sodded and a 12-foot wide, hard surfaced road extends along the crest of the dam. The top of the dam is 121.0 feet, and the ends of the embankment terminate at a ground elevation of 108 feet on the north end and 112 feet on the west end. The spillway consists of the conduit outlet works in the South Mayde Creek channel section with emergency spillway around and over the ends of the dam. Plate 2-02 shows a local vicinity map for Addicks Reservoir. Plate 2-04 shows typical sections for Addicks Dam.
- b. Addicks Outlet Works. Five rectangular conduits, 8' wide x 6' high x 252' long, each with invert elevation 67.5 feet at intake, extend through the dam at the channel section. The four outside conduits are controlled by means of rectangular electrically-operated 8' x 10' sluice gates. The center conduit is controlled by twin 3' x 8' electrically-operated sluice gates. Discharge through the conduits passes through a 43.5 foot spillway into a 40' x 60' longitudinal stilling basin, then through a 150'

riprap lined outlet channel emptying into the improved channel of South Mayde Creek. Plate 2-06 shows a plan and profile view of the Addicks Outlet works.

- c. Barker Dam. The reservoir is formed by an earthen dam about 72,000 feet long constructed with 1 on 3 side slopes with a maximum height above stream bed of 36.5 feet. Both slopes of the dam are sodded and a 12-foot wide, hard surfaced road extends along the crest. Top of the dam is 113.1 feet, and the ends of the embankment terminate at a ground elevation of 104.0 feet. The spillway consists of the conduit outlet works in the Buffalo Bayou channel section with emergency spillway around and over the ends of the dam. Plate 2-03 shows a local vicinity map for Barker Reservoir. Plate 2-05 shows typical sections for Barker Dam.
- d. Barker Outlet Works. Five rectangular conduits, 9' wide x 7' high x 190.5' long, each with invert elevation 70.2 feet at intake, extend through the dam at the channel section. The four outside conduits are controlled by means of rectangular electrically-operated 9' x 11' sluice gates. The center conduit is controlled by twin 3.5' x 9' electrically-operated sluice gates. Discharge through the conduits passes through a 55.5' spillway into a 50' x 60' longitudinal stilling basin, then through a 160' riprap lined outlet channel emptying into the improved channel of Buffalo Bayou. Plate 2-07 shows a plan and profile view of the Barker Outlet works

2-04. Related Control Facilities. Addicks and Barker Reservoirs serve in conjunction with approximately 7.4 miles of Buffalo Bayou channel improvements immediately downstream of the dams to provide flood protection along Buffalo Bayou. Construction of additional downstream channel improvements along Buffalo Bayou were authorized by the Flood Control Act of 1954, but this construction was never performed due to public opposition concerned with aesthetic and environmental effects to Buffalo Bayou, and the rapid development of the area.

2-05. Real Estate Acquisition. Fee simple title has been obtained on approximately 12,460 acres for Addicks Reservoir and 12,060 acres for Barker Reservoir. Property limits are defined by elevation 103.0 for Addicks Reservoir and elevation 95.0 for Barker Reservoir, based on NAVD 1988 datum.

2-06. Public Facilities. There are five existing public recreation areas associated with Addicks and Barker Reservoirs. They are Bear Creek Pioneers Park, Congresssman Bill Archer Park, Cullen Park, George Bush Park, Millie Bush Bark Park and Barker Visitors Area. These parks include: Precinct 3 Park Headquarters, County Extension Agent, a Farm and Ranch Club, a Community Center, sports fields and courts, three 18-hole golf courses, dog parks, model airplane fields,

American Shooting Center, jogging trails, picnic areas, playground areas, restroom/concession buildings, and parking areas. Public facility areas are shown on Plates 2-08 and 2-09.

III - HISTORY OF PROJECT

3-01. Authorization. Addicks and Barker Dams were authorized by the 1939 Flood Control Act, a modification of the 1938 River and Harbor Act, House Document No. 456, 75th Congress, 2nd Session, which authorized flood control work in the Buffalo Bayou watershed. The project was further modified by the Flood Control Act of 1954, House Document No. 250, 83rd Congress, 2nd Session, which authorized straightening, enlarging, and lining where necessary, on Buffalo, Brays, and White Oak Bayous.

The existing project, as authorized, provides for flood risk management, the protection of the City of Houston from flood damages, and the prevention of excessive velocities and silt deposits in the Houston Ship Channel Turning Basin.

3-02. Planning and Design. The original flood control project for the main stem of Buffalo Bayou was authorized for the purpose of protecting urban development along Buffalo Bayou through the City of Houston. Its authorization was prompted by devastating floods in 1929 and 1935.

Initial planning and design for Addicks and Barker Reservoirs were based on the Definite Project Report for Buffalo Bayou dated June 1940. The original Barker Outfall structure and outlet channel was completed in 1945. The original Addicks Outfall structure and outlet channel was completed in 1948. The original design of each of the outfalls included five box culvert conduits, with one conduit gated and the other four uncontrolled. As the construction of the gates neared completion in 1948 gates were installed on two of the four uncontrolled conduits at each reservoir. Gates were added to the remaining conduits in 1962 and 1963. All conduits are currently gated.

Subsequent project-related reports and Design Memoranda are listed in Table 1-01.

3-03. Construction. A history of construction activities for Addicks and Barker Reservoirs is presented in Table 3-01.

TABLE 3-01
HISTORY OF CONSTRUCTION ACTIVITIES

Activity		Addicks	Barker
Reservoir, Conduits and One Gate	(Start)	May 1946	Feb 1942
	(Complete)	Dec 1948	Feb 1945
Date of Initial Operation		Jun 1948	Aug 1945
Two Additional Conduit Gates	(Start)	Feb 1948	Feb 1948
	(Complete)	Apr 1949	Apr 1949
Two Remaining Conduit Gates	(Start)	Jan 1962	Jan 1962
	(Complete)	Feb 1963	Feb 1963
Emergency Seepage Control Cont	(Start)	Sep 1977	Sep 1977
	(Complete)	Aug 1979	Sep 1979
Raise Main Embankment	(Start)	Jul 1986	Jun 1986
	(Complete)	Aug 1987	Aug 1988
Armor plate Ends of Dam w/RCC	(Start)	May 1987	May 1987
	(Complete)	Sep 1988	Sep 1988
T-wall Contract at Outlet	(Start)	Dec 1988	Sep 1989
	(Complete)	Sep 1989	Jun 1991
Outlet Structure Renovations	(Start)	1998	1998
(Electrical Work and Gate Repairs)	(Complete)	1999	1999
Fill Voids Under Conduits Phase 1	(Start)	May 2009	May 2009
	(Complete)	May 2009	May 2009
Fill Voids Under Conduits Phase 2	(Start)	Mar 2010	Mar 2010
	(Complete)	Apr 2010	Apr 2010

3-04. Related Projects. The original Federally authorized flood control plan for the City of Houston provided for three detention reservoirs (Addicks, Barker, and White Oak). A system of canals was to convey releases from White Oak Reservoir, north of Houston, to the San Jacinto River, and from Addicks and Barker Reservoirs, south of Houston, to Galveston Bay. Also, a levee was to be constructed along the Cypress Creek divide to prevent overflow from the Cypress Creek watershed into Addicks Reservoir. The original design concept for the dams provided for five outlet conduits at each dam, with four of the five to be uncontrolled.

Construction of Barker Dam was initiated in February 1942 and completed in February 1945. During preconstruction planning for Addicks Dam, it was determined to be more economical to increase the capacity of Addicks Reservoir to accommodate the overflow from Cypress Creek and delete the authorized levee.

Construction of Addicks Dam was initiated in May 1946 and completed in December 1948. Also, rectification and enlargement of approximately 7.4 miles of the Buffalo Bayou channel immediately downstream of the dams was completed in 1948. However, during construction of Addicks Dam, it was recognized that the planned discharge canals would be delayed because of rapid development in the Houston area. Therefore, in order to provide limited protection downstream on Buffalo Bayou until problems with the discharge canals could be resolved, gates were installed on two of the four uncontrolled conduits at each reservoir.

A review of reports completed in 1952 concluded that rising land costs and rapid development made construction of White Oak Reservoir and the discharge canals impracticable, and, in lieu of these facilities, recommended channel rectification of Buffalo, Brays and White Oak Bayous. These improvements were subsequently authorized by the Flood Control Act of 1954. The plan envisioned straightening and enlarging the channels to contain the Standard Project Flood (SPF) with concrete lining to the level of the 10-year frequency flood. It was rationalized at the time that since the reservoirs provided a measure of flood protection for Buffalo Bayou, priority would be placed on channel rectification of Brays and White Oak Bayous. Channel improvements for 25.4 miles of Brays Bayou and 10.7 miles of White Oak Bayou were completed in 1971 and 1975, respectively. However, rectification of Buffalo Bayou was delayed by public opposition concerned with aesthetic and environmental effects of the plan on the existing stream.

3-05. Modifications to Regulations. The original design concept for both dams provided for four of the five outlet conduits to be uncontrolled, permitting a combined uncontrolled discharge of about 15,700 cubic feet per second (cfs) into Buffalo Bayou. When two of the four un-gated conduits were gated at each dam in 1948, the combined uncontrolled discharge was about 7,900 cfs, which was considered to be the channel capacity at that time. Increasing urban development adjacent to Buffalo Bayou during the 1940's and 1950's created a potential flood threat by the uncontrolled release from the reservoirs. Studies undertaken in 1960 showed the feasibility of gating the remaining uncontrolled conduits, and this work was subsequently completed in 1963. The total of all releases, plus local runoff downstream from the dams, would start at 4,000 cfs and be gradually increased to 6,000 cfs except under emergency conditions. While the gating of the last two uncontrolled conduits on both projects in 1963 made it possible to reduce downstream flooding, it also prolonged storage of rainfall runoff behind the dams.

Continued residential development along Buffalo Bayou downstream from the reservoirs resulted in channel encroachment and by late 1970; flows in excess of 3,000 cfs in the unimproved channel below the dams would begin to threaten the first floor elevations of some residences. Even without significant downstream inflows, release rates of 2,500 to 2,800 cfs would produce prolonged nuisance type flooding of flower beds, trees and lawns for a considerable number of residences adjacent to the Bayou and in some of its tributary swales. Discharges in this range

do not leave any freeboard for inflows from rainfall.

In early 1971, an inspection of Buffalo Bayou revealed serious bank erosion at several locations. In order to provide temporary relief from this problem, until the local interests could provide the necessary remedial measures, releases from the reservoirs were temporarily restricted to 500 cfs at Piney Point. During dry periods with little or no chance of rain, releases could be made from 700 to 1,000 cfs. When rainfall was expected, releases had to be reduced or shut off entirely.

The reduction in release rates and the resulting prolonged detention of water in the reservoirs generated a number of complaints from local residents during the latter part of 1971. The complaints generally referred to the floodwaters that were stored in the reservoirs and expressed concern that the reservoirs were becoming breeding grounds for mosquitoes and that the prolonged storage would kill the trees and make the area unfit for parks sites. The District received complaints of an undesirable odor due to the prolonged detention of floodwaters in the wooded areas at the Addicks Outlet Works when releases were being made.

A study was started in 1971 and completed in 1972 revising the regulation procedures to maintain the best balance of reservoir releases into the inadequate downstream channel without serious damage as opposed to the prolonged storage of water in the reservoirs. The interim procedures described herein were put in place until local interests were able to complete their improvements. These improvements as planned were expected to permit total releases from the reservoirs of 2,000 to 2,500 cfs. Based on the available data at the time and new field surveys the anticipated operational procedure with the local channel improvements was determined to permit releases of 2,000 cfs. In 1974, local interests completed improvements to the channel in areas which were extensive damage to adjacent structures was threatening. Regulation procedures were implemented to allow combined releases of Addicks and Barker Dams up to 2,000 cfs at Piney Point, local inflow included.

In early 1976, Harris County Flood Control District excavated Turkey Creek Ditch adjacent to Federal property below Addicks Dam. The ditch, about 15 feet deep, intercepted and exposed a sand stratum that was believed to be continuous through pervious sections of the Dam embankments foundation that opened to the surface of the pool area. During subsequent rises in the reservoir pool, seepage was noted in the exposed sand strata in the ditch. This was considered to be a serious seepage problem that threatened the stability of the embankment, and created a potential for failure of the dam in the event of a high reservoir pool. Immediate action was taken to fix the problem. Since Barker Reservoir had Barker and Clodine Ditches below its dam, the repairs for Addicks Dam were implemented on Barker Dam also. These repairs for the various reaches of the embankments included a bentonite slurry trench seepage barrier extending through the earth fill dams into the relatively impervious clay strata, earthen stability berms placed on the

downstream slope of the embankments, and upstream clay blanketing. Emergency modifications were completed between 1977 and 1979.

In 1976 a restudy of Addicks and Barker Reservoirs was initiated to determine the adequacy of the two dams with respect to safety and functional reliability. On 8 May 1977, the Hydrology Report for Addicks and Barker Reservoirs was submitted to SWD for approval. In this report, exhibit D titled "Description of Addicks and Barker Reservoirs Regulation Program" section D-5 Regulatory Conditions, modified the flood risk management regulations for each reservoir. The May, 1977 Hydrology Report was approved by SWD. Since that report, the flood risk management regulations have remained the same. The current regulation procedures stipulate that releases from both reservoirs, plus the downstream inflow, will not exceed 2,000 cfs at Piney Point on Buffalo Bayou except under emergency conditions.

3-06. Principal Regulation Problems. The chief regulation problem associated with Addicks and Barker Reservoirs has been the continually diminishing downstream non-damaging channel capacity due to encroachment. Additionally continual upstream development has increased inflow into the Reservoirs due to these developments and is likely to continue. Plates 3-01 and 3-02 display water surface profiles and floor elevations along Buffalo Bayou downstream of the reservoirs.

Additional regulation problems include seepage and boils infiltrating the embankments. While the gating of two previously uncontrolled conduits on both projects in 1963 made it possible to reduce downstream flooding, it also prolonged storage of rainfall runoff behind the dams, and resulted in a serious seepage problem through pervious sections of the embankments and foundations. This seepage problem threatened the stability of the embankments, and created a potential for failure of the dams in the event of a high reservoir pool. Repairs for various reaches of the embankments included a bentonite slurry trench seepage barrier extending through the earth fill dams into the relatively imperious clay strata, earthen stability berms placed on the downstream slope of the embankments, and upstream clay blanketing. These emergency modifications were completed between 1977 and 1979 at a cost of about \$12 million.

IV - WATERSHED CHARACTERISTICS

4-01. General Characteristics.

- a. Buffalo Bayou Watershed. Buffalo Bayou is located in the San Jacinto Watershed Basin. The Buffalo Bayou watershed lies primarily in Harris and Fort Bend Counties in southeast Texas. The basin is bounded on the north by Cypress Creek; on the east by the San Jacinto River; on the south by Clear Creek; and on the west by the Brazos River. Barker Dam is located on Buffalo Bayou about 1.5 miles above the confluence of South Mayde Creek. Addicks Dam is located on South Mayde Creek about one mile above its confluence with Buffalo Bayou.
- b. Barker Reservoir Watershed. The portion of the Buffalo Bayou watershed flowing into Barker Reservoir lies within Harris, Waller, and Fort Bend Counties. The watershed, a roughly trapezoidal area of approximately 130 square miles, is approximately 23 miles long with an average width of 6 miles. The watershed is shown on Plate 4-01.
- c. Addicks Reservoir Watershed. The South Mayde Creek watershed flowing into Addicks Reservoir lies within Harris County. The watershed is roughly 15 miles long, 10 miles wide, and has a drainage area of approximately 136 square miles. The watershed includes several major tributaries including Bear Creek, Langham Creek, Horsepen Creek and Turkey Creek. The watershed is shown on Plate 4-01.
- d. Cypress Creek Watershed. The 130 square mile watershed of Cypress Creek upstream of U.S. Highway 290 lies north of and adjacent to the Addicks Reservoir watershed. The general land slope of Harris and Waller Counties in this area is in a southerly direction while the Cypress Creek channel flows in an easterly direction to its outlet into the San Jacinto River in eastern Harris County. Consequently, the flood plain for Cypress Creek is relatively shallow with a poorly defined divide to the south and floodwaters from larger floods flow southward into the Addicks Reservoir watershed. The watershed is shown on Plate 4-01.

4-02. Topography. Natural ground elevations in the Addicks and Barker Reservoir watersheds vary from approximately 200 feet at the upstream divides to approximately 68 feet at Addicks Dam and approximately 70 feet at Barker Dam. Natural stream flow gradients in the basin are very uniform at about 5 feet per mile sloping in a southeastern direction.

4-03. Geology & Soils. The geologic formations which outcrop on the Buffalo Bayou watershed are of the Quaternary system. The southeastern part of the basin is occupied by Beaumont clay, and the northeastern part by Lissie sands. Recent alluvium deposits occupy the shallow stream valleys. The formations dip

southeasterly in the same direction at the land surface, but on a much steeper slope. The soils are of the Coastal Prairie series and generally drain poorly.

- a. Addicks Dam. The existing embankment materials are typically stiff to hard sandy clays with thin layers, seams, and pockets of silty sands, clayey sands, and sandy silts. The existing embankment is founded on a layer of stiff to hard sandy clays and clays varying in thickness from 8 to 30 feet. The sandy clays overlie a medium dense to very dense layer of silty sand, clayey sand, or sandy silt. The thickness of this layer varies considerably from a few feet to 60 feet. In some reaches of the embankment the layer was not encountered. Deeper materials are very stiff to hard clays with some sandy silt or clayey silt layers.

During the period of September 1977 to March 1979, approximately 6.8 miles of the existing embankment were modified by remedial seepage control construction. This construction included an embankment slurry trench along approximately 3.5 miles of the embankment. An upstream slurry trench was constructed for 1.87 miles with a downstream stability berm constructed along approximately 3.3 miles of the existing embankment. The 3-foot wide embankment slurry trench located approximately 20 feet upstream of the existing embankment fully penetrates the embankment and silty sand foundation layer. The upstream slurry trench of 3-foot width excavated along the upstream embankment toe fully penetrated the silty sand foundation layer. The slurry trenches were backfilled with a soil-bentonite mixture classified as a clayey sand. The downstream stability berm constructed along most of the reach of the upstream slurry trench is a compacted sandy clay fill which intersects the existing embankment slope at elevation 108 feet NAVD 1988 and slopes to natural ground on a 1 vertical on 7 or 8 horizontal slope. Reaches where slurry trenches and downstream stability berms were constructed and details of the construction are given in the Emergency Seepage Control Construction Completion Report, Buffalo Bayou and Tributaries, Addicks and Barker Dams, Texas, March 1983.

In 1986, approximately 23,600 linear feet of the main earth embankment of Addicks Dam was raised about 1 to 2 feet to the minimum freeboard elevation of 121 feet NAVD 1988 and approximately 8,800 linear feet was raised about 3 feet to the computed freeboard elevation of 121 feet NAVD 1988. This generally was accomplished by the addition of compacted fill on the downstream slope and crown of the embankment. The compacted fill was composed of sandy clays and clayey sand material excavated from borrow areas within the reservoir. The downstream slope of the enlarged embankment was resurfaced with the existing topsoil materials suitable for establishing turf. A portion of the

flexible base material on the existing crown was reused in constructing the open surfaced roadway on the new 12-foot wide crown. The enlarged main embankments generally have side slopes of 1 vertical to 3 horizontal on the upstream side and 1 vertical to 2.5 horizontal on the downstream side. Exceptions to the 1 vertical to 3 horizontal upstream slope occurred on Addicks Dam between stations 160+00 and 235+00 and between stations 380+00 and 460+00 where the existing embankment crest was approximately 1.0 foot below the crest of the proposed embankment. In these reaches the side slope on the upstream side would be 1 vertical to 2.5 horizontal to allow reshaping of the existing crown with minimal disturbance to the upstream and downstream side slopes.

- b. Barker Dam. The existing embankment materials are typically stiff to hard sandy clays with thin layers, seams, and pockets of silty sands, clayey sands, and sandy silts. The existing embankment is founded on a layer of stiff to hard sandy clay varying in thickness from 7 to 25 feet. The sandy clays overlie a medium dense to very dense layer of silty sand, sandy silt, or clayey sand. The thickness of this layer varies from a few feet to 35 feet. In some reaches of the embankment the layer was not encountered. Deeper materials are predominantly very stiff to hard clays with some sandy silt or clayey silt layers.

Approximately 9.1 miles of the existing embankment was modified by remedial seepage control construction in 1978 and 1979. The construction included an embankment slurry trench along approximately 1.9 miles of the embankment. A downstream stability berm was constructed along approximately 7.2 miles of the existing embankment. The embankment slurry trench located 20 feet upstream of the existing embankment centerline is a minimum of 3 feet thick. The slurry trench fully penetrates the existing embankment and silty sand foundation layer and was backfilled with a soil-bentonite backfill mixture which has been classified as a clayey sand. The downstream stability berm is a compacted sandy clay fill that slopes to natural ground on a 1 vertical on 8 horizontal slope. Reaches where slurry trenches and downstream stability berms were constructed and details of the construction are given in the Emergency Seepage Control Construction Completion Report, Buffalo Bayou and Tributaries, Addicks and Barker Dams, Texas, March 1983.

In 1986, approximately 14,800 linear feet of the main earth embankment on Barker Dam was raised about 2 to 3 feet to the minimum freeboard elevation of 113.1 feet NAVD 1988 and approximately 42,750 linear feet was raised about 3 to 5 feet to varying computed freeboard elevations up to 113.1 feet NAVD 1988. This generally was accomplished by the addition of compacted fill on the downstream slope and crown of the

embankment. The compacted fill was composed of sandy clays and clayey sand excavated from borrow areas within the reservoir. The downstream slope of the enlarged embankment was resurfaced with the existing topsoil materials suitable for establishing turf. A portion of the flexible base material on the existing crown was reused in constructing the open surfaced roadway on the new 12-foot crown. The enlarged main embankments generally have side slopes of 1 vertical to 3 horizontal on the upstream side and 1 vertical to 2.5 horizontal on the downstream side.

- c. Groundwater conditions. Water table measurements were made in some of the borings taken prior to remedial seepage control construction. The measurements indicated a water table existed 5 to 15 feet below natural ground along Addicks Dam and 5 to 25 feet below natural ground along Barker Dam.
- d. Subsidence. The geologic area has experienced large regional subsidence due to groundwater extraction which continues today albeit at a decreased rate in recent years due to restrictions on groundwater extraction. Although the regional subsidence in the Barker area appears to be evenly distributed over the region, there could be localized differential settlement around the conduit and the soils (CL/CH) are compressible

4-04. Sediment. Subsequent to project completion and through the 1973-1975 reservoir re-surveys, there has been no evidence of appreciable erosion in the watersheds above the dams or serious sedimentation problems. Since 1975, construction activities associated with urbanization of the upper watersheds have substantially increased the sediment load of the streams flowing into the reservoirs. As a result of the Galveston District's policy established in the late 1970's of prohibiting drainage improvements on the Government-owned reservoir lands, sediment deposits have been restricted to the improved channels on privately-owned land and to the shallow overbanks of the upper elevations of the reservoirs. In 1981, the Galveston District relaxed the drainage policy regarding improved channels with the requirement of positive sediment control above improved channel reaches on Government-owned lands. Sediment ranges have been set up above the Government-owned lands and within the reservoir area to monitor Harris County and Fort Bend County sediment basin operation and maintenance programs on channel improvements brought onto government-owned land.

4-05. Climate.

- a. General. The Buffalo Bayou watershed lies in a relatively humid and temperate climatic region. Summers are long and hot, but are tempered somewhat by sea breezes from the Gulf of Mexico. Winters are generally mild, and snowfall is infrequent. Prevailing winds are from the south or southeast.
- b. Temperature. The daily range in temperatures is moderate except in the winter months when polar air masses periodically cause sharp drops. The average annual temperature for this area is about 69 degrees. Temperature extremes range from 109 degrees (2000) to 5 degrees (1980). Table 4-01 presents climatological data relative to temperature at representative United States Weather Service stations near Addicks and Barker Reservoirs.

TABLE 4-01
TEMPERATURE DATA

Station	Years of Record Thru 2010	<u>Temperature in Degrees Fahrenheit</u>		
		Mean Annual	Maximum Recorded	Minimum Recorded
Houston (Hobby Airport)	30	70.2	108	5
Houston (Bush Airport)	30	69.8	109	5
Sugarland	63	69.1	108	6

- c. Precipitation. Precipitation in the Addicks and Barker Reservoir area is well distributed throughout the year. Summer precipitation typically results from intense, short, isolated convective cells, while winter and spring precipitation is generally produced by more widespread frontal events. The area is also affected by torrential rainfall associated with hurricanes and other tropical disturbances. The highest recorded 24-hour precipitation in the Houston area was 42 inches on 25-26 July 1979 (Tropical Storm Claudette) north of Alvin, a national record for that time period. Another intense 24-hour total of 19.58 inches was recorded on 8 June 2001 (Tropical Storm Allison) in Houston Heights. Tropical Allison produced a six-day rainfall in Houston that amounted to 38.6 inches. The highest recorded annual precipitation was 72.85 inches in 1992, and the lowest recorded annual precipitation was 22.40 inches in 1954. Average monthly and annual rainfall totals for the Houston area are presented in Table 4-02.

TABLE 4-02
AVERAGE MONTHLY AND ANNUAL RAINFALL

Month	Average Rainfall (Inches)	
	Barker	Addicks
Jan	3.25	4.28
Feb	2.98	3.06
March	3.24	2.55
April	3.09	3.11
May	4.21	4.03
June	4.20	4.13
July	3.02	3.03
Aug	3.72	3.46
Sept	4.19	4.29
Oct	4.11	4.29
Nov	3.81	3.75
<u>Dec</u>	<u>3.24</u>	<u>3.31</u>
Total	43.06	43.29

Periods of Record (1945-2005 for Barker, 1948-2005 for Addicks)

- d. Evaporation. Since Addicks and Barker Reservoirs are detention-type reservoirs with only flood pools of short duration, evaporation is not a consideration in their operation.
- e. Wind. The mean annual wind speed for the Houston area is 7.6 miles per hour, with the highest wind speed being 84 miles per hour in March 1926.

4-06. Storms and Floods. The maximum known flood on Buffalo Bayou occurred in December of 1935. During this flood, overflow occurred from White Oak Bayou into Buffalo Bayou and considerable overflow occurred from Buffalo Bayou into Brays Bayou. A peak flow rate of 40,000 cfs was estimated for Buffalo Bayou at Waugh Drive, located about 25 stream miles below the reservoirs. Buffalo Bayou below the intersection of White Oak Bayou, located about 28 stream miles below the reservoirs, had an estimated flow of 53,000 cfs. Since establishment of stream gaging stations, the maximum flood which has occurred on Buffalo Bayou was that of June 2001 when a peak discharge of 14,000 cfs was recorded at Shepherd Drive. The largest combined discharge from both reservoirs occurred in June 1960 when a total outflow of 5,800 cfs was estimated. The maximum impoundment in Addicks and Barker Reservoirs occurred in March of 1992 when pool elevations reached 97.46 ft and 93.6 ft NAVD 1988, respectively. These pools resulted from a total rainfall of over 8 inches in a 9-hour period normally referred to as the "Ash Wednesday Flood of 1992. Chapter 8 of this manual contains information on additional major storm events.

4-07. Runoff Characteristics. The Buffalo Bayou basin above Addicks and Barker Dams produces moderate to high runoff. During the re-analysis of the basin, it was found that 1.0 to 2.5 inches of rainfall generally was needed to satisfy initial losses before significant runoff begins. The total contributing drainage area during moderate flood events for Addicks and Barker Reservoirs is 136 and 130 square miles, respectively. Under major flood events, Addicks Reservoir receives about one-third of its total volume from the 130 square mile drainage area of the Upper Cypress Creek Basin. The time of concentration from the period of most intense rainfall for major floods is about 5 to 13 hours for the basin. The volume of runoff (inflow volume) is summarized in the average monthly and annual project flows in Table 4-03.

TABLE 4-03
AVERAGE INFLOW VOLUMES AT ADDICKS AND BARKER RESERVOIRS
RECORDED FOR PROJECT RELEASES 1/

Month	Inflow (1,000 ac-ft)	Month	Inflow (1,000 ac-ft)
January	18	July	14
February	19	August	10
March	16	September	17
April	14	October	18
May	20	November	21
June	18	December	20
		<u>ANNUAL TOTAL</u>	<u>203</u>

1/ Period of Record: 1964 through 2010.

4-08. Water Quality. Addicks and Barker Reservoirs are detention reservoirs with flood pools of short duration; water quality is not a consideration in their operation.

4-09. Channel and Floodway Characteristics. The Buffalo Bayou channel downstream of Addicks and Barker Reservoirs remains in a relatively natural state; however; adjacent development has encroached to very near the main channel for several miles downstream of the two projects. Plates 3-01 and 3-02 show water surface profiles for various flows down Buffalo Bayou with first floor slab elevations. Potential flood damage to these properties is the major constraint on releases while bank erosion is also a concern. The primary stream gaging station by which Addicks and Barker Reservoirs are regulated is Buffalo Bayou at Piney Point, approximately 10.7 stream miles below Barker Dam. Other pertinent stream gaging stations include Buffalo Bayou near Addicks and Buffalo Bayou at West Belt Drive, approximately 3.0 and 6.5 miles downstream of Barker Dam respectively. These station locations are shown in Plate 5-01, and a discharge rating curve for the Buffalo Bayou at Piney Point gage is provided in Plate 4-02.

4-10. Upstream Structures. There are no significant upstream flood control structures on Buffalo Bayou or its tributaries.

4-11. Downstream Structures. There are no significant downstream flood control structures on Buffalo Bayou or its tributaries.

4-12. Economic Data.

- a. Population. Population by county in the vicinity of Addicks and Barker Reservoirs are shown in Table 4-04.

TABLE 4-04
POPULATION OF COUNTIES IN THE
VICINITY OF ADDICKS AND BARKER RESERVOIRS

County	1980 ^{1/}	1990 ^{1/}	2000 ^{1/}	2010 ^{1/}	% Change 2000-2010
Fort Bend	130,962	225,421	354,452	585,375	+65.1
Harris	2,409,547	2,818,101	3,400,578	4,092,459	+20.3
Montgomery	127,222	182,201	293,768	455,746	+55.1
Waller	19,798	23,389	32,663	43,205	+32.3

^{1/} U. S. Bureau of the Census, Census of Housing and Population..

- b. Agriculture. The Addicks and Barker Reservoir watersheds are approximately 50% and 40% undeveloped respectively. The undeveloped areas are used primarily for pasture land and general mixed agricultural purposes.
- c. Industry. The Addicks and Barker Reservoir watersheds are approximately 50% and 60% urbanized respectively, most of which is residential and related commercial and office land use. There is very little heavy industrial development in the Addicks and Barker Reservoir watersheds or in the upper Buffalo Bayou watershed immediately downstream of the two projects.
- d. Recreation. Approximately 24,520 acres of existing and proposed public use areas are designated for use by the general public for parks, recreational purposes, and commercial concessions. A brief description of public facilities available in these areas is presented in Section 2-06. A detailed description of existing and proposed public facilities is provided in Design Memorandum No. 3, Master Plan Update, Addicks and Barker Reservoirs, Buffalo Bayou Watershed, Houston, Texas, dated August 1986.

- e. Flood Damages. Prior to development of the extensive flood control system in the Buffalo Bayou watershed, frequent flooding caused extensive property damage and occasional loss of life. Since construction of the Addicks and Barker Reservoir projects, flood damages from Buffalo Bayou and its downstream tributaries above White Oak Bayou have been drastically reduced. The flood damage reduction has been accomplished through the progressive reduction in allowable combined discharge for the two projects to accommodate increasing downstream development. Estimated flood damages prevented by Addicks and Barker Reservoirs are shown in Table 4-05 on the following page.

TABLE 4-05
DAMAGES PREVENTED BY ADDICKS AND BARKER RESERVOIRS
(FY 1980 THROUGH FY 2010)

Fiscal Year <u>2</u> / (FY)	Damages Prevented 1/ (\$000)
1980	501
1981	17,733
1982	11,700
1983	16,000
1984	0
1985	18,800
1986	25,500
1987	34,792
1988	0
1989	60,434
1990	27,960
1991	22,420
1992	397,600
1993	306,100
1994	289,700
1995	340,000
1996	260
1997	285
1998	478
1999	445
2000	415
2001	24,000
2002	23,300
2003	385,000
2004	194,060
2005	371,953
2006	387,200
2007	801,000
2008	804,200
2009	964,000
2010	762,000
<u>2011</u>	<u>0</u>
Average	203,801

1/ Damages prevented by Galveston District flood control projects.

2/ The Fiscal Year is from October through September.

V - DATA COLLECTION AND COMMUNICATION NETWORKS

5-01. Hydrometeorological Stations.

- a. Facilities. The Corps of Engineers (CORPS), National Weather Service (NWS), and United States Geological Survey (USGS) cooperate in the collection and dissemination of hydrologic data related to Addicks and Barker Reservoirs. The locations of gaging stations used to regulate Addicks and Barker Reservoirs are shown on Plate 5-01. These stream gaging stations essential to the operation of Addicks and Barker Reservoirs are shown in Table 5-01.

TABLE 5-01
STREAMGAGING STATIONS PERTINENT
TO ADDICKS AND BARKER RESERVOIRS

Description	Parameter and DCP Recording Interval	USGS Station Number	Latitude	Longitude
Buffalo Bayou near Katy	Stage/15-minute	8072300	29.74305° N	-95.80666° W
Buffalo Bayou at Houston, Texas	Stage/15-minute	8074000	29.76000° N	95.40833° W
Barker Reservoir near Addicks	Stage/15-minute	8072500	29.76972° N	95.64694° W
South Mayde Creek near Addicks	Stage/15-minute	8072700	29.80106° N	-95.69245° W
Bear Creek near Barker	Stage/15-minute	8072730	29.83078° N	-95.68689° W
Langham Creek at West Little York Road	Stage/15-minute	8072760	29.86717° N	-95.64661° W
Langham Creek near Addicks	Stage/15-minute	8072800	29.83578° N	-95.62522° W
Addicks Reservoir near Addicks	Stage/15-minute	8073000	29.79111° N	95.62333° W
Buffalo Bayou near Fulshear, Texas	Stage/15-minute	8072350	29.72277° N	-95.76694° W
Buffalo Bayou near State Highway 6	Stage/15-minute	8072600	29.76920° N	-95.64310° W
Buffalo Bayou at West Belt Drive	Stage/15-minute	8073600	29.76217° N	-95.55772° W
Buffalo Bayou at Piney Point	Stage/15-minute	8073700	29.74667° N	95.52333° W
Cypress Creek at Katy Hockley Road	Stage/15-minute	8068720	29.92083° N	-95.83333° W
Cypress Creek at House Hahl Road	Stage/15-minute	8068740	29.95928° N	-95.71778° W

b. Reporting

1. The reporting procedures for gaging stations are on a cooperative basis with the USGS. All gaging stations are automated gages consisting of pressure sensors, bubble gages or radar sensors supplying data to data collection platforms. Some automated gaging stations are equipped with automated rain gages that provide precipitation data. These gaging stations automatically report pool elevations, stream gage heights and precipitation using the data collection platform (DCP) which records the data and transmits it hourly or when a threshold value is exceeded. These data are transmitted via GOES satellite to a Direct Receive Ground Station and computer facility, owned and operated by the National Oceanic and Atmospheric Administration, at Wallops Island, Virginia. These data are then rebroadcast over the Domestic Satellite System (DOMSAT) to a Direct Receive Only Terminal (DROT) in the district or server district. SWG currently receives data through a network socket connection to a data acquisition server located in the Fort Worth District via the USACE network. The US Geological Survey is another data source for the district office.
2. Rainfall and stream stage data are automatically stored in data files and used by the Hydrology and Hydraulics/Water Control (H&H/WC) Branch in routine and emergency water management activities. Once in these files, the data are then utilized for checking project status, defining basin conditions, forecasting stream flows, and disseminating information to other Corps elements. Data from these files serve as the primary data source from which all Hydrology and Hydraulics functions are carried out. The processing of this data is by internal computer software programs based on a database (HEC-DSS) developed by the Corps' Hydrologic Engineering Center (HEC) at Davis, California.

c. Maintenance

1. The NWS rainfall reporting sites are maintained by NWS personnel as a part of the observer network program. USACE provides funding by interagency transfer to the NWS through the NWS/CORPS Cooperative Reporting Network Program operated on a nationwide basis.
2. Malfunctions of automated DCP rainfall, elevation, and stream-gage stations are reported to the USGS which operates/maintains the gages. The Corps provides funding by interagency transfer to the

USGS through the USGS/CORPS Cooperative Stream Gaging Program operated on a nationwide basis.

5-02. Water Quality Stations.

- a. Facilities. Since Addicks and Barker Reservoirs are detention-type reservoirs with only flood pools of short duration, water quality is not a consideration in their operation. There are no water quality stations associated with the two projects.

5-03. Sediment Stations. Sediment ranges have been established where major tributaries enter Addicks and Barker Reservoirs. The ranges are re-surveyed at variable time intervals depending on the frequency of storm events, sedimentation rates, and available funding.

5-04. Recording Hydrologic Data.

- a. Project Data.

1. Hourly values of stream stage, pool elevations, and precipitation are automatically transmitted to the Corps Water Management System (CWMS) server via DCP. Upon receipt of the data, the values are decoded into engineering units and written to HEC-DSS and CWMS databases. Data is checked and corrected by regulation personnel as necessary for quality control.
2. Processed daily parameters (inflow and total release) are also archived in the project HEC-DSS file. Monthly totals are accumulated from the daily information and stored permanently in the project file. For permanent hard copy records required by ER1110-2-240, daily and monthly data in the project file are used to publish monthly charts for Addicks and Barker Reservoirs.
3. The rainfall and river stage data from the above sources are automatically shunted to data files within the WCDS and used by the Hydrology/Water Control (H&H/WC) Branch in routine and emergency water management activities. Once in these files, the data is utilized for checking project status, defining basin conditions, forecasting flows into the reservoirs, and disseminating information to other Corps elements. Data from these files serve as the primary data source from which all Hydrology and Hydraulics functions are carried out. The processing of this data is by internal computer software programs based on a database (DSS) developed by the Corps' Hydrologic Engineering Center (HEC) located in Davis, California.

- b. Stream Gage Data. Stage data for Buffalo Bayou and other stations identified in Table 5-01 are received and processed into the project HEC-DSS file as described above. In addition to the Hydrology and Hydraulics computer files, the USGS maintains an archive of this station data.
- c. Precipitation Data. The project HEC-DSS file stores precipitation data from the DCP stations after the data is checked and corrected by regulation personnel for quality control. Precipitation data received through the NWS-AWIPS system is also stored in the project HEC-DSS file. The NWS also records the data from their observer network permanently within their standard climatological records.

5-05. Communications Network. Wire line facilities at Addicks and Barker Reservoirs are local and long-distance commercial telephone service. Radio communication is by a VHF-FM fixed station capable of reaching local mobile stations and other portable stations. Responsibility for the project's fixed equipment and its repairs, as conditions warrant, is a required function of ACE-IT. The HF-SSB Radio System is used to maintain contact, if needed, with the District Office and Southwestern Division Office. ACE-IT has the responsibility to maintain this System.

5-06. Communication with Project. There is no scheduled or set communications between the Hydrology/Water Control (H&H/WC) Branch and the projects. Normal data channels are through the DCP network. Maintaining project releases within the criteria of Chapter 7 does not require detailed real-time coordination. The primary mode of communication is by telephone, cell phone and the HF-SSB Radio System as an alternative back-up system.

- a. Regulating Office with Project Office. The Chief, Engineering/Construction Division through the Chief, Hydrology/Water Control (H&H/WC) Branch, is responsible for setting project regulating criteria for standard operations as documented in this manual and by separate communications for non-routine operations. Communication is normally by telephone in response to problems, furnish flow forecasts, alert project to developing floods, obtain data, or to schedule special water releases. Should communications with the Hydrology/Water Control (H&H/WC) Branch be disrupted, the Dam Tender will direct regulation of the pool in accordance with the provisions of Chapter 7 and Exhibit B (Standing Instructions to Dam Tender) of this manual.
- b. Between Project Office and Others. When communications with the district office is disrupted, the Dam Tender is responsible for alerting local agencies that might be adversely impacted by project operations such as

large changes in release rates and changing pool stages, especially when pool stages are approaching the limits of the reservoir boundary. This warning will be accomplished by the most expedient and effective means of communication available. When adequate time exists, information to be passed to the general public will be accomplished in coordination with and through the Public Affairs Office.

5-07. Project Reporting Instructions. No hydrologic data are routinely reported by the project. However, in the event of a failure in the automated data system, the project personnel will furnish pool elevation, stream gage and rainfall data to the Hydrology/Water Control (H&H/WC) Branch by telephone, cell phone or district radio if necessary. The actual reporting requirements will be established by the Chief of the Hydrology/Water Control (H&H/WC) Branch on a case by case basis to assure adequate data is available for the conditions that exist at the time. Non-routine items such as malfunctioning gates, facilities problems, etc. that may affect normal project operations related to pool limits and release rates should be reported by telephone, to the Chief Hydrology/Water Control (H&H/WC) Branch. If these are expected to be long term impacts, the telephone report should be followed up by a memorandum from the Dam Tender to the Chief, Engineering /Construction Division.

5-08. Warnings. Flood emergency warnings and other information that needs to be passed to the general public will be made by newspapers, radio, and television and newspapers to the extent adequate time exists. These announcements are coordinated by the Public Affairs Office for the general public, and by the Office of Emergency Management Operations Office for distribution through emergency communication channels required by ER500-1-1. These offices rely on the Project Office and Hydrology/Water Control (H&H/WC) Branch to alert them of a developing situation that requires warnings or information releases outside the Corps channels. In general, the Hydrology/Water Control (H&H/WC) Branch will provide these alerts. For events which are developing locally, and often quite rapidly, Project Office personnel must provide the alert.

- a. Local Warnings. In rapidly changing situations where time frames are inadequate for dissemination of information through the above procedure, the Project Office will provide warnings or alerts to the local agencies responsible for the immediate areas of potential impact. The Offices of Emergency Management would be notified first followed by other critical local agencies, law enforcement and the civil defense. The Project Office should maintain a current list of these agencies that would be endangered or adversely impacted by pool levels outside normal limits or by sudden or large changes in releases. Notifications to the agencies on this list would be by the most appropriate means in response to the situation that is developing. This could include telephone, cell phone and radio.

- b. Flood Emergency Plan. Studies have been made to determine the possible downstream flood conditions that could exist for the Spillway Design Flood event. Plate 5-02 through 5-09 shows approximate Spillway Design Flood inundation limits.

5-09. Routine Information for Public Release. Information on current pool elevations, project releases and selected stream stages are made available to the public by telephone from the Hydrology/Water Control (H&H/WC) Branch. Streamflow data is also available through the Internet from the USGS.

VI - HYDROLOGIC FORECAST

6-01. General.

a. Role of the Corps. The role of U.S. Army Corps of Engineers (USACE) is to make hydrologic forecasts for flood risk management. The forecasts are provided to project personnel, and planned changes in the release rates are furnished to the National Weather Service – West Gulf River Forecast Center (NWS-WGRFC) in Fort Worth, Texas. The Public Affairs Office, which is kept informed of the lake conditions, makes news releases.

b. Role of Other Agencies. NWS-WGRFC provides information about river flow and flood forecasts to the Corps of Engineers and to the general public. Timely access to weather and water information is provided through NWS systems, including the

- NWS Home Page – www.weather.gov
- NOAAPORT
- NOAA Weather Wire Service (NWWS)
- Emergency Managers Weather Information Network (EMWIN)
- NOAA Weather Radio (NWR)
- Family of Services (FOS)
- Commercial weather information vendors.

The National Weather Service - Weather Forecast Offices (NWS-WFO) issues routine scheduled reports containing the following information:

1. Weather forecasts (daily forecasts, severe weather forecasts, and seven-day extended forecasts).
2. Quantitative Precipitation Forecasts: Twelve successive 6-hour precipitation forecasts are updated each 12 hours. Three successive 24-hour precipitation forecasts are updated every 12 hours. QPF is also created/issued by the WGRFC for ingest into the hydrologic models used for river stage forecasting. WGRFC QPF is available for viewing on the WGRFC webpage at www.weather.gov/wgrfc. WGRFC QPF is also transmitted to USACE via the Fort Worth District.
3. Five-day river stage forecasts, when conditions warrant, from the West Gulf River Forecast Center.
4. Urgent priority messages such as severe weather warnings, severe weather watches and statements, and instructions from civil defense centers during emergency situations.
5. Other information reports, on a periodic basis:
 - i. Winter weather and road conditions.
 - ii. River and flood warnings.
 - iii. Damage Reports.
 - iv. Thirty-day weather forecasts.

6-02. Flood Condition Forecasts.

- a. Requirements. Flood forecasts are required whenever substantial rainfall has fallen above or below Addicks and Barker Reservoirs, considered to be greater than 1/2 inch, or during the evacuation of the flood pool.
- b. Methods. The Corps of Engineers makes the following forecasts with assistance from the National Weather Service:
 1. Predicting Inflow Into the Reservoirs. The Hydrologic Engineering Center (HEC) in Davis, California developed a real time water control software system. The Tulsa District made further developments and improvements to the system. A real-time flood forecasting model was developed by the Fort Worth District. This system is used to predict the inflow into the reservoirs. The forecasting system consists of PRECIP and HEC-HMS models. Both models use a one-hour time interval. Precipitation estimates are available from three main sources: precipitation gages, radar, and satellite. Data from these sources are used by NWS to produce a suite of hydrologic forecasts. Weather Surveillance Radar-1988 Doppler (WSR-88D), also known as Next Generation Weather Radar (NEXRAD), observe the presence and calculate the speed and direction of severe weather. WSR-88D also provides estimated quantitative precipitation amounts.

The NWS increases the accuracy of the WSR-88D quantitative precipitation estimates by a three-stage process. Stage I performs basic quality control of the radar data and converts reflectivity from the individual radar sites to precipitation rates. Stage II refines the quality of the radar data and precipitation estimates. The radar estimates are compared and if different, adjusted to measured rainfall from a variety of rain gauge networks, whose data is ingested at the NWS. Stage III formulates a composite rainfall pattern of bias-corrected estimates made by multiple radar sites.

The hourly precipitation data is obtained from rain gages equipped with data collection platforms (DCPs) and from a variety of ALERT systems maintained by various partner agencies. Daily precipitation data is obtained from Addicks and Barker Reservoirs and also the National Weather Service Advanced Weather Interactive Processing System (AWIPS).

2. Predicting flood levels on Buffalo Bayou. The NWS-WGRFC ingests release information from Barker and Addicks from the USACE Galveston District and combines this information with rainfall estimates and forecasts to generate a forecast of river levels along Buffalo Bayou below the Barker and Addicks Reservoirs. Forecasts are produced at three locations; West

Belt, Piney Point, and Shepherd Drive. Forecasts from the WGRFC are sent to the WFO Houston/Galveston for dissemination to the public. Forecasts are available on the NWS Advanced Hydrologic Prediction Service at <http://water.weather.gov/ahps2/index.php?wfo=hgx>

6-03. Long Range Forecast.

Long-range weather forecasts are made by the NWS Climate Prediction Center and available online at <http://www.cpc.ncep.noaa.gov/>.

6-04. Drought Forecast.

Addicks and Barker are flood risk management reservoirs. They do not impound water except for flood risk management and are normally dry. These reservoirs do not have a drought contingency plan.

VII. WATER CONTROL PLAN

7-01. General Objectives. Construction of Addicks and Barker Reservoirs (a portion of the Buffalo Bayou, Texas project) was authorized by the River and Harbor Act, approved 20 June 1938, and modified by the Flood Control Acts of 11 August 1939, and 3 September 1954, for flood control on Buffalo Bayou for the protection of the City of Houston, Texas.

The Flood Control Act of 1944 provided authority to lease land in Addicks and Barker Reservoirs. Harris County leased 7,468 acres and developed Bear Creek Park for recreational purposes.

P.L. 89-72, Federal Water Project Recreation Act provides for Federal cost sharing in recreation development at completed projects. The City of Houston is planning development of the proposed 10,600 acre Cullen Park under this Act.

P.L. 92-500 requires that all Federal facilities shall be managed, operated and maintained so as to protect and enhance the quality of water and land resources through conformance with applicable Federal, state, interstate and local substantive standards.

7-02. Constraints. Constraints on the operation of Addicks and Barker Reservoirs are many and varied.

a. Spillway Design Flood Impacts. Addicks and Barker Reservoirs were originally designed as detention reservoirs with one controlled and four uncontrolled outlet conduits and no over-flow auxiliary spillways at the ends of the dams. The original design was predicated on the basis that the available freeboard plus the capacity of the gated outlet would prevent the embankments from overtopping. Later modifications (1948 and 1963) combined with the abandonment of the original channel rectification and diversion plan produced a situation where the spillway design flood was within 0.5 feet of flow around the ends of Barker dam and produced flow around the ends of Addicks dam. A preliminary revision to the spillway design flood in 1967 and an approved revision in 1977 both produced flow over the embankments of both dams. The occurrence of this situation could create a condition favorable for considerable property damage to the public and the possible loss of life. Spillway Design Flood Impacts are currently being reanalyzed as part of a Dam Safety Modification Study and this manual will be updated with results from the study after it is reviewed and approved.

b. Upstream Reservoir Impacts. Acquisition of real estate was based on the original design. Presently, pool levels in excess of Government-owned land will damage residential developments adjacent to Government-owned lands

c. Reservoir Release Restrictions. The original design included a downstream rectified channel and diversion channel with a capacity of approximately 18,000 cfs. Present non-damaging channel capacity is approximately 3,000 cfs. Releases, when combined with uncontrolled runoff and outflow from Addicks and Barker Reservoirs, are limited to 2,000 cfs. due to serious embankment problems and impacts to privately owned land. Reservoir gates should only be opened uniformly (symmetrically) to maintain structural integrity of the outfalls.

7-03. Overall Plan For Water Control. Addicks and Barker Reservoirs will be operated to provide maximum downstream flood protection on South Mayde Creek and Buffalo Bayou. Normal system operation will attempt to maintain equal available storage capacity for each reservoir within the constraints relating to the safety of the structure.

7-04. Standing Instructions To Dam Tender. A summary of these instructions is also included in Exhibit B.

a. Normal Operation. The Acting Natural Resource Manager will act as Dam Tender when regulation is required. The duties of the Dam Tender are as follows:

- (1) The Dam Tender will execute all instructions issued by the Reservoir Regulation Section relating to reservoir operations.
- (2) The Dam Tender is to observe and be cognizant of all available hydrologic and meteorological data that is pertinent to the operation of the projects. This data when requested by the Reservoir Regulation Section will be reported by telephone, e-mail or radio.
- (3) The Dam Tender will dispatch personnel to the dam sites to keep the gates under surveillance whenever reservoir pool stages warrants.
- (4) If one inch of rainfall or more falls in 24 hours or less and is recorded at the dam or on the watershed below the dam or if flooding is predicted below the dams, the Dam Tender will contact Reservoir Control for instructions. If an unwarranted delay does ensue, the Dam Tender will proceed to the reservoirs, close the gates, and then contact Reservoir Control personnel.
- (5) When releases are being made, the Dam Tender will monitor downstream conditions. If flow approaches the limiting flow of 2000 cfs at the Piney Point gage, or if one-half inch of rainfall in 24 hours or less occurs downstream or if flooding is predicted below the dams, the Dam Tender will notify the Reservoir Control. If an unwarranted delay does ensue, the Dam Tender will proceed to the reservoirs, close the gates, and then contact Reservoir Control personnel.

(6) The conduit outlet and stilling basin must be visually monitored very closely during all releases and during all high tailwater events. If unusual conditions occur (such as riprap displacement, surging, or submerged outlet) notify Water Management and Dam Safety immediately.

(7) The Dam Tender will notify lessees of land in the reservoirs when advised by the Reservoir Control that flooding of their land is imminent to permit the removal of stock and equipment from pertinent areas.

b. Emergency Operations. Communication between the Dam Tender and the Reservoir Control will be by telephone (primary), cell phone, or by e-mail, with the District radio net serving as a backup system. Emergency operations are to be used if communications fail, the Dam Tender's instructions are as follows:

(1) The Dam Tender will attempt to restore communications as soon as possible.

(2) If 1 inch of rainfall or more occurs in 24 hours or less below the reservoirs and/or flooding is predicted or occurring downstream, the Dam Tender will close all gates on the reservoirs and keep them under surveillance until communications are restored, or an authorized representative of the District arrives, or the induced surcharge regulation schedule dictates releases.

(3) If flood control releases are in progress, flooding is not forecasted and rainfall below the reservoirs is less than one-half inch in 24 hours, then no change in operation will be made until communications are restored or the induced surcharge regulation schedule dictates releases.

(4) If flood control releases are in progress and rainfall below the reservoirs is more than one-half inch in 24 hours or less, or flooding is predicted, the Dam Tender will close all gates on the reservoirs unless the induced surcharge regulation schedules (see paragraph 7-05.b.) are controlling.

(5) If inflow and pool elevation conditions dictate the use of the induced surcharge regulation schedule and instructions from Reservoir Control are unavailable, releases will be made by the Dam Tender in accordance with the induced surcharge regulation schedules shown on plates 7-03 and 7-04. The gates should remain at the maximum opening attained from the induced surcharge regulation schedules until reservoir levels fall to elevation 101 feet NAVD 1988 in Addicks Reservoir and 94.9 feet NAVD 1988 in Barker Reservoir. Then, if the outflow from both reservoirs when combined with the uncontrolled runoff downstream is greater than channel capacity, adjust the gates until the total discharges do not exceed channel capacity and follow the normal operating procedures.

(6) The conduit outlet and stilling basin must be visually monitored very closely during all releases and during all high tailwater events. If unusual conditions occur (such as riprap displacement, surging, or submerged outlet) close all conduit gates immediately and continue efforts to re-establish communications with the district office.

7-05. Flood Control. In keeping with the primary objective of flood control for Addicks and Barker Reservoirs, the general plan for reservoir regulation will be to operate the reservoirs in a manner that will utilize to the maximum extent possible, the available storage to prevent the occurrence of damaging stages on Buffalo Bayou within the limits placed by the constraints on project operations.

a. Normal Flood Control Regulation. Reservoir Control has the responsibility for directing the regulation of Addicks and Barker Reservoirs. Normal conditions are defined to exist when the reservoir pools are not in the range of the induced surcharge schedule.

(1) If flooding on Buffalo Bayou is neither expected nor occurring, the reservoirs will operate with two gates set at one-foot openings to pass normal low flows. This setting will limit the discharge on each reservoir to approximately 100 - 250 cfs.

(2) The gates on both reservoirs will be closed when 1 inch of rainfall occurs over the watershed below the reservoirs in 24 hours or less, or when flooding is predicted downstream.

(3) Keep the gates closed and under surveillance as long as necessary to prevent flooding below the dams. Begin releases in accordance with the paragraph below or in accordance with the induced surcharge schedule if pool elevations exceed 101 feet NAVD 1988 in Addicks or 95.7 feet NAVD 1988 in Barker. Continue these operations until the flood control storage has been evacuated or, in the case of induced surcharge releases, until a peak pool elevation is attained. Initial releases shall be made through two conduit gates until additional discharge capacity is needed.

(4) If inflow and pool elevation conditions do not dictate use of the induced surcharge regulation schedule for the reservoirs and the downstream runoff has receded to non-damaging stages, then open gates gradually to release amounts which, when combined with uncontrolled runoff, will not exceed 2,000 cfs at Piney Point. In order to maintain equal available storage in both reservoirs releases based on available downstream channel capacity will be made at rates necessary to maintain a difference in reservoir storages of no more than 20 percent. If, during the release period, rains in excess of 0.5 inch within 24 hours fall over the watershed below the reservoirs or flooding is predicted, the gates will be closed until the above operations can be resumed.

(5) When the reservoirs are emptied, close gates to normal position of two conduit gates at an opening of 1.0 foot-(releasing 100-250 cfs).

b. Induced Surcharge Flood Control Regulation. At any time the reservoir pool equals or exceeds 101 feet NAVD 1988 in Addicks Reservoir and 95.7 feet NAVD 1988 in Barker Reservoir monitoring of pool elevation should immediately ensue to determine if inflow is causing pool elevation to continue to rise. If inflow and pool elevation conditions dictate, reservoir releases will be made in accordance with the induced surcharge regulation schedules shown on plates 7-03 and 7-04. The gates should remain at the maximum opening attained from the induced surcharges regulation schedules until reservoir levels fall to elevation 101 feet NAVD 1988 in Addicks and 94.9 NAVD 1988 feet in Barker. Then, if the outflow from both reservoirs when combined with the uncontrolled runoff downstream is greater than channel capacity, adjust the gates until the total discharges do not exceed channel capacity and follow the normal operating procedures.

The conduit and stilling basin must be visually monitored very closely during all high releases and during high tailwater events. If unusual conditions occur (such as riprap displacement, surging, or submerged outlet) notify Water Management and Dam Safety immediately.

c. Constraints Regarding Flood Control Operation. Constraints on flood control operation are the same constraints enumerated in paragraph 7-02.

7-06. Recreation. Addicks and Barker Reservoirs are detention reservoirs with a normally dry pool. The lack of permanent storage normally prohibits releases for canoe races and float trips down Buffalo Bayou. The normal dry state of the reservoir area has encouraged local interest in recreational development on the Government-owned land.

a. Land Usage. Harris County has leased 3,085 acres in Addicks Reservoir for Bear Creek Pioneer Park. This land use development includes camping areas, hiking trails, picnic areas, play ground areas, petting zoo, baseball fields, soccer fields, dog park, Precinct 3 Headquarters, County Extension Agent. A Farm and Ranch Club, a Community Center, sports fields and courts, and three 18-hole golf courses with a club house. Use of the pool above elevation 88.9 feet NAVD 1988 for flood control starts to restrict the use of these facilities and creates public relation problems. Harris County has leased 7,800 acres in Barker Reservoir for George Bush Park. This development includes hike and bike trails, picnic areas, play ground areas, baseball fields, soccer fields, model airplane airport, dog park and a shooting range. Use of the pool above elevation 89.2 feet NAVD 1988 for flood control starts to restrict the use of these facilities and creates public relation issues.

The City of Houston, Texas, has leased 9,270 acres in Addicks Reservoir for Cullen Park. This development includes a veladrome and community park. This development will produce similar issues. The city has no leased acreage in Barker Reservoir.

Fort Bend County has leased 1,961 acres in Barker Reservoir. This development includes a day camp for the scouts. This development will produce similar issues.

b. Reservoir Regulation For Special Events. In the late 1980's a request was made of the Galveston District to provide water for a special event on Buffalo Bayou. The district commander honored this request as a way to support the community. Every year since then the district has stored water for certain events by a deviation from the approved Water Control Plan. These events have historically been the Buffalo Bayou Regatta sponsored by the Buffalo Bayou Partnership, Buffalo Bayou Trash Bash and a charity event involving a Houston Rubber Duck Race.

A request for a deviation from the Regulation Manual for Addicks and Barker Reservoirs was granted in April of 1989. The letter of approval, signed by the Chief of Engineering, Southwestern Division (SWD) gave approval to store water in both reservoirs every year for these special events with the understanding that the impoundment of only this amount of water would ensure minimum impact on these projects. It was recommended that a revision be made to the Water Control Manual to address these special requests.

Based on the above authorization, water can be stored to an elevation of 78.9 feet NAVD 1988 in Addicks Reservoir and 79.7 feet NAVD 1988 in Barker Reservoir to support special events without deviation approval. Even though a deviation will not be necessary from SWD to store water up to an elevation of 79 feet NAVD 1988 for these events, Reservoir Control will notify Reservoir Control personnel in SWD of the events prior to initiation. This will serve to keep SWD personnel aware of district involvement with such events and be able to respond to any issues that might arise from district participation. Reservoir regulation for these events will not be allowed to impact the overall mission of the projects.

7-07. Water Quality. Addicks Reservoir does not have an ongoing water quality program at the present time.

7-08. Fish And Wildlife. None.

7-09. Water Supply. None.

7-10. Hydroelectric Power. None.

7-11. Navigation. Addicks and Barker Reservoirs are not navigation projects; however, the trap effect of the reservoir reduces the sediment inflow into the Houston Ship Channel.

7-12. Drought Contingency Plan. Addicks and Barker Reservoirs are kept dry for flood risk management. A Drought Contingency Plan is not applicable to these two reservoirs.

7-13. Flood Emergency Action Plan. Reference" Addicks & Barker Emergency Action Plan, Annex I to Galveston District Emergency Operation Plan", Completion Date: 18 August 2006. This is a stand-alone document. Copies are located in Emergency Management and the Engineering – Construction Division.

Description: This document meets requirements of Federal Guidelines for Dam Safety: Emergency Action Planning for Dam Owners, Engineering Regulations 1130-2-530, and 1110-2-1156 which require an emergency action plan be provided for each Corps of Engineers dam. This Emergency Action Plan for Addicks and Barker Dams is directed at recognizing potential dangers, outlining actions to be taken, and assuring key individuals are aware of their responsibilities and have ready access to a plan of action outlining their roles. This document serves as a ready reference for both Corps personnel and local authorities to identify early signs of potentially dangerous conditions and the subsequent actions to be taken including notification of key personnel, immediate corrective action and evacuation of upstream and downstream areas if necessary. This document describes a plan to be followed by the Galveston District in the event of an impending dam safety emergency at Addicks and Barker Dams that consists of reservoir regulation, advance emergency planning, monitoring of instruments, embankment and foundation surveillance coordination, and warning the resident population of potential or imminent flooding. Notification procedures were developed in accordance with Federal Guidelines for Dam Safety: Emergency Action Planning for Dam Owners and ER 1110-2-101.

7-14. Other. None

7-15. Deviation From Normal Regulations. The District Engineer is occasionally requested to deviate from the normal regulation of the reservoirs. Prior approval for a deviation is obtained from Southwestern Division(SWD)except as noted in section 7-06 subparagraph b and subparagraph a below. Deviation requests usually fall under the following categories:

a. Emergencies. Some emergencies that can be expected are: drowning and other accidents, failure of operation facilities, and flushing of pollution where water quality is not a project purpose. Necessary action under emergency conditions is taken immediately unless such action would create equal or worse conditions. SWD will be

informed as soon as practicable. A written confirmation showing the deviation and conditions will be furnished to Reservoir Control personnel in SWD.

b. Unplanned Minor Deviations. There are unplanned instances that create a temporary need for minor deviations from the normal regulation of the reservoirs, although they are not considered emergencies. Construction activities account for the major portion of the incidents that includes utility stream crossing, bridge work, and major construction contracts. Changes in releases are sometimes necessary for maintenance and inspection. Requests for changes of release rates are generally for a few hours to a few days. Each request is analyzed on its own merits. Consideration is given to upstream watershed conditions, potential flood threat, condition of the reservoirs, and possible alternative measures. In the interest of maintaining good public relations, the requests are complied with, providing there are no adverse effects on the overall operation of the projects for the authorized purposes. Approval for these minor deviations will normally be obtained from Reservoir Control personnel in SWD by telephone. A written confirmation showing the deviation and conditions will be furnished to Reservoir Control personnel in SWD.

c. Planned Deviations. Each condition should be analyzed on its own merits. Sufficient data on flood potential, reservoir and watershed conditions, possible alternative measures, benefits to be expected, and probable effects on other authorized and useful purposes will be presented by e-mail to Reservoir Control personnel in SWD along with recommendations for review and approval.

d. Unplanned Major Deviations. There are unplanned instances that create a temporary need for major deviations from the normal regulation plan and may be considered, but are not, emergencies. Flood control releases account for the major portion of these incidents and typical examples include project pre-releases or exceeding downstream channel capacity, incidents that have a short window of opportunity in an effort to minimize damages or optimize benefits. Requests for changes in release rates generally involve time periods ranging from a few hours to a few days. Each request is analyzed on its own merits. In evaluating the proposed deviation, consideration must be given to upstream watershed conditions, potential flood threat, and condition of the reservoirs, and alternative measures that can be taken. Approval for these major deviations normally will be obtained from the Southwestern Division Office (SWD) by telephone or email. Written confirmation explaining the deviation and its cause will be furnished to the SWD water control manager.

7-16. Rate of Release Change. Changes in release rates will be accomplished in a manner which minimizes damage to the downstream channel. Every reasonable precaution will be made to prevent, if possible, bank sloughing, undercutting, excessive erosion, and danger to human and animal lives. Generally, limit the change in opening

of the sluice gates to no more than one foot per each half hour for each gate, corresponds to approximately 100-250 cfs per change. All gate operations should be symmetrical as practical with and allowable difference in gate openings not to exceed one foot.

7-17. Operation Curves and Tables. Area-Capacity curves for Addicks and Barker Reservoirs are shown on Plates 7-01 and Plate 7-02 respectively. Induced Surcharge Regulation Schedule curves for Addicks and Barker Reservoirs are shown on Plates 7-03 and Plate 7-04 respectively. Outlet rating curves for Addicks and Barker Reservoirs are shown on Plates 7-05 and Plate 7-06 respectively.

Elevation-Area/Capacity tables are included in this manual as Table 7-01 for Addicks Reservoir and in Table 7-02 for Barker Reservoir. These tables are located in this manual in the Supplementary Tables section.

VIII – EFFECT OF WATER CONTROL PLAN

8-01. General.

The main purpose of both Addicks and Barker Reservoirs is flood risk management. The reservoirs also provide recreational benefits and limited habitat for wildlife.

8-02. Flood Control.

- a. Spillway Design Flood. The original spillway design floods were computed in 1940. This design was performed before construction of the reservoirs. The spillway design storm for the study was the 1899 Hearne, Texas storm modified to include the rates of rainfall recorded at Taylor, Texas on the 9th and 10th of September 1921. The average rainfall over a 100 square mile area for this storm was about 30 inches in 72 hours, with a peak intensity of 4.40 inches per hour. For the original design of Addicks Reservoir the peak inflow was estimated to be 50,000 cfs, and the total inflow volume was estimated to be 190,000 acre-feet. For Barker Reservoir the peak inflow was estimated to be 40,300 cfs, and the total inflow volume was estimated to be 214,500 acre-feet.

There are considerable differences between the 1940 design features discussed above and the actual constructed project. Features included in the 1940 design that never were constructed included a levee to prevent Cypress Creek watershed flows from entering Addicks Reservoir, a Reservoir on White Oak Bayou, and a system of canals to convey releases from White Oak Bayou to the San Jacinto River. During construction it was determined to be more economically feasible to increase the capacity of Addicks Reservoir to accommodate Cypress Creek overflows, and the levee was never constructed. A review of reports in 1952 concluded that rising land costs and rapid development made construction of White Oak Reservoir and the canals impracticable.

In 1962 the “Reservoir Regulation Manual for Addicks and Barker Reservoirs” was released with revised spillway design flood information that accounted for the actual constructed project. This 1962 design included all gated conduits, and included the Cypress Creek overflow into Addicks Reservoir, Brays Bayou rectification, Buffalo Bayou Rectification, and White Oak Bayou rectification. Previously prepared unit hydrographs were used to compute volumes of runoff as well as peak flows and times of peaks. Routing was performed using the coefficient method. For additional information reference the 1962 Reservoir Regulation Manual.

In 1977 a restudy of Addicks and Barker Reservoirs was deemed necessary because urbanization was reaching levels in excess of the original 1962 design study. Details of this restudy can be found in “Buffalo Bayou and

Tributaries, Addicks and Barker Reservoirs, Hydrology” dated August 1977. Spillway design flood inflow hydrographs were computed consistent with Standard 1 design criteria as outlined in EC 1110-2-163 “Spillway and Freeboard Requirements for dams”, dated August 1975. In accordance with these criteria the adopted spillway design storm was of probable maximum severity.

The 1977 spillway design rainfall was determined in accordance with the method described in Hydrometeorological Report No. 51, dated September 1976, entitled “Probable Maximum Precipitation Estimates, United States East of the 105h Meridian”. The average rainfall for the spillway design flood was computed as 44.6 inches in 72 hours, with a peak intensity of 11.3 inches. The watershed of Addicks and Barker Reservoirs, Cypress Creek, and Buffalo Bayou above Piney Point were modeled to reflect ultimate conditions using the generalized storm network computation capability of HEC-1. Basins and subbasins were delineated on topographic maps of the study area. Loss rates and unit hydrograph coefficients were based on gages in the Houston area. All stream flow routing was accomplished using the Modified Puls method. Unit hydrographs of storm runoff were computed for each basin using the Clark synthetic unit hydrograph procedure.

The 1977 flood hydrograph adopted for Addicks Reservoir was produced by the spillway design storm centered over Addicks Reservoir Watershed, and the flood hydrograph adopted for Barker Reservoir was produced by the spillway design storm centered over Barker Reservoir Watershed. These centerings were selected because they produce the largest inflow rates into the reservoirs. For Addicks Reservoir the peak inflow was calculated as 294,570 cfs, and the total inflow volume was calculated as 462,145 acre-feet (approximately one-third of the inflow volume is overflow from Cypress Creek). For Barker Reservoir the peak inflow was calculated as 255,779 cfs, and the total inflow volume was calculated as 279,072 acre-feet. For additional information on the calculation of the SDF reference the 1977 hydrology report. The adopted spillway design flood hydrographs for Addicks and Barker are shown on plates 8-01 and 8-02.

The spillway design flood is currently being reanalyzed and this manual will be updated when the updated analysis is completed and approved.

- b. Standard Project Flood (SPF). The original standard project floods were computed in 1940. As with the original Spillway Design Flood the original Standard Project Flood was calculated incorporating features that were never actually constructed. In the original design of Addicks Reservoir the peak inflow was estimated to be 41,000 cfs, and the total inflow volume was estimated to be 146,000 acre-feet. For Barker Reservoir the peak inflow was

estimated to be 32,300 cfs, and the total inflow volume was estimated to be 164,000 acre-feet.

In 1962 the “Reservoir Regulation Manual for Addicks and Barker Reservoirs” was released with revised standard project flood information including the current design at that time. The 1962 design included all gated conduits, and included the Cypress Creek overflow into Addicks Reservoir, Brays Bayou rectification, Buffalo Bayou rectification, and White Oak Bayou rectification. Previously prepared unit hydrographs were used to compute volumes of runoff as well as peak flows and times of peaks. Routing was performed using the coefficient method. For additional information reference the 1962 Reservoir Regulation Manual.

In 1977 standard project flood inflow hydrographs were computed for Addicks and Barker Reservoirs using the same methodology previously described in the spillway design flood section. Rainfall was taken as 50 percent of the spillway design rainfall. For Addicks Reservoir the standard project flood peak inflow has been computed as 124,094 cfs, and the total inflow volume was computed to be 193,956 acre-feet (approximately one-third of the inflow volume is overflow from Cypress Creek). For Barker Reservoir the peak inflow was computed to be 86,961 cfs, and the total inflow volume was computed to be 125,061 acre-feet. The adopted standard project flood hydrographs for Addicks and Barker are shown on plates 8-03 and 8-04.

The standard project flood is currently being reanalyzed and this manual will be updated when the updated analysis is completed and approved.

- c. Other Floods. Tables 8-01 and Table 8-02 include details for the top 10 significant pools for Addicks and Barker Reservoirs.

Table 8-01
Addicks Reservoir - Other Significant Flood Events

DATE	ELEV. (1)	SURFACE AREA IN ACRES	CAPACITY IN ACRE-FEET (2)	% CAPACITY MAX. POOL (3)
9 MAR '92	97.46	9,189	65,264	32.7
30 APR '09	96.90	8,771	60,233	30.2
7 NOV '02	96.45	8,395	56,371	28.2
17 NOV '98	95.70	7,809	50,301	25.2
23 OCT '94	95.63	7,759	49,757	24.9
15 MAY '68	95.16	7,425	46,189	23.1
25 NOV '04	94.88	7,242	44,137	22.1
8 JUL '07	94.82	7,206	43,703	21.9
4 SEP '81	94.25	6,876	39,690	19.9
17 SEP '98	93.95	6,704	37,653	18.9

Table 8-02
Barker Reservoir - Other Significant Flood Events

DATE	ELEV. (1)	SURFACE AREA IN ACRES	CAPACITY IN ACRE-FEET (2)	% CAPACITY MAX. POOL (3)
6 MAR '92	93.60	11,494	66,489	31.7
7 NOV '02	93.24	11,404	62,368	29.8
18 NOV '98	92.31	10,987	51,934	24.8
9 JUL '07	91.85	10,736	46,935	22.4
28 NOV '04	91.69	10,699	45,225	21.6
20 APR '91	91.34	10,425	41,539	19.8
1 MAY '09	91.21	10,347	40,189	19.2
15 MAY '68	90.60	9,528	34,081	16.3
31 MAY '97	90.58	9,495	33,890	16.2
22 OCT '94	90.54	9,427	33,512	16.0

NOTES:

-
- (1) Elevations of water surface are in feet-NAVD (1988, Epoch 2001).
 - (2) One acre-foot of water is one acre of water, one foot deep.
 - (3) Percent of capacity of maximum possible pool before water spills around the ends of the dams.

8-03. Recreation. Recreational areas are available to the public in both Addicks and Barker Reservoirs. The district has approved construction of a variety of recreational and multi-use facilities while protecting and preserving the natural habitat in the reservoirs. The recreation opportunities are numerous which includes a variety of parks, hike and bike trails, nature studies and photography. There are three types of wildlife habitat, open land, woodland and wetlands that harbor many types of animals including birds, deer, reptiles and amphibians. Reservoir pools inundate some of these areas from time to time, but the majority of the recreational facilities are in the upper reaches of the reservoirs and do not flood often. Except for periods of heavy rainfall, the dams do not normally impound water.

8-04. Water Quality. There are no water quality interests associated with Addicks and Barker Reservoirs.

8-05. Fish and Wildlife. There are no fish and wildlife interests associated with Addicks and Barker Reservoirs. The area does provide some limited habitat for game such as deer, fish, and birds. This is not a purpose of the reservoirs but a positive side effect due to the existence of the reservoirs.

8-06. Water Supply. There are no water supply interests associated with Addicks and Barker Reservoirs.

8-07. Hydroelectric Power. There are no hydroelectric interests associated with Addicks and Barker Reservoirs.

8-08. Navigation. There are no navigation interests associated with Addicks and Barker Reservoirs.

8-09. Drought Contingency Plans. There are no drought contingency plans associated with Addicks and Barker Reservoirs.

8-10. Flood Emergency Action Plan. Reference” Addicks & Barker Emergency Action Plan, Annex I to Galveston District Emergency Operation Plan”, Completion Date: 18 August 2006. This is a stand-alone document. Copies are located in Emergency Management and the Engineering – Construction Division.

Description: This document meets requirements of Federal Guidelines for Dam Safety: Emergency Action Planning for Dam Owners, Engineering Regulations 1130-2-530, and 1110-2-1156 which require an emergency action plan be provided for each Corps of Engineers dam. This Emergency Action Plan for Addicks and Barker Dams is directed at recognizing potential dangers, outlining actions to be taken, and assuring key individuals are aware of their responsibilities and have ready access to a plan of action outlining their roles. This document serves as a ready reference for both Corps personnel and local authorities to identify early signs of potentially dangerous conditions and the subsequent actions to be taken. Notification procedures were developed in accordance with Federal Guidelines for Dam Safety: Emergency Action Planning for Dam Owners and ER 1110-2-101.

8-11. Frequencies.

- a. Peak Inflow Probability. Pool probabilities up to the 0.1% were derived using 31-yearly peak pool elevations using Weibull plotting positions and by performing a coincident frequency analysis. This analysis is summarized in the document “Addicks and Barker Pool Probability Analysis, USACE, Galveston District, October 2011”. Data for Sections 8-11a and 8-11b and corresponding plates is taken from this referenced document. The document has been reviewed and approved by the USACE Hydrologic Engineering Center (HEC) in Davis, California.

An assessment of yearly peak pools and inflows show that coincidence of inflow events can occur when there is a residual pool from an antecedent event. Annual peak stage can occur when the antecedent pool is empty or when the antecedent pool contains water due to a prior event. Based on this assessment, a coincident frequency analysis is appropriate using procedures from EM 1110-2-1415. The coincident analysis was used to

define the 2%-, 1%-, 0.2%-, and 0.1% probabilities. Observed data was used for the rest of the frequency curve.

Using procedures from EM 1110-2-1415 a relationship using rainfall frequency inflow hydrographs and varying initial pool elevations as index elevations was established. The following Table 8-03 tabulates the peak inflows associated with various rainfall frequencies.

Table 8-03
Rainfall Frequency and Peak Inflow

Addicks Reservoir		Barker Reservoir	
Percent Chance Exceedance	Flow (cfs)	Percent Chance Exceedance	Flow (cfs)
0.1	97135	0.1	61289
0.2	84597	0.2	52729
1	58699	1	36166
2	49787	2	30500
4	41906	4	25559
10	33023	10	19884
50	18593	50	12397
90	5020	90	4215

b. Pool Elevation Duration and Frequency. Pool elevation-frequency curves are shown on Plate 8-05 for Addicks Reservoir and 8-06 for Barker Reservoir. The pool elevation duration curves are shown on Plate 8-07 for Addicks Reservoir and 8-08 for Barker Reservoir.

c. Key Control Points. The key control point for the operations of the Addicks and Barker Reservoirs is the gage at Piney Point (USGS station number 8073700). A stage-discharge curve for the Piney Point gage is included as plate 4-02. The location of this key control point and other monitoring gages are displayed on Plate 5-01.

8-12. Other Studies.

a. Examples of Regulation. None

b. Channel and Floodway Improvement. None

IX - WATER CONTROL MANAGEMENT

9-01. Responsibilities and Organization.

- a. Corps of Engineers. Addicks and Barker Reservoirs are owned by the U.S. Government and operated by the U.S. Army Corps of Engineers. The Galveston District maintains full responsibility for its day-to-day operation and regulation. Operations and maintenance at the project are the responsibility of the Dam Tender operating under the functional authority of the Galveston District Project Operations Branch directly responsible to the Chief, Operations Divisions. Regulation procedures and criteria are the responsibility of the Chief, Hydrology/Water Control (H&H/WC) Branch operating under the functional authority of the Chief of Engineering-Construction Division. The regulation procedures and criteria to be followed by the Dam Tender are presented in Chapter 7 and are condensed in Exhibit B as Standing Instructions To Dam Tender. An Organization and Communications Chart for Water Management is shown on Plate 9-01.
 1. The Chief, Hydrology and Hydrology/Water Control (H&H/WC) Branch is responsible for preparing and publishing a project Water Control Manual with the water management procedures and criteria for the project in compliance with ER1110-2-240. The manual serves as the standard water control plan for the project and is used at all times except when superseded by an approved deviation as provided for in Chapter 7 or the approved Addicks and Barker Emergency Action Plan in response to Dam failure.
 2. The Dam Tender is responsible for maintaining the project releases and pool levels specified in this Water Control Manual.
 3. The SWD Reservoir Control Center is responsible for reviewing and determining the acceptability of the recommended standard water control plan and deviation requests as needed.
- b. Other Federal Agencies.
 1. The National Weather Service has the responsibility for providing rainfall forecasts needed in water management functions.
 2. The United States Geological Survey has the responsibility for providing stream flow data needed in water management functions.
- c. State and County Agencies. Harris County Flood Control District, as a

part of their emergency operations, provides rainfall data used in water management functions.

- d. Private Organizations. These organizations have no responsibility in the operation of the projects.

9-02. Interagency Coordination.

- a. National Weather Service. The Corps of Engineers participates in a Cooperative Rainfall Network Program with the NWS for collecting rainfall data as described in paragraph 5-01.
- b. U.S. Geological Survey. As detailed in paragraph 5-01, the U. S. Geological Survey (USGS) operates and maintains Corps of Engineers stream gages as a function of the CE/USGS cooperative stream gaging program to provide the stage data, stream flow and rainfall data needed in the Corps' real time water management activities.

9-03. Interagency Agreements. There are no interagency agreements associated with Addicks and Barker Reservoirs.

9-04. Commissions, River Authorities, Compacts and Committees. There are no commissions, river authorities, compacts, or committees associated with Addicks and Barker Reservoirs.

9-05. Non-Federal Hydropower. There are no non-federal hydropower interests associated with Addicks and Barker Reservoirs.

9-06. Reports.

- a. Daily Reservoir Report. This report is prepared by the Hydrology/Water Control (H&H/WC) Branch daily to cover a period of 24 hours. The report provides data for use by personnel whose work requires knowledge pertaining to the regulation of reservoirs, field investigations, stream gaging, construction activities affected by releases from reservoirs, answering public inquiries, and preparing public releases.
- b. Monthly Reservoir Report. The Hydrology/Water Control (H&H/WC) Branch prepares the monthly reservoir reports in accordance with ER 1110-2-240. These reports are a tabular record of regulation for all flood control, navigation, or multiple-purpose storage reservoirs that are under supervision of, or of direct interest to, the District Office. Supplemental information on the regulation of the reservoirs, such as explanation of deviations from approved schedules, are added as a note on the report or as an attachment. These reports are promptly prepared each month

and maintained in such form as to be readily available for transmittal to the Chief of Engineers, or others, upon request.

- c. Flood Damage Report. The Hydrology/Water Control (H&H/WC) Branch submits data to Emergency Operation Center (EOC) to be included in daily situation reports during floods in accordance with ER 500-1-1. The report contains various types of information relative to the floods. Information specifically required for reservoirs are as follows: name of reservoir, reservoir stage, predicted maximum stage and anticipated date, rates of inflow and outflow in cfs, percent of flood control storage utilized to date, and any special information particularly pertinent to the flood situation.
- d. Post Flood Report. This report is prepared in accordance with ER 500-1-1 as soon as practical after a flood causing major damage. The report describes flood emergency operations by the Corps of Engineers and others. Included in summary form are: available hydrologic information, damage estimates, and other engineering data considered to be essential for flood control and flood plain studies or for the review of possible claims against the United States. The report is prepared by the District Office Planning Section. Information derived from field investigations by personnel of the Hydrology and Hydraulics Section along with information compiled by the Hydrology/Water Control (H&H/WC) Branch is also included. The report should be completed within approx. 3 months of the time of flooding, including a statement on the final cost of flood damages occurring
- e. Annual Report. This report is prepared by the Hydraulics and Hydrology/Water Control (H&H/WC) Branch in accordance with ER 1110-2-240. The report contains a summation of the general conditions of the river basins and the individual projects in the District for the preceding fiscal year. The report also presents the activities and accomplishments of the Reservoir Control Section for the past year. The report is forwarded to the SWD Reservoir Control Center for inclusion in the Division's Annual Report.
- f. Summary of Reports. Table 9-01 is a summary of the reports required in the regulation of reservoirs in the Galveston District.

TABLE 9-01
TABULATION OF REPORTS

Name of Report	When Required	Regulation Requiring Report
Daily Reservoir Report	Daily	-
Monthly Reservoir Report	Monthly	EC 1110-2-240
Flood Situation Reports	During Floods	ER 500-1-1
Post Flood Reports	Following a Flood Causing Major Damage	ER 500-1-1
Annual Reports	Annually	EC 1110-2-240

SUPPLEMENTARY TABLES

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
66	6 25	6 26	6 26	6 26	6 26	6 26	6 26	6 26	6 26	6 26
66.1	6 26	6 26	6 26	6 26	6 26	6 26	6 26	6 27	6 27	6 27
66.2	6 27	6 27	6 27	6 27	6 27	6 27	6 27	6 27	6 27	6 27
66.3	6 27	6 27	6 27	6 27	6 28	6 28	6 28	6 28	6 28	6 28
66.4	6 28	6 28	6 28	6 28	6 28	6 28	6 28	6 28	6 28	6 28
66.5	6 29	6 29	6 29	6 29	6 29	6 29	6 29	6 29	6 29	6 29
66.6	7 29	7 29	7 29	7 29	7 29	7 30	7 30	7 30	7 30	7 30
66.7	7 30	7 30	7 30	7 30	7 30	7 30	7 30	7 30	7 30	7 30
66.8	7 31	7 31	7 31	7 31	7 31	7 31	7 31	7 31	7 31	7 31
66.9	7 31	7 31	7 31	7 31	7 31	7 32	7 32	7 32	7 32	7 32
67	7 32	7 32	7 32	7 32	7 32	7 32	7 32	7 32	7 32	7 33
67.1	7 33	7 33	7 33	7 33	7 33	7 33	7 33	7 33	7 33	7 33
67.2	7 33	7 33	7 33	7 34	7 34	7 34	7 34	7 34	7 34	7 34
67.3	7 34	7 34	7 34	7 34	7 34	7 34	7 34	7 34	7 35	7 35
67.4	7 35	7 35	7 35	7 35	7 35	7 35	7 35	7 35	7 35	7 35
67.5	7 35	7 36	7 36	7 36	7 36	7 36	7 36	7 36	7 36	7 36
67.6	7 36	7 36	7 36	7 36	7 36	7 37	7 37	7 37	7 37	7 37
67.7	7 37	7 37	7 37	7 37	7 37	7 37	7 37	7 37	7 37	7 38
67.8	7 38	7 38	7 38	7 38	7 38	7 38	7 38	7 38	7 38	7 38
67.9	7 38	7 38	7 38	7 39	7 39	7 39	7 39	7 39	7 39	7 39

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
68	7 39	7 39	7 39	7 39	7 39	7 39	7 39	7 40	7 40	7 40
68.1	7 40	7 40	7 40	7 40	7 40	7 40	7 40	7 40	7 40	7 40
68.2	7 41	7 41	7 41	7 41	7 41	7 41	7 41	7 41	7 41	7 41
68.3	7 41	7 41	7 41	7 42	8 42	8 42	8 42	8 42	8 42	8 42
68.4	8 42	8 42	8 42	8 42	8 42	8 42	8 42	8 43	8 43	8 43
68.5	8 43	8 43	8 43	8 43	8 43	8 43	8 43	8 43	8 43	8 43
68.6	8 44	8 44	8 44	8 44	8 44	8 44	8 44	8 44	8 44	8 44
68.7	8 44	8 44	8 44	8 45	8 45	8 45	8 45	8 45	8 45	8 45
68.8	8 45	8 45	8 45	8 45	8 45	8 45	8 46	8 46	8 46	8 46
68.9	8 46	8 46	8 46	8 46	8 46	8 46	8 46	8 46	8 46	8 47
69	8 47	8 47	8 47	8 47	8 47	8 47	8 47	8 47	8 47	8 47
69.1	8 47	8 47	8 48	8 48	8 48	8 48	8 48	8 48	8 48	8 48
69.2	8 48	8 48	8 48	8 48	8 49	8 49	8 49	8 49	8 49	8 49
69.3	8 49	8 49	8 49	8 49	8 49	8 49	8 49	8 50	8 50	8 50
69.4	8 50	8 50	8 50	8 50	8 50	8 50	8 50	8 50	8 50	8 50
69.5	8 51	8 51	8 51	8 51	8 51	8 51	8 51	8 51	8 51	8 51
69.6	8 51	8 51	8 52	8 52	8 52	8 52	8 52	8 52	8 52	8 52
69.7	8 52	8 52	8 52	8 52	8 52	8 53	8 53	8 53	8 53	8 53
69.8	8 53	8 53	8 53	8 53	8 53	8 53	8 53	8 54	8 54	8 54
69.9	8 54	8 54	8 54	8 54	8 54	8 54	8 54	8 54	8 54	8 55

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
70	8	8	8	8	8	8	8	8	8	8	8
	55	55	55	55	55	55	55	55	55	55	55
70.1	8	8	8	8	8	8	8	8	8	8	8
	55	55	56	56	56	56	56	56	56	56	56
70.2	8	8	8	8	8	8	8	8	8	8	8
	56	56	56	56	57	57	57	57	57	57	57
70.3	8	8	8	8	8	8	8	8	8	8	8
	57	57	57	57	57	57	57	58	58	58	58
70.4	8	8	8	8	8	8	8	8	8	8	8
	58	58	58	58	58	58	58	58	58	58	59
70.5	8	8	8	8	8	8	8	8	8	8	8
	59	59	59	59	59	59	59	59	59	59	59
70.6	8	8	8	8	8	8	8	8	8	8	8
	60	60	60	60	60	60	60	60	60	60	60
70.7	8	8	8	8	8	8	8	8	8	8	8
	60	60	61	61	61	61	61	61	61	61	61
70.8	8	8	8	8	8	8	8	8	8	8	8
	61	61	61	61	62	62	62	62	62	62	62
70.9	8	9	9	9	9	9	9	9	9	9	9
	62	62	62	62	62	62	62	63	63	63	63
71	9	9	9	9	9	9	9	9	9	9	9
	63	63	63	63	63	63	63	63	64	64	64
71.1	9	9	9	9	9	9	9	9	9	9	9
	64	64	64	64	64	64	64	64	64	64	65
71.2	9	9	9	9	9	9	9	9	9	9	9
	65	65	65	65	65	65	65	65	65	65	65
71.3	9	9	9	9	9	9	9	9	9	9	9
	66	66	66	66	66	66	66	66	66	66	66
71.4	9	9	9	9	9	9	9	9	9	9	9
	66	66	67	67	67	67	67	67	67	67	67
71.5	9	9	9	9	9	9	9	9	9	9	9
	67	67	67	68	68	68	68	68	68	68	68
71.6	9	9	9	9	9	9	9	9	9	9	9
	68	68	68	68	68	68	69	69	69	69	69
71.7	9	9	9	9	9	9	9	9	9	9	9
	69	69	69	69	69	69	69	70	70	70	70
71.8	9	9	9	9	9	9	9	9	9	9	9
	70	70	70	70	70	70	70	70	70	71	71
71.9	9	9	9	9	9	9	9	9	9	9	9
	71	71	71	71	71	71	71	71	71	71	72

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.09
72	9	9	9	9	9	9	9	9	9	9	9
	72	72	72	72	72	72	72	72	72	72	72
72.1	9	9	9	9	9	9	9	9	9	9	9
	73	73	73	73	73	73	73	73	73	73	73
72.2	9	9	9	9	9	9	9	9	9	9	9
	73	74	74	74	74	74	74	74	74	74	74
72.3	9	9	9	9	9	9	9	9	9	9	9
	74	74	75	75	75	75	75	75	75	75	75
72.4	9	9	9	9	9	9	9	9	9	9	9
	75	75	75	76	76	76	76	76	76	76	76
72.5	9	9	9	9	9	9	9	9	9	9	9
	76	76	76	76	77	77	77	77	77	77	77
72.6	9	9	9	9	9	9	9	9	9	9	9
	77	77	77	77	77	77	78	78	78	78	78
72.7	9	9	9	9	9	9	9	9	9	9	9
	78	78	78	78	78	78	78	79	79	79	79
72.8	9	9	9	9	9	9	9	9	9	9	9
	79	79	79	79	79	79	79	79	80	80	80
72.9	9	9	9	9	9	9	9	9	9	9	9
	80	80	80	80	80	80	80	80	80	81	81
73	9	9	9	9	9	9	9	9	9	9	9
	81	81	81	81	81	81	81	81	81	82	82
73.1	9	9	9	9	9	9	9	9	9	9	9
	82	82	82	82	82	82	82	82	82	82	83
73.2	9	9	9	9	9	9	9	9	9	9	9
	83	83	83	83	83	83	83	83	83	83	84
73.3	9	9	9	9	9	9	9	9	9	9	9
	84	84	84	84	84	84	84	84	84	84	84
73.4	9	9	9	9	9	9	9	9	9	9	10
	85	85	85	85	85	85	85	85	85	85	85
73.5	10	10	10	10	10	10	10	10	10	10	10
	86	86	86	86	86	86	86	86	86	86	86
73.6	10	10	10	10	10	10	10	10	10	10	10
	86	87	87	87	87	87	87	87	87	87	87
73.7	10	10	10	10	10	10	10	10	10	10	10
	87	88	88	88	88	88	88	88	88	88	88
73.8	10	10	10	10	10	10	10	10	10	10	10
	88	88	89	89	89	89	89	89	89	89	89
73.9	10	10	10	10	10	10	10	10	10	10	10
	89	89	90	90	90	90	90	90	90	90	90

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
74	10 90	10 90	10 90	10 91	10 91	10 91	10 91	10 91	10 91	10 91
74.1	11 91	11 91	11 92	11 92	11 92	11 92	11 92	11 92	11 92	11 92
74.2	11 92	12 93	12 93	12 93	12 93	12 93	12 93	12 93	12 93	12 93
74.3	12 94	13 94	13 94	13 94	13 94	13 94	13 94	13 95	13 95	13 95
74.4	13 95	14 95	14 95	14 95	14 95	14 96	14 96	14 96	14 96	14 96
74.5	14 96	15 96	15 97	15 97	15 97	15 97	15 97	15 97	15 97	15 98
74.6	16 98	16 98	16 98	16 98	16 98	16 99	16 99	16 99	16 99	17 99
74.7	17 99	17 100	17 100	17 100	17 100	17 100	17 100	17 101	18 101	18 101
74.8	18 101	18 101	18 101	18 102	18 102	18 102	18 102	18 102	19 103	19 103
74.9	19 103	19 103	19 103	19 104	19 104	19 104	20 104	20 104	20 105	20 105
75	20 105	20 105	20 105	20 105	20 106	20 106	20 106	20 106	20 107	20 107
75.1	20 107	21 107	21 107	21 108	21 108	21 108	21 108	21 108	21 109	21 109
75.2	21 109	21 109	21 109	21 110	21 110	21 110	21 110	21 110	21 111	21 111
75.3	21 111	21 111	21 112	21 112	21 112	21 112	21 112	21 113	21 113	21 113
75.4	21 113	21 113	21 114	21 114	22 114	22 114	22 114	22 115	22 115	22 115
75.5	22 115	22 116	22 116	22 116	22 116	22 116	22 117	22 117	22 117	22 117
75.6	22 118	22 118	22 118	22 118	22 118	22 119	22 119	22 119	22 119	22 120
75.7	22 120	22 120	22 120	22 120	22 121	22 121	23 121	23 121	23 122	23 122
75.8	23 122	23 122	23 122	23 123	23 123	23 123	23 123	23 124	23 124	23 124
75.9	23 124	23 125	23 125	23 125	23 125	23 125	23 126	23 126	23 126	23 126

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
76	23 127	23 127	23 127	23 127	23 128	23 128	23 128	23 128	23 128	23 129
76.1	24 129	24 129	24 129	24 130	24 130	24 130	24 130	24 131	24 131	24 131
76.2	24 131	24 132	24 132	24 132	24 132	24 132	24 132	24 133	24 133	24 133
76.3	24 134	24 134	24 134	24 134	24 135	24 135	24 135	24 135	24 136	24 136
76.4	24 138	24 138	24 137	24 137	24 137	24 137	24 138	24 138	24 138	24 138
76.5	24 139	24 139	24 139	24 139	25 140	25 140	25 140	25 140	25 140	25 141
76.6	25 141	25 141	25 141	25 142	25 142	25 142	25 142	25 143	25 143	25 143
76.7	25 143	25 144	25 144	25 144	25 144	25 145	25 145	25 145	25 145	25 146
76.8	25 146	25 146	25 146	25 147	25 147	25 147	25 147	25 148	25 148	25 148
76.9	25 148	25 149	25 149	25 149	25 150	25 150	26 150	26 150	26 151	26 151
77	26 151	26 151	26 152	27 152	27 152	27 152	28 153	28 153	29 153	29 153
77.1	29 154	30 154	30 154	30 155	31 155	31 155	32 156	32 156	32 156	33 157
77.2	33 157	34 157	34 158	35 158	35 158	35 159	36 159	36 159	37 160	37 160
77.3	38 160	38 161	38 161	39 162	39 162	40 162	40 163	41 163	41 164	42 164
77.4	42 164	42 165	43 165	43 166	44 166	44 167	45 167	45 167	46 168	46 168
77.5	47 169	47 169	48 170	48 170	49 171	49 171	50 172	50 172	51 173	51 173
77.6	52 174	52 174	53 175	53 175	54 176	54 176	55 177	55 178	56 178	56 179
77.7	57 179	57 180	58 180	59 181	59 182	60 182	60 183	61 183	61 184	62 185
77.8	62 185	63 186	64 186	64 187	65 188	65 188	66 189	66 190	67 190	68 191
77.9	68 192	69 192	69 193	70 194	70 194	71 195	72 196	72 197	73 197	73 198

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
78	74 199	75 200	76 200	77 201	79 202	80 203	81 203	82 204	83 205	84 206
78.1	86 207	87 208	88 209	89 209	90 210	92 211	93 212	94 213	95 214	97 215
78.2	98 216	99 217	100 218	102 219	103 220	104 221	106 222	107 223	108 224	110 225
78.3	111 226	112 227	114 229	115 230	117 231	118 232	119 233	121 234	122 236	124 237
78.4	125 238	126 239	128 241	129 242	131 243	132 245	134 246	135 247	137 249	138 250
78.5	140 251	141 253	143 254	144 256	146 257	148 259	149 260	151 262	152 263	154 265
78.6	155 266	157 268	159 269	160 271	162 273	164 274	165 276	167 277	169 279	170 281
78.7	172 283	174 284	175 286	177 288	179 290	180 291	182 293	184 295	186 297	187 299
78.8	189 301	191 302	193 304	194 306	196 308	198 310	200 312	202 314	204 316	205 318
78.9	207 320	209 322	211 325	213 327	215 329	217 331	219 333	220 335	222 338	224 340
79	226 342	227 344	228 347	228 349	229 351	230 353	230 356	231 358	232 360	233 363
79.1	233 365	234 367	235 370	235 372	236 374	237 377	238 379	238 382	239 384	240 386
79.2	240 389	241 391	242 394	243 396	243 398	244 401	245 403	245 406	246 408	247 411
79.3	248 413	249 416	249 418	250 421	251 423	251 426	252 428	253 431	254 433	254 436
79.4	255 438	256 441	256 443	257 446	258 448	259 451	259 454	260 456	261 459	262 461
79.5	262 464	263 467	264 469	265 472	265 475	266 477	267 480	268 483	269 485	269 488
79.6	270 491	271 493	272 496	272 499	273 502	274 504	275 507	275 510	276 513	277 515
79.7	278 518	279 521	279 524	280 526	281 529	282 532	282 535	283 538	284 541	285 543
79.8	286 546	286 549	287 552	288 555	289 558	289 561	290 564	291 566	292 569	293 572
79.9	293 575	294 578	295 581	296 584	297 587	297 590	298 593	299 596	300 599	301 602

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.09
80	301 605	302 608	303 611	303 614	304 617	305 620	305 623	306 626	307 629	307 632	307 632
80.1	308 635	309 639	309 642	310 645	311 648	311 651	312 654	313 657	313 660	314 663	314 663
80.2	315 667	316 670	316 673	317 676	318 679	318 682	319 686	320 689	320 692	321 695	321 695
80.3	322 698	322 702	323 705	324 708	324 711	325 715	326 718	326 721	327 724	328 728	328 728
80.4	329 731	329 734	330 738	331 741	331 744	332 747	333 751	333 754	334 757	335 761	335 761
80.5	335 764	336 767	337 771	338 774	338 778	339 781	340 784	340 788	341 791	342 795	342 795
80.6	342 798	343 801	344 805	345 808	345 812	346 815	347 819	347 822	348 826	349 829	349 829
80.7	350 833	350 836	351 840	352 843	352 847	353 850	354 854	355 857	355 861	356 864	356 864
80.8	357 868	357 871	358 875	359 879	360 882	360 886	361 889	362 893	363 897	363 900	363 900
80.9	364 904	365 908	365 911	366 915	367 919	368 922	368 926	369 930	370 933	371 937	371 937
81	371 941	372 944	373 948	374 952	375 956	376 959	377 963	377 967	378 971	379 974	379 974
81.1	380 978	381 982	382 986	383 990	384 994	384 997	385 1001	386 1005	387 1009	388 1013	388 1013
81.2	389 1017	390 1021	391 1025	392 1028	393 1032	393 1036	394 1040	395 1044	396 1048	397 1052	397 1052
81.3	398 1056	399 1060	400 1064	401 1068	402 1072	402 1076	403 1080	404 1084	405 1088	406 1092	406 1092
81.4	407 1096	408 1100	409 1104	410 1109	411 1113	412 1117	412 1121	413 1125	414 1129	415 1133	415 1133
81.5	416 1137	417 1142	418 1146	419 1150	420 1154	421 1158	422 1163	423 1167	424 1171	425 1175	425 1175
81.6	425 1180	426 1184	427 1188	428 1192	429 1197	430 1201	431 1205	432 1210	433 1214	434 1218	434 1218
81.7	435 1223	436 1227	437 1231	438 1236	439 1240	440 1244	441 1249	441 1253	442 1258	443 1262	443 1262
81.8	444 1267	445 1271	446 1275	447 1280	448 1284	449 1289	450 1293	451 1298	452 1302	453 1307	453 1307
81.9	454 1311	455 1316	456 1321	457 1325	458 1330	459 1334	460 1339	461 1343	462 1348	463 1353	463 1353

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
82	464 1357	465 1362	466 1367	468 1371	469 1376	471 1381	472 1385	473 1390	475 1395	476 1400	
82.1	478 1404	479 1409	480 1414	482 1419	483 1424	485 1428	486 1433	487 1438	489 1443	490 1448	
82.2	492 1453	493 1458	495 1463	496 1468	497 1473	499 1478	500 1483	502 1488	503 1493	505 1498	
82.3	506 1503	508 1508	509 1513	510 1518	512 1523	513 1528	515 1533	516 1539	518 1544	519 1549	
82.4	521 1554	522 1559	524 1565	525 1570	527 1575	528 1580	530 1586	531 1591	533 1596	534 1602	
82.5	536 1607	537 1612	539 1618	540 1623	542 1628	543 1634	545 1639	546 1645	548 1650	549 1656	
82.6	551 1661	552 1667	554 1672	555 1678	557 1683	558 1689	560 1695	561 1700	563 1706	564 1711	
82.7	566 1717	567 1723	569 1728	570 1734	572 1740	573 1745	575 1751	577 1757	578 1763	580 1769	
82.8	581 1774	583 1780	584 1786	586 1792	587 1798	589 1804	591 1810	592 1815	594 1821	595 1827	
82.9	597 1833	598 1839	600 1845	602 1851	603 1857	605 1863	606 1869	608 1875	609 1881	611 1888	
83	613 1894	615 1900	617 1906	619 1912	621 1918	623 1925	626 1931	628 1937	630 1943	632 1950	
83.1	634 1956	636 1962	639 1969	641 1975	643 1982	645 1988	647 1995	650 2001	652 2007	654 2014	
83.2	656 2021	658 2027	661 2034	663 2040	665 2047	667 2054	670 2060	672 2067	674 2074	676 2081	
83.3	679 2087	681 2094	683 2101	685 2108	688 2115	690 2122	692 2128	695 2135	697 2142	699 2149	
83.4	701 2156	704 2163	706 2170	708 2177	711 2185	713 2192	715 2199	718 2206	720 2213	722 2220	
83.5	725 2228	727 2235	729 2242	732 2249	734 2257	736 2264	739 2271	741 2279	743 2286	746 2294	
83.6	748 2301	750 2309	753 2316	755 2324	758 2331	760 2339	762 2347	765 2354	767 2362	769 2370	
83.7	772 2377	774 2385	777 2393	779 2400	782 2408	784 2416	786 2424	789 2432	791 2440	794 2448	
83.8	796 2456	799 2464	801 2472	803 2480	806 2488	808 2496	811 2504	813 2512	816 2520	818 2528	
83.9	821 2536	823 2545	826 2553	828 2561	831 2569	833 2578	836 2586	838 2595	841 2603	843 2611	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.09
84	846 2620	849 2628	852 2637	855 2645	859 2654	862 2662	865 2671	868 2680	871 2688	875 2697	
84.1	878 2706	881 2715	884 2724	888 2732	891 2741	894 2750	898 2759	901 2768	904 2777	907 2786	
84.2	911 2795	914 2805	917 2814	921 2823	924 2832	927 2841	931 2851	934 2860	937 2869	941 2879	
84.3	944 2888	948 2898	951 2907	954 2917	958 2926	961 2936	965 2945	968 2955	971 2965	975 2974	
84.4	978 2984	982 2994	985 3004	989 3014	992 3024	995 3034	999 3044	1002 3054	1006 3064	1009 3074	
84.5	1013 3084	1016 3094	1020 3104	1023 3114	1027 3125	1030 3135	1034 3145	1037 3156	1041 3166	1045 3176	
84.6	1048 3187	1052 3197	1055 3208	1058 3218	1062 3229	1066 3240	1069 3250	1073 3261	1077 3272	1080 3283	
84.7	1084 3293	1087 3304	1091 3315	1095 3326	1098 3337	1102 3348	1106 3359	1109 3370	1113 3381	1117 3392	
84.8	1120 3404	1124 3415	1128 3426	1131 3437	1135 3449	1139 3460	1142 3472	1146 3483	1150 3494	1154 3506	
84.9	1157 3518	1161 3529	1165 3541	1169 3552	1172 3564	1176 3576	1180 3588	1184 3599	1187 3611	1191 3623	
85	1195 3635	1199 3647	1203 3659	1207 3671	1211 3683	1215 3695	1219 3708	1223 3720	1227 3732	1231 3744	
85.1	1236 3757	1239 3769	1243 3781	1247 3794	1251 3806	1255 3819	1259 3831	1263 3844	1267 3857	1271 3869	
85.2	1275 3882	1279 3895	1283 3908	1288 3921	1292 3933	1296 3946	1300 3959	1304 3972	1308 3985	1312 3999	
85.3	1316 4012	1321 4025	1325 4038	1329 4051	1333 4065	1337 4078	1341 4091	1346 4105	1350 4118	1354 4132	
85.4	1358 4145	1362 4159	1367 4173	1371 4186	1375 4200	1379 4214	1384 4228	1388 4242	1392 4255	1396 4269	
85.5	1401 4283	1405 4297	1409 4311	1413 4326	1418 4340	1422 4354	1426 4368	1431 4382	1435 4397	1439 4411	
85.6	1444 4426	1448 4440	1452 4454	1457 4469	1461 4484	1465 4498	1470 4513	1474 4528	1479 4542	1483 4557	
85.7	1487 4572	1492 4587	1496 4602	1501 4617	1505 4632	1509 4647	1514 4662	1518 4677	1523 4692	1527 4708	
85.8	1532 4723	1536 4738	1541 4754	1545 4769	1550 4785	1554 4800	1559 4816	1563 4831	1568 4847	1572 4863	
85.9	1577 4878	1581 4894	1586 4910	1590 4926	1595 4942	1600 4958	1604 4974	1609 4990	1613 5006	1618 5022	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)	
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09		
86	1622	1627	1632	1636	1641	1646	1651	1655	1660	1665		
	5038	5055	5071	5087	5104	5120	5137	5153	5170	5186		
86.1	1668	1674	1679	1684	1688	1693	1698	1703	1707	1712		
	5203	5220	5236	5253	5270	5287	5304	5321	5338	5355		
86.2	1717	1722	1727	1731	1736	1741	1746	1751	1756	1760		
	5372	5390	5407	5424	5441	5459	5476	5494	5511	5529		
86.3	1765	1770	1775	1780	1785	1790	1795	1799	1804	1809		
	5546	5564	5582	5600	5617	5635	5653	5671	5689	5707		
86.4	1814	1819	1824	1829	1834	1839	1844	1849	1854	1859		
	5725	5744	5762	5780	5798	5817	5835	5854	5872	5891		
86.5	1864	1869	1874	1879	1884	1889	1894	1899	1904	1909		
	5909	5928	5947	5965	5984	6003	6022	6041	6060	6079		
86.6	1914	1919	1924	1928	1934	1939	1945	1950	1955	1960		
	6098	6117	6137	6156	6175	6195	6214	6233	6253	6272		
86.7	1965	1970	1975	1980	1986	1991	1996	2001	2006	2011		
	6292	6312	6332	6351	6371	6391	6411	6431	6451	6471		
86.8	2017	2022	2027	2032	2037	2043	2048	2053	2058	2064		
	6491	6511	6532	6552	6572	6593	6613	6634	6654	6675		
86.9	2069	2074	2079	2085	2090	2095	2101	2106	2111	2116		
	6695	6716	6737	6758	6779	6800	6821	6842	6863	6884		
87	2122	2127	2133	2138	2144	2149	2155	2161	2166	2172		
	6905	6926	6948	6969	6990	7012	7033	7055	7077	7098		
87.1	2177	2183	2188	2194	2200	2205	2211	2216	2222	2228		
	7120	7142	7164	7186	7207	7229	7252	7274	7296	7318		
87.2	2233	2239	2245	2250	2256	2262	2267	2273	2279	2285		
	7340	7363	7385	7408	7430	7453	7475	7498	7521	7544		
87.3	2290	2296	2302	2307	2313	2319	2325	2331	2336	2342		
	7567	7590	7613	7636	7659	7682	7705	7728	7752	7775		
87.4	2348	2354	2359	2365	2371	2377	2383	2389	2394	2400		
	7799	7822	7846	7869	7893	7917	7940	7964	7988	8012		
87.5	2406	2412	2418	2424	2430	2436	2442	2447	2453	2459		
	8036	8060	8084	8109	8133	8157	8182	8206	8231	8255		
87.6	2465	2471	2477	2483	2489	2495	2501	2507	2513	2519		
	8280	8304	8329	8354	8379	8404	8429	8454	8479	8504		
87.7	2525	2531	2537	2543	2549	2555	2561	2567	2573	2579		
	8529	8555	8580	8605	8631	8656	8682	8708	8733	8759		
87.8	2585	2591	2598	2604	2610	2616	2622	2628	2634	2640		
	8785	8811	8837	8863	8889	8915	8941	8967	8994	9020		
87.9	2647	2653	2659	2665	2671	2677	2684	2690	2696	2702		
	9046	9073	9099	9126	9153	9180	9206	9233	9260	9287		

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.10
88	2708 9314	2714 9341	2720 9368	2727 9396	2733 9423	2739 9450	2745 9478	2751 9505	2757 9533	2763 9560	2763 9560
88.1	2768 9588	2775 9616	2781 9644	2787 9671	2793 9699	2800 9727	2806 9755	2812 9783	2818 9811	2824 9840	2824 9840
88.2	2830 9868	2836 9896	2843 9925	2849 9953	2855 9982	2861 10010	2867 10039	2874 10068	2880 10096	2886 10125	2886 10125
88.3	2892 10154	2898 10183	2905 10212	2911 10241	2917 10270	2923 10299	2930 10329	2936 10358	2942 10387	2948 10417	2948 10417
88.4	2955 10446	2961 10476	2967 10506	2974 10535	2980 10565	2986 10595	2993 10625	2999 10655	3005 10685	3012 10715	3012 10715
88.5	3018 10745	3024 10775	3031 10806	3037 10836	3043 10866	3050 10897	3056 10927	3063 10958	3069 10989	3075 11019	3075 11019
88.6	3082 11050	3088 11081	3095 11112	3101 11143	3108 11174	3114 11205	3121 11236	3127 11267	3134 11299	3140 11330	3140 11330
88.7	3147 11361	3153 11393	3160 11425	3166 11456	3173 11488	3179 11520	3186 11551	3192 11583	3199 11615	3205 11647	3205 11647
88.8	3212 11679	3218 11712	3225 11744	3231 11776	3238 11808	3245 11841	3251 11873	3258 11906	3264 11938	3271 11971	3271 11971
88.9	3278 12004	3284 12037	3291 12070	3298 12102	3304 12135	3311 12169	3318 12202	3324 12235	3331 12268	3338 12302	3338 12302
89	3344 12335	3351 12368	3358 12402	3365 12436	3372 12469	3379 12503	3386 12537	3393 12571	3400 12605	3407 12639	3407 12639
89.1	3414 12673	3421 12707	3428 12741	3435 12776	3442 12810	3449 12844	3456 12879	3463 12913	3470 12948	3477 12983	3477 12983
89.2	3484 13018	3491 13053	3498 13088	3505 13123	3512 13158	3519 13193	3526 13228	3533 13263	3540 13299	3547 13334	3547 13334
89.3	3555 13370	3562 13405	3569 13441	3576 13477	3583 13512	3590 13548	3597 13584	3605 13620	3612 13656	3619 13692	3619 13692
89.4	3626 13729	3633 13765	3641 13801	3648 13838	3655 13874	3662 13911	3669 13947	3677 13984	3684 14021	3691 14058	3691 14058
89.5	3698 14095	3706 14132	3713 14169	3720 14206	3727 14243	3735 14281	3742 14318	3749 14356	3757 14393	3764 14431	3764 14431
89.6	3771 14468	3779 14506	3786 14544	3793 14582	3801 14620	3808 14658	3815 14696	3823 14734	3830 14772	3838 14811	3838 14811
89.7	3845 14849	3852 14888	3860 14926	3867 14965	3875 15004	3882 15042	3889 15081	3897 15120	3904 15159	3912 15198	3912 15198
89.8	3919 15237	3927 15277	3934 15316	3942 15355	3949 15395	3957 15434	3964 15474	3972 15514	3979 15553	3987 15593	3987 15593
89.9	3994 15633	4002 15673	4010 15713	4017 15753	4025 15793	4032 15834	4040 15874	4047 15914	4055 15955	4063 15996	4063 15996

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
90	4070	4077	4084	4091	4098	4105	4113	4120	4127	4134	
	16036	16077	16118	16159	16200	16241	16282	16323	16364	16405	
90.1	4141	4148	4155	4162	4169	4176	4184	4191	4198	4205	
	16447	16488	16530	16571	16613	16655	16697	16738	16780	16822	
90.2	4212	4219	4226	4234	4241	4248	4255	4262	4270	4277	
	16864	16907	16949	16991	17034	17076	17118	17161	17204	17246	
90.3	4284	4291	4298	4306	4313	4320	4327	4335	4342	4349	
	17289	17332	17375	17418	17461	17504	17548	17591	17634	17678	
90.4	4357	4364	4371	4378	4386	4393	4400	4408	4415	4422	
	17721	17765	17809	17852	17896	17940	17984	18028	18072	18116	
90.5	4430	4437	4444	4452	4459	4466	4474	4481	4489	4496	
	18161	18205	18249	18294	18338	18383	18428	18472	18517	18562	
90.6	4503	4511	4518	4526	4533	4540	4548	4556	4563	4570	
	18607	18652	18697	18743	18788	18833	18879	18924	18970	19016	
90.7	4578	4585	4593	4600	4608	4615	4623	4630	4638	4645	
	19061	19107	19153	19199	19245	19291	19337	19384	19430	19476	
90.8	4653	4660	4668	4675	4683	4690	4698	4705	4713	4721	
	19523	19569	19616	19663	19709	19756	19803	19850	19897	19945	
90.9	4728	4736	4743	4751	4758	4766	4774	4781	4789	4797	
	19992	20039	20087	20134	20182	20229	20277	20325	20372	20420	
91	4804	4812	4820	4827	4835	4843	4850	4858	4866	4873	
	20468	20516	20565	20613	20661	20710	20758	20807	20855	20904	
91.1	4881	4889	4897	4904	4912	4920	4928	4935	4943	4951	
	20953	21002	21050	21099	21149	21198	21247	21296	21346	21395	
91.2	4959	4967	4974	4982	4990	4998	5006	5013	5021	5029	
	21445	21494	21544	21594	21644	21694	21744	21794	21844	21894	
91.3	5037	5045	5053	5060	5068	5076	5084	5092	5100	5108	
	21944	21995	22045	22096	22147	22197	22248	22299	22350	22401	
91.4	5116	5124	5131	5139	5147	5155	5163	5171	5179	5187	
	22452	22503	22555	22606	22657	22709	22760	22812	22864	22916	
91.5	5195	5203	5211	5219	5227	5235	5243	5251	5259	5267	
	22968	23020	23072	23124	23176	23228	23281	23333	23386	23438	
91.6	5275	5283	5291	5298	5307	5315	5323	5331	5339	5348	
	23491	23544	23597	23650	23703	23756	23809	23862	23916	23969	
91.7	5356	5364	5372	5380	5388	5396	5404	5412	5421	5429	
	24023	24076	24130	24184	24237	24291	24345	24399	24454	24508	
91.8	5437	5445	5453	5461	5470	5478	5486	5494	5502	5510	
	24562	24617	24671	24726	24780	24835	24890	24945	25000	25055	
91.9	5519	5527	5535	5543	5552	5560	5568	5576	5585	5593	
	25110	25165	25221	25276	25331	25387	25443	25498	25554	25610	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.09
92	5601	5607	5612	5618	5623	5628	5634	5639	5645	5650	5650
	25666	25722	25778	25834	25890	25947	26003	26059	26116	26172	26172
92.1	5656	5661	5667	5672	5678	5683	5689	5694	5700	5705	5705
	26229	26285	26342	26399	26456	26512	26569	26626	26683	26740	26740
92.2	5711	5716	5722	5727	5733	5738	5744	5749	5755	5761	5761
	26797	26854	26911	26969	27026	27083	27141	27198	27256	27313	27313
92.3	5766	5772	5777	5783	5788	5794	5799	5805	5810	5816	5816
	27371	27429	27486	27544	27602	27660	27718	27776	27834	27892	27892
92.4	5822	5827	5833	5838	5844	5849	5855	5861	5866	5872	5872
	27950	28009	28067	28125	28184	28242	28301	28359	28418	28477	28477
92.5	5877	5883	5889	5894	5900	5905	5911	5917	5922	5928	5928
	28535	28594	28653	28712	28771	28830	28889	28948	29007	29067	29067
92.6	5933	5939	5945	5950	5956	5961	5967	5973	5978	5984	5984
	29126	29185	29245	29304	29364	29423	29483	29543	29602	29662	29662
92.7	5990	5995	6001	6007	6012	6018	6024	6029	6035	6041	6041
	29722	29782	29842	29902	29962	30022	30082	30143	30203	30263	30263
92.8	6046	6052	6058	6063	6069	6075	6080	6086	6092	6097	6097
	30324	30384	30445	30505	30566	30627	30688	30748	30809	30870	30870
92.9	6103	6109	6114	6120	6126	6132	6137	6143	6149	6154	6154
	30931	30992	31053	31115	31176	31237	31298	31360	31421	31483	31483
93	6160	6166	6171	6177	6183	6188	6194	6199	6205	6211	6211
	31544	31606	31668	31729	31791	31853	31915	31977	32039	32101	32101
93.1	6216	6222	6228	6233	6239	6245	6250	6256	6261	6267	6267
	32163	32225	32288	32350	32412	32475	32537	32600	32662	32725	32725
93.2	6273	6278	6284	6290	6295	6301	6307	6312	6318	6324	6324
	32788	32850	32913	32976	33039	33102	33165	33228	33291	33355	33355
93.3	6329	6335	6341	6346	6352	6358	6364	6369	6375	6381	6381
	33418	33481	33545	33608	33671	33735	33799	33862	33926	33990	33990
93.4	6386	6392	6398	6403	6409	6415	6421	6426	6432	6438	6438
	34054	34118	34181	34245	34310	34374	34438	34502	34566	34631	34631
93.5	6444	6449	6455	6461	6466	6472	6478	6484	6489	6495	6495
	34695	34760	34824	34889	34953	35018	35083	35148	35212	35277	35277
93.6	6501	6507	6512	6518	6524	6530	6536	6541	6547	6553	6553
	35342	35407	35472	35538	35603	35668	35733	35799	35864	35930	35930
93.7	6559	6564	6570	6576	6582	6588	6593	6599	6605	6611	6611
	35995	36061	36127	36192	36258	36324	36390	36456	36522	36588	36588
93.8	6617	6623	6628	6634	6640	6646	6651	6657	6663	6669	6669
	36654	36720	36787	36853	36919	36986	37052	37119	37185	37252	37252
93.9	6675	6681	6686	6692	6698	6704	6710	6716	6722	6727	6727
	37319	37385	37452	37519	37586	37653	37720	37787	37854	37922	37922

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.10
94	6733	6739	6745	6750	6756	6762	6767	6773	6779	6784	6789
	37989	38056	38124	38191	38259	38326	38394	38462	38530	38597	38665
94.1	6790	6796	6801	6807	6813	6819	6824	6830	6836	6841	6847
	38665	38733	38801	38869	38937	39005	39074	39142	39210	39279	39347
94.2	6847	6853	6859	6864	6870	6876	6882	6887	6893	6899	6904
	39347	39416	39484	39553	39621	39690	39759	39828	39897	39966	40035
94.3	6904	6910	6916	6922	6927	6933	6939	6945	6951	6956	6962
	40035	40104	40173	40242	40311	40381	40450	40519	40589	40658	40728
94.4	6962	6968	6974	6979	6985	6991	6997	7002	7008	7014	7020
	40728	40798	40867	40937	41007	41077	41147	41217	41287	41357	41427
94.5	7020	7026	7031	7037	7043	7049	7055	7060	7066	7072	7078
	41427	41497	41568	41638	41708	41779	41849	41920	41991	42061	42132
94.6	7078	7084	7090	7096	7101	7107	7113	7119	7125	7130	7136
	42132	42203	42274	42345	42416	42487	42558	42629	42700	42771	42843
94.7	7136	7142	7148	7154	7160	7165	7171	7177	7183	7189	7195
	42843	42914	42985	43057	43129	43200	43272	43344	43415	43487	43559
94.8	7195	7201	7206	7212	7218	7224	7230	7236	7242	7248	7253
	43559	43631	43703	43775	43847	43920	43992	44064	44137	44209	44282
94.9	7253	7259	7265	7271	7277	7283	7289	7295	7301	7307	7312
	44282	44354	44427	44499	44572	44645	44718	44791	44864	44937	45010
95	7312	7319	7326	7333	7340	7347	7354	7361	7368	7375	7382
	45010	45083	45156	45230	45303	45376	45450	45523	45597	45671	45745
95.1	7382	7389	7396	7403	7410	7417	7425	7432	7439	7446	7453
	45745	45818	45892	45966	46040	46115	46189	46263	46337	46412	46486
95.2	7453	7460	7467	7474	7481	7488	7495	7502	7509	7516	7523
	46486	46561	46636	46710	46785	46860	46935	47010	47085	47160	47235
95.3	7523	7530	7537	7544	7552	7559	7566	7573	7580	7587	7594
	47235	47310	47386	47461	47537	47612	47688	47764	47839	47915	47991
95.4	7594	7601	7608	7616	7623	7630	7637	7644	7651	7658	7665
	47991	48067	48143	48219	48295	48372	48448	48524	48601	48677	48754
95.5	7665	7673	7680	7687	7694	7701	7708	7716	7723	7730	7737
	48754	48831	48907	48984	49061	49138	49215	49292	49370	49447	49524
95.6	7737	7744	7751	7758	7766	7773	7780	7787	7795	7802	7809
	49524	49602	49679	49757	49834	49912	49990	50067	50145	50223	50301
95.7	7809	7816	7823	7831	7838	7845	7852	7859	7867	7874	7881
	50301	50380	50458	50536	50614	50693	50771	50850	50928	51007	51086
95.8	7881	7888	7896	7903	7910	7917	7925	7932	7939	7947	7954
	51086	51165	51244	51323	51402	51481	51560	51639	51719	51798	51878
95.9	7954	7961	7968	7976	7983	7990	7998	8005	8012	8019	7954
	51878	51957	52037	52117	52196	52276	52356	52436	52516	52596	52676

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.10
96	8027	8035	8043	8051	8059	8067	8075	8083	8092	8100	8108
	52677	52757	52837	52918	52998	53079	53160	53241	53321	53402	53483
96.1	8108	8116	8124	8132	8140	8148	8157	8165	8173	8181	8189
	53483	53565	53646	53727	53808	53890	53971	54053	54135	54216	54298
96.2	8189	8197	8206	8214	8222	8230	8238	8246	8255	8263	8271
	54298	54380	54462	54544	54627	54709	54791	54874	54956	55039	55121
96.3	8271	8279	8287	8296	8304	8312	8320	8329	8337	8345	8353
	55121	55204	55287	55370	55453	55536	55619	55702	55786	55869	55953
96.4	8353	8362	8370	8378	8386	8395	8403	8411	8419	8428	8436
	55953	56036	56120	56203	56287	56371	56455	56539	56623	56708	56792
96.5	8436	8444	8453	8461	8469	8477	8486	8494	8502	8511	8519
	56792	56876	56961	57045	57130	57215	57300	57385	57470	57555	57640
96.6	8519	8527	8536	8544	8552	8561	8569	8577	8586	8594	8603
	57640	57725	57810	57896	57981	58067	58152	58238	58324	58410	58496
96.7	8603	8611	8619	8628	8636	8644	8653	8661	8670	8678	8686
	58496	58582	58668	58754	58841	58927	59013	59100	59187	59273	59360
96.8	8686	8695	8703	8712	8720	8729	8737	8745	8754	8762	8771
	59360	59447	59534	59621	59708	59796	59883	59970	60058	60145	60233
96.9	8771	8779	8788	8796	8805	8813	8821	8830	8838	8847	8855
	60233	60321	60409	60497	60585	60673	60761	60849	60937	61026	61114
97	8855	8863	8870	8877	8884	8891	8899	8906	8913	8920	8927
	61114	61203	61292	61380	61469	61558	61647	61736	61825	61914	62004
97.1	8927	8935	8942	8949	8956	8964	8971	8978	8985	8992	9000
	62004	62093	62182	62272	62361	62451	62540	62630	62720	62810	62900
97.2	9000	9007	9014	9021	9029	9036	9043	9050	9058	9065	9072
	62900	62990	63080	63170	63260	63351	63441	63532	63622	63713	63803
97.3	9072	9080	9087	9094	9101	9109	9116	9123	9130	9138	9145
	63803	63894	63985	64076	64167	64258	64349	64440	64532	64623	64714
97.4	9145	9152	9160	9167	9174	9182	9189	9196	9204	9211	9218
	64714	64806	64897	64989	65081	65173	65264	65356	65448	65540	65633
97.5	9218	9226	9233	9240	9248	9255	9262	9270	9277	9284	9292
	65633	65725	65817	65909	66002	66094	66187	66280	66372	66465	66558
97.6	9292	9299	9306	9314	9321	9328	9336	9343	9351	9358	9365
	66558	66651	66744	66837	66930	67024	67117	67210	67304	67397	67491
97.7	9365	9373	9380	9388	9395	9402	9410	9417	9425	9432	9439
	67491	67585	67678	67772	67866	67960	68054	68148	68242	68337	68431
97.8	9439	9447	9454	9462	9469	9477	9484	9491	9499	9506	9514
	68431	68526	68620	68715	68809	68904	68999	69094	69189	69284	69379
97.9	9514	9521	9529	9536	9544	9551	9558	9566	9573	9581	9589
	69379	69474	69569	69664	69760	69855	69951	70047	70142	70238	70333

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	Capacity (Ac-ft) 0.09
98	9588 70334	9596 70430	9604 70526	9612 70622	9620 70718	9628 70814	9636 70911	9643 71007	9651 71103	9659 71200	
98.1	9667 71297	9675 71393	9683 71490	9691 71587	9699 71684	9707 71781	9715 71878	9723 71975	9731 72073	9738 72170	
98.2	9746 72267	9754 72365	9762 72462	9770 72560	9778 72658	9786 72756	9794 72854	9802 72951	9810 73050	9818 73148	
98.3	9826 73246	9834 73344	9842 73443	9850 73541	9858 73640	9866 73738	9874 73837	9882 73936	9890 74035	9898 74133	
98.4	9906 74232	9914 74332	9922 74431	9930 74530	9938 74629	9946 74729	9954 74828	9962 74928	9970 75028	9978 75127	
98.5	9986 75227	9994 75327	10002 75427	10010 75527	10018 75627	10026 75727	10034 75828	10042 75928	10050 76029	10058 76129	
98.6	10067 76230	10075 76330	10083 76431	10091 76532	10099 76633	10107 76734	10115 76835	10123 76936	10131 77038	10139 77139	
98.7	10147 77240	10155 77342	10164 77444	10172 77545	10180 77647	10188 77749	10196 77851	10204 77953	10212 78055	10220 78157	
98.8	10225 78259	10237 78362	10245 78464	10253 78566	10261 78669	10269 78772	10277 78874	10286 78977	10294 79080	10302 79183	
98.9	10310 79286	10318 79389	10326 79492	10334 79596	10343 79699	10351 79803	10359 79906	10367 80010	10375 80114	10384 80217	
99	10392 80321	10400 80425	10408 80529	10415 80633	10423 80737	10431 80842	10439 80946	10447 81051	10455 81155	10463 81260	
99.1	10471 81364	10479 81469	10486 81574	10494 81679	10502 81784	10510 81889	10518 81994	10526 82099	10534 82204	10542 82310	
99.2	10550 82415	10558 82521	10566 82626	10574 82732	10582 82838	10589 82944	10597 83050	10605 83156	10613 83262	10621 83368	
99.3	10629 83474	10637 83581	10645 83687	10653 83794	10661 83900	10669 84007	10677 84113	10685 84220	10693 84327	10701 84434	
99.4	10709 84541	10717 84648	10725 84756	10733 84863	10741 84970	10749 85078	10757 85185	10765 85293	10773 85400	10781 85508	
99.5	10789 85616	10797 85724	10805 85832	10813 85940	10821 86048	10829 86157	10837 86265	10845 86373	10853 86482	10861 86590	
99.6	10869 86699	10877 86808	10885 86917	10894 87025	10902 87134	10910 87243	10918 87353	10926 87462	10934 87571	10942 87681	
99.7	10950 87790	10958 87900	10966 88009	10974 88119	10982 88229	10990 88338	10999 88448	11007 88558	11015 88669	11023 88779	
99.8	11031 88889	11039 88999	11047 89110	11055 89220	11063 89331	11072 89442	11080 89552	11088 89663	11096 89774	11104 89885	
99.9	11112 89986	11120 90107	11128 90219	11137 90330	11145 90441	11153 90553	11161 90664	11169 90776	11177 90888	11186 91000	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
100	11194 91111	11200 91223	11207 91335	11214 91448	11221 91560	11228 91672	11234 91784	11241 91897	11248 92009	11255 92122
100.1	11261 92234	11268 92347	11275 92460	11282 92572	11288 92685	11295 92798	11302 92911	11309 93024	11316 93137	11322 93250
100.2	11329 93364	11336 93477	11343 93590	11350 93704	11356 93817	11363 93931	11370 94045	11377 94158	11384 94272	11390 94386
100.3	11397 94500	11404 94614	11411 94728	11418 94842	11425 94957	11431 95071	11438 95185	11445 95300	11452 95414	11459 95529
100.4	11466 95643	11472 95758	11479 95873	11486 95987	11493 96102	11500 96217	11507 96332	11513 96447	11520 96563	11527 96678
100.5	11534 96793	11541 96909	11548 97024	11555 97140	11561 97255	11568 97371	11575 97486	11582 97602	11589 97718	11596 97834
100.6	11603 97950	11609 98066	11616 98182	11623 98298	11630 98415	11637 98531	11644 98647	11651 98764	11658 98880	11665 98997
100.7	11671 99114	11678 99230	11685 99347	11692 99464	11699 99581	11706 99698	11713 99815	11720 99932	11727 100050	11734 100167
100.8	11741 100284	11747 100402	11754 100519	11761 100637	11768 100754	11775 100872	11782 100990	11789 101108	11796 101226	11803 101344
100.9	11810 101462	11817 101580	11824 101698	11831 101816	11838 101935	11845 102053	11851 102172	11858 102290	11865 102409	11872 102528
101	11879 102646	11885 102765	11892 102884	11898 103003	11904 103122	11910 103241	11916 103360	11922 103479	11928 103599	11934 103718
101.1	11941 103837	11947 103957	11953 104076	11959 104196	11965 104315	11971 104435	11977 104555	11983 104675	11990 104794	11996 104914
101.2	12002 105034	12008 105154	12014 105275	12020 105395	12027 105515	12033 105635	12039 105756	12045 105876	12051 105997	12057 106117
101.3	12063 106238	12070 106358	12076 106479	12082 106600	12088 106721	12094 106842	12101 106963	12107 107084	12113 107205	12119 107326
101.4	12125 107447	12131 107568	12138 107690	12144 107811	12150 107933	12156 108054	12162 108176	12169 108297	12175 108419	12181 108541
101.5	12187 108663	12193 108785	12199 108907	12206 109029	12212 109151	12218 109273	12224 109395	12231 109517	12237 109640	12243 109762
101.6	12249 109885	12255 110007	12262 110130	12268 110252	12274 110375	12280 110498	12286 110621	12293 110743	12299 110866	12305 110989
101.7	12311 111113	12318 111236	12324 111359	12330 111482	12336 111605	12342 111729	12349 111852	12355 111976	12361 112099	12367 112223
101.8	12374 112347	12380 112471	12386 112594	12392 112718	12399 112842	12405 112966	12411 113090	12417 113214	12424 113339	12430 113463
101.9	12436 113587	12442 113712	12449 113836	12455 113961	12461 114085	12468 114210	12474 114335	12480 114459	12486 114584	12493 114709

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
102	12499	12504	12509	12514	12519	12524	12530	12535	12540	12545	
	114834	114959	115084	115209	115334	115460	115585	115710	115836	115961	
102.1	12550	12555	12560	12565	12571	12576	12581	12586	12591	12596	
	116086	116212	116338	116463	116589	116715	116840	116966	117092	117218	
102.2	12601	12607	12612	12617	12622	12627	12632	12637	12643	12648	
	117344	117470	117596	117722	117849	117975	118101	118227	118354	118480	
102.3	12653	12658	12663	12668	12674	12679	12684	12689	12694	12699	
	118607	118733	118860	118987	119113	119240	119367	119494	119621	119748	
102.4	12704	12710	12715	12720	12725	12730	12735	12741	12746	12751	
	119875	120002	120129	120256	120383	120511	120638	120765	120893	121020	
102.5	12756	12761	12766	12772	12777	12782	12787	12792	12798	12803	
	121148	121275	121403	121531	121658	121786	121914	122042	122170	122298	
102.6	12808	12813	12818	12823	12829	12834	12839	12844	12849	12855	
	122426	122554	122682	122810	122939	123067	123195	123324	123452	123581	
102.7	12860	12865	12870	12875	12881	12886	12891	12896	12901	12907	
	123709	123838	123967	124095	124224	124353	124482	124611	124740	124869	
102.8	12912	12917	12922	12927	12933	12938	12943	12948	12953	12959	
	124998	125127	125256	125385	125515	125644	125773	125903	126032	126162	
102.9	12964	12969	12974	12979	12985	12990	12995	13000	13006	13011	
	126232	126421	126551	126681	126811	126940	127070	127200	127330	127460	
103	13016	13021	13025	13030	13034	13039	13044	13048	13053	13057	
	127591	127721	127851	127981	128112	128242	128372	128503	128633	128764	
103.1	13062	13067	13071	13076	13080	13085	13090	13094	13099	13104	
	128895	129025	129156	129287	129417	129548	129679	129810	129941	130072	
103.2	13108	13113	13117	13122	13127	13131	13136	13141	13145	13150	
	130203	130334	130465	130596	130728	130859	130990	131122	131253	131385	
103.3	13154	13159	13164	13168	13173	13178	13182	13187	13191	13196	
	131516	131648	131779	131911	132043	132174	132306	132438	132570	132702	
103.4	13201	13205	13210	13215	13219	13224	13228	13233	13238	13242	
	132834	132966	133098	133230	133362	133495	133627	133759	133891	134024	
103.5	13247	13252	13256	13261	13266	13270	13275	13280	13284	13289	
	134156	134289	134421	134554	134687	134819	134952	135085	135218	135350	
103.6	13293	13298	13303	13307	13312	13317	13321	13326	13331	13335	
	135483	135616	135749	135882	136015	136149	136282	136415	136548	136682	
103.7	13340	13345	13349	13354	13359	13363	13368	13373	13377	13382	
	136815	136948	137082	137215	137349	137483	137616	137750	137884	138017	
103.8	13387	13391	13396	13401	13405	13410	13415	13419	13424	13429	
	138151	138285	138419	138553	138687	138821	138955	139090	139224	139358	
103.9	13433	13438	13443	13447	13452	13457	13461	13466	13471	13475	
	139432	139567	139701	139835	140030	140165	140299	140434	140568	140703	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
104	13480	13486	13491	13496	13502	13507	13513	13518	13524	13529	
	140838	140973	141108	141243	141378	141513	141648	141783	141918	142053	
104.1	13535	13540	13546	13551	13557	13562	13568	13573	13579	13584	
	142189	142324	142460	142595	142731	142866	143002	143137	143273	143409	
104.2	13590	13595	13601	13606	13612	13617	13623	13628	13634	13639	
	143545	143681	143817	143953	144089	144225	144361	144498	144634	144770	
104.3	13645	13650	13656	13661	13667	13672	13678	13683	13689	13694	
	144907	145043	145180	145316	145453	145590	145726	145863	146000	146137	
104.4	13700	13705	13711	13716	13722	13727	13733	13738	13744	13750	
	146274	146411	146548	146685	146822	146960	147097	147234	147372	147509	
104.5	13755	13761	13766	13772	13777	13783	13788	13794	13799	13805	
	147647	147784	147922	148060	148197	148335	148473	148611	148749	148887	
104.6	13810	13816	13822	13827	13833	13838	13844	13849	13855	13860	
	149025	149163	149301	149439	149578	149716	149855	149993	150131	150270	
104.7	13866	13871	13877	13883	13888	13894	13899	13905	13910	13916	
	150409	150547	150686	150825	150964	151103	151242	151381	151520	151659	
104.8	13921	13927	13933	13938	13944	13949	13955	13960	13966	13972	
	151798	151937	152077	152216	152355	152495	152634	152774	152914	153053	
104.9	13977	13983	13988	13994	13999	14005	14011	14016	14022	14027	
	153193	153333	153473	153613	153753	153893	154033	154173	154313	154453	
105	14033	14039	14044	14050	14055	14061	14067	14072	14078	14084	
	154593	154734	154874	155015	155155	155296	155436	155577	155718	155859	
105.1	14089	14095	14101	14108	14112	14118	14123	14129	14135	14140	
	156000	156141	156282	156423	156564	156705	156846	156987	157129	157270	
105.2	14146	14152	14157	14163	14169	14174	14180	14186	14191	14197	
	157411	157553	157694	157836	157978	158119	158261	158403	158545	158687	
105.3	14203	14208	14214	14220	14225	14231	14237	14242	14248	14254	
	158829	158971	159113	159255	159397	159540	159682	159824	159967	160109	
105.4	14259	14265	14271	14276	14282	14288	14293	14299	14305	14311	
	160252	160395	160537	160680	160823	160966	161108	161251	161394	161538	
105.5	14316	14322	14328	14333	14339	14345	14350	14356	14362	14368	
	161681	161824	161967	162110	162254	162397	162541	162684	162828	162971	
105.6	14373	14379	14385	14390	14396	14402	14408	14413	14419	14425	
	163115	163259	163403	163547	163691	163835	163979	164123	164267	164411	
105.7	14430	14436	14442	14448	14453	14459	14465	14470	14476	14482	
	164555	164700	164844	164988	165133	165278	165422	165567	165712	165856	
105.8	14488	14493	14499	14505	14511	14516	14522	14528	14533	14539	
	166001	166146	166291	166436	166581	166726	166872	167017	167162	167307	
105.9	14545	14551	14556	14562	14568	14574	14579	14585	14591	14597	
	167453	167598	167744	167889	168035	168181	168327	168472	168618	168764	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
106	14602 168910	14610 169056	14617 169202	14624 169349	14631 169495	14639 169641	14646 169788	14653 169934	14660 170081	14668 170227
106.1	14675 170374	14682 170521	14689 170668	14697 170815	14704 170962	14711 171109	14718 171256	14726 171403	14733 171550	14740 171698
106.2	14748 171845	14755 171993	14762 172140	14769 172288	14777 172436	14784 172583	14791 172731	14799 172879	14806 173027	14813 173175
106.3	14820 173324	14828 173472	14835 173620	14842 173769	14850 173917	14857 174066	14864 174214	14872 174363	14879 174512	14886 174660
106.4	14893 174809	14901 174958	14908 175107	14915 175256	14923 175406	14930 175555	14937 175704	14945 175854	14952 176003	14959 176153
106.5	14967 176302	14974 176452	14981 176602	14989 176752	14996 176902	15003 177052	15011 177202	15018 177352	15025 177502	15033 177652
106.6	15040 177803	15047 177953	15055 178104	15062 178254	15069 178405	15077 178556	15084 178706	15091 178857	15099 179008	15106 179159
106.7	15114 179310	15121 179461	15128 179613	15136 179764	15143 179915	15150 180067	15158 180218	15165 180370	15173 180522	15180 180674
106.8	15187 180825	15195 180977	15202 181129	15209 181281	15217 181433	15224 181586	15232 181738	15239 181890	15246 182043	15254 182195
106.9	15261 182348	15269 182500	15276 182653	15283 182806	15291 182959	15298 183112	15306 183265	15313 183418	15320 183571	15328 183724
107	15335 183878	15344 184031	15352 184184	15361 184338	15369 184492	15378 184645	15386 184799	15395 184953	15404 185107	15412 185261
107.1	15421 185415	15429 185570	15438 185724	15446 185878	15455 186033	15463 186187	15472 186342	15480 186497	15489 186652	15498 186807
107.2	15506 186962	15515 187117	15523 187272	15532 187427	15540 187583	15549 187738	15558 187894	15566 188049	15575 188205	15583 188361
107.3	15592 188517	15601 188673	15609 188829	15618 188985	15626 189141	15635 189297	15643 189454	15652 189610	15661 189767	15669 189923
107.4	15678 190080	15687 190237	15695 190394	15704 190551	15712 190708	15721 190865	15730 191022	15738 191180	15747 191337	15756 191495
107.5	15764 191652	15773 191810	15781 191968	15790 192126	15799 192283	15807 192442	15816 192600	15825 192758	15833 192916	15842 193075
107.6	15851 193233	15859 193392	15868 193550	15877 193709	15885 193868	15894 194027	15903 194186	15911 194345	15920 194504	15929 194663
107.7	15937 194822	15946 194982	15955 195141	15963 195301	15972 195461	15981 195620	15990 195780	15998 195940	16007 196100	16016 196260
107.8	16024 196420	16033 196581	16042 196741	16050 196902	16059 197062	16068 197223	16077 197383	16085 197544	16094 197705	16103 197866
107.9	16112 198027	16120 198188	16129 198350	16138 198511	16146 198672	16155 198834	16164 198995	16173 199157	16181 199319	16190 199481

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
108	16199 199643	16206 199805	16213 199967	16220 200129	16227 200291	16235 200454	16242 200616	16249 200778	16256 200941	16263 201104
108.1	16270 201266	16277 201429	16285 201592	16292 201755	16299 201918	16306 202081	16313 202244	16320 202407	16327 202570	16335 202733
108.2	16342 202897	16349 203060	16356 203224	16363 203387	16370 203551	16377 203715	16385 203879	16392 204042	16399 204206	16406 204370
108.3	16413 204535	16420 204699	16428 204863	16435 205027	16442 205192	16449 205356	16456 205521	16464 205685	16471 205850	16478 206015
108.4	16485 206179	16492 206344	16499 206509	16507 206674	16514 206839	16521 207005	16528 207170	16535 207335	16543 207501	16550 207666
108.5	16557 207832	16564 207997	16571 208163	16579 208329	16586 208494	16593 208660	16600 208826	16607 208992	16615 209158	16622 209325
108.6	16629 209491	16636 209657	16644 209824	16651 209990	16658 210157	16665 210323	16672 210490	16680 210657	16687 210824	16694 210990
108.7	16701 211157	16709 211324	16716 211492	16723 211659	16730 211826	16738 211993	16745 212161	16752 212328	16759 212496	16766 212663
108.8	16774 212831	16781 212999	16788 213167	16795 213335	16803 213503	16810 213671	16817 213839	16825 214007	16832 214175	16839 214344
108.9	16846 214512	16854 214681	16861 214849	16868 215018	16875 215187	16883 215355	16890 215524	16897 215693	16904 215862	16912 216031
109	16919 216200	16926 216370	16933 216539	16940 216708	16947 216878	16954 217047	16961 217217	16968 217386	16975 217556	16982 217726
109.1	16989 217896	16996 218066	17003 218236	17010 218406	17017 218576	17024 218746	17031 218916	17038 219087	17045 219257	17052 219428
109.2	17059 219598	17066 219769	17073 219940	17080 220110	17087 220281	17094 220452	17101 220623	17108 220794	17115 220965	17123 221136
109.3	17130 221308	17137 221479	17144 221650	17151 221822	17158 221993	17165 222165	17172 222337	17179 222508	17186 222680	17193 222852
109.4	17200 223024	17207 223196	17214 223368	17221 223540	17228 223713	17235 223885	17242 224057	17249 224230	17257 224402	17264 224575
109.5	17271 224748	17278 224920	17285 225093	17292 225266	17299 225439	17306 225612	17313 225785	17320 225958	17327 226132	17334 226305
109.6	17341 226478	17348 226652	17356 226825	17363 226999	17370 227173	17377 227346	17384 227520	17391 227694	17398 227868	17405 228042
109.7	17412 228216	17419 228390	17427 228564	17434 228739	17441 228913	17448 229087	17455 229262	17462 229437	17469 229611	17476 229786
109.8	17483 229961	17490 230136	17498 230311	17505 230486	17512 230661	17519 230836	17526 231011	17533 231186	17540 231362	17547 231537
109.9	17555 231713	17562 231888	17569 232064	17576 232240	17583 232415	17590 232591	17597 232767	17604 232943	17612 233119	17619 233295

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft) 0	Capacity (Ac-ft) 0.01	Capacity (Ac-ft) 0.02	Capacity (Ac-ft) 0.03	Capacity (Ac-ft) 0.04	Capacity (Ac-ft) 0.05	Capacity (Ac-ft) 0.06	Capacity (Ac-ft) 0.07	Capacity (Ac-ft) 0.08	Capacity (Ac-ft) 0.09	
110	17626	17632	17639	17646	17652	17659	17665	17672	17679	17685	
	233472	233648	233824	234001	234177	234354	234530	234707	234884	235061	
110.1	17692	17699	17705	17712	17718	17725	17732	17738	17745	17751	
	235238	235415	235592	235769	235946	236123	236300	236478	236655	236833	
110.2	17758	17765	17771	17778	17785	17791	17798	17804	17811	17818	
	237010	237188	237365	237543	237721	237899	238077	238255	238433	238611	
110.3	17824	17831	17838	17844	17851	17858	17864	17871	17877	17884	
	238789	238967	239146	239324	239503	239681	239860	240039	240217	240396	
110.4	17891	17897	17904	17911	17917	17924	17931	17937	17944	17951	
	240575	240754	240933	241112	241291	241470	241650	241829	242008	242188	
110.5	17957	17964	17971	17977	17984	17991	17997	18004	18011	18017	
	242367	242547	242727	242906	243086	243266	243446	243626	243806	243986	
110.6	18024	18031	18037	18044	18051	18057	18064	18071	18077	18084	
	244166	244347	244527	244707	244888	245068	245249	245430	245610	245791	
110.7	18091	18097	18104	18111	18117	18124	18131	18137	18144	18151	
	245972	246153	246334	246515	246696	246877	247059	247240	247421	247603	
110.8	18158	18164	18171	18178	18184	18191	18198	18204	18211	18218	
	247785	247966	248148	248330	248511	248693	248875	249057	249239	249421	
110.9	18225	18231	18238	18245	18251	18258	18265	18271	18278	18285	
	249604	249786	249968	250151	250333	250516	250698	250881	251064	251247	
111	18292	18297	18303	18309	18314	18320	18325	18331	18337	18342	
	251429	251612	251795	251978	252162	252345	252528	252711	252895	253078	
111.1	18348	18353	18359	18365	18370	18376	18382	18387	18393	18399	
	253261	253445	253628	253812	253996	254179	254363	254547	254731	254915	
111.2	18404	18410	18415	18421	18427	18432	18438	18444	18449	18455	
	255099	255283	255467	255651	255836	256020	256204	256389	256573	256758	
111.3	18461	18466	18472	18477	18483	18489	18494	18500	18506	18511	
	256942	257127	257312	257496	257681	257866	258051	258236	258421	258606	
111.4	18517	18523	18528	18534	18540	18545	18551	18557	18562	18568	
	258791	258976	259162	259347	259532	259718	259903	260089	260274	260460	
111.5	18574	18579	18585	18591	18596	18602	18608	18613	18619	18625	
	260646	260831	261017	261203	261389	261575	261761	261947	262133	262320	
111.6	18630	18636	18642	18647	18653	18659	18664	18670	18676	18681	
	262506	262692	262879	263065	263251	263438	263625	263811	263998	264185	
111.7	18687	18693	18698	18704	18710	18715	18721	18727	18732	18738	
	264372	264559	264746	264933	265120	265307	265494	265681	265868	266056	
111.8	18744	18749	18755	18761	18767	18772	18778	18784	18789	18795	
	266243	266431	266618	266806	266993	267181	267369	267557	267745	267932	
111.9	18801	18806	18812	18818	18823	18829	18835	18841	18846	18852	
	268120	268308	268497	268685	268873	269061	269250	269438	269626	269815	

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
112	18858 270003	18864 270192	18871 270381	18877 270569	18884 270758	18890 270947	18897 271136	18903 271325	18910 271514	18916 271703
112.1	18923 271892	18929 272082	18936 272271	18942 272460	18949 272650	18956 272839	18962 273029	18969 273219	18975 273408	18982 273598
112.2	18988 273788	18995 273978	19001 274168	19008 274358	19014 274548	19021 274738	19027 274928	19034 275119	19040 275309	19047 275500
112.3	19054 275690	19060 275881	19067 276071	19073 276262	19080 276453	19086 276644	19093 276834	19099 277025	19106 277216	19113 277408
112.4	19119 277599	19126 277790	19132 277981	19139 278173	19145 278364	19152 278555	19158 278747	19165 278939	19172 279130	19178 279322
112.5	19185 279514	19191 279706	19198 279898	19204 280090	19211 280282	19218 280474	19224 280666	19231 280858	19237 281051	19244 281243
112.6	19250 281436	19257 281628	19264 281821	19270 282013	19277 282206	19283 282399	19290 282592	19297 282785	19303 282978	19310 283171
112.7	19316 283364	19323 283557	19329 283750	19336 283944	19343 284137	19349 284331	19356 284524	19362 284718	19369 284911	19376 285105
112.8	19382 285299	19389 285493	19395 285687	19402 285881	19409 286075	19415 286269	19422 286463	19429 286657	19435 286852	19442 287046
112.9	19448 287240	19455 287435	19462 287630	19468 287824	19475 288019	19481 288214	19488 288408	19495 288603	19501 288798	19508 288993
113	19515 289189	19522 289384	19530 289579	19537 289774	19545 289970	19552 290165	19560 290361	19567 290556	19575 290752	19583 290948
113.1	19590 291144	19598 291340	19605 291536	19613 291732	19620 291928	19628 292124	19636 292321	19643 292517	19651 292713	19658 292910
113.2	19666 293107	19673 293303	19681 293500	19689 293697	19696 293894	19704 294091	19711 294288	19719 294485	19727 294682	19734 294880
113.3	19742 295077	19749 295274	19757 295472	19765 295670	19772 295867	19780 296065	19787 296263	19795 296461	19803 296659	19810 296857
113.4	19818 297055	19825 297253	19833 297451	19841 297650	19848 297848	19856 298047	19864 298245	19871 298444	19879 298643	19886 298842
113.5	19894 299041	19902 299240	19909 299439	19917 299638	19925 299837	19932 300036	19940 300236	19948 300435	19955 300635	19963 300834
113.6	19970 301034	19978 301234	19986 301433	19993 301633	20001 301833	20009 302033	20016 302233	20024 302434	20032 302634	20039 302834
113.7	20047 303035	20055 303235	20062 303436	20070 303636	20078 303837	20085 304038	20093 304239	20101 304440	20108 304641	20116 304842
113.8	20124 305043	20131 305244	20139 305446	20147 305647	20154 305849	20162 306050	20170 306252	20177 306454	20185 306656	20193 306857
113.9	20200 307059	20208 307261	20216 307464	20223 307666	20231 307868	20239 308070	20246 308273	20254 308475	20262 308678	20270 308881

Table 7-01

Elevation-Area/Capacity Table - Addicks Reservoir

Elevation (ft) NAVD 1988	Area (ft ²) Capacity (Ac-ft) 0	Area (ft ²) Capacity (Ac-ft) 0.01	Area (ft ²) Capacity (Ac-ft) 0.02	Area (ft ²) Capacity (Ac-ft) 0.03	Area (ft ²) Capacity (Ac-ft) 0.04	Area (ft ²) Capacity (Ac-ft) 0.05	Area (ft ²) Capacity (Ac-ft) 0.06	Area (ft ²) Capacity (Ac-ft) 0.07	Area (ft ²) Capacity (Ac-ft) 0.08	Area (ft ²) Capacity (Ac-ft) 0.09
114	20277 309083	20284 309286	20290 309489	20296 309692	20302 309895	20309 310098	20315 310301	20321 310504	20328 310707	20334 310911
114.1	20340 311114	20346 311318	20353 311521	20358 311725	20365 311928	20372 312132	20378 312336	20384 312539	20390 312743	20397 312947
114.2	20403 313151	20409 313355	20416 313559	20422 313764	20428 313968	20435 314172	20441 314377	20447 314581	20453 314786	20460 314990
114.3	20466 315195	20472 315399	20479 315604	20485 315809	20491 316014	20498 316219	20504 316424	20510 316629	20517 316834	20523 317039
114.4	20529 317244	20536 317450	20542 317655	20548 317861	20555 318066	20561 318272	20567 318477	20573 318683	20580 318889	20586 319095
114.5	20592 319301	20599 319507	20605 319713	20611 319919	20618 320125	20624 320331	20630 320537	20637 320744	20643 320950	20649 321156
114.6	20656 321363	20662 321570	20668 321776	20675 321983	20681 322190	20687 322397	20694 322603	20700 322810	20707 323017	20713 323225
114.7	20719 323432	20726 323639	20732 323846	20738 324054	20745 324261	20751 324468	20757 324676	20764 324884	20770 325091	20776 325299
114.8	20783 325507	20789 325715	20795 325923	20802 326131	20808 326339	20815 326547	20821 326755	20827 326963	20834 327171	20840 327380
114.9	20846 327588	20853 327797	20859 328005	20865 328214	20872 328423	20878 328631	20885 328840	20891 329049	20897 329258	20904 329467
115	20910 329676	20917 329885	20924 330094	20931 330304	20938 330513	20944 330722	20951 330932	20958 331141	20965 331351	20972 331561
115.1	20979 331771	20986 331980	20992 332190	20998 332400	21006 332610	21013 332820	21020 333030	21027 333241	21034 333451	21041 333661
115.2	21047 333872	21054 334082	21061 334293	21068 334504	21075 334714	21082 334925	21089 335136	21096 335347	21103 335558	21109 335769
115.3	21116 335980	21123 336191	21130 336402	21137 336614	21144 336825	21151 337037	21158 337248	21165 337460	21171 337672	21178 337883
115.4	21185 338095	21192 338307	21199 338519	21206 338731	21213 338943	21220 339155	21227 339367	21234 339580	21241 339792	21247 340005
115.5	21254 340217	21261 340430	21268 340642	21275 340855	21282 341068	21289 341281	21296 341494	21303 341707	21310 341920	21317 342133
115.6	21324 342346	21330 342559	21337 342773	21344 342986	21351 343199	21358 343413	21365 343627	21372 343840	21379 344054	21386 344268
115.7	21393 344482	21400 344696	21407 344910	21414 345124	21421 345338	21428 345552	21434 345767	21441 345981	21448 346195	21455 346410
115.8	21462 346625	21469 346839	21476 347054	21483 347269	21490 347484	21497 347699	21504 347914	21511 348129	21518 348344	21525 348559
115.9	21532 348774	21539 348990	21546 349205	21553 349421	21560 349636	21567 349852	21574 350067	21581 350283	21587 350499	21594 350715

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)	
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09				
72	4	4	4	4	4	4	4	4	4	4	4	4	4	4
	0	0	0	0	0	0	0	0	0	0	0	0	0	0
72.1	4	4	4	4	4	4	4	4	4	4	4	4	4	4
	0	0	0	1	1	1	1	1	1	1	1	1	1	1
72.2	4	4	4	4	4	4	4	4	4	4	4	4	4	4
	1	1	1	1	1	1	1	1	1	1	1	1	1	1
72.3	4	4	5	5	5	5	5	5	5	5	5	5	5	5
	1	1	1	1	1	1	1	2	2	2	2	2	2	2
72.4	5	5	5	5	5	5	5	5	5	5	5	5	5	5
	2	2	2	2	2	2	2	2	2	2	2	2	2	2
72.5	5	5	5	5	5	5	5	5	5	5	5	5	5	5
	2	2	2	2	2	2	2	3	3	3	3	3	3	3
72.6	5	5	5	5	5	5	5	5	5	5	5	5	5	5
	3	3	3	3	3	3	3	3	3	3	3	3	3	3
72.7	6	6	6	6	6	6	6	6	6	6	6	6	6	6
	3	3	3	3	3	3	4	4	4	4	4	4	4	4
72.8	6	6	6	6	6	6	6	6	6	6	6	6	6	6
	4	4	4	4	4	4	4	4	4	4	4	4	4	4
72.9	6	6	6	6	6	6	6	6	6	6	6	6	6	6
	4	4	5	5	5	5	5	5	5	5	5	5	5	5
73	6	7	7	7	7	7	7	7	7	7	7	7	7	7
	5	5	5	5	5	5	5	5	5	5	5	5	5	5
73.1	7	7	7	7	7	7	7	7	7	7	7	7	7	7
	6	6	6	6	6	6	6	6	6	6	6	6	6	6
73.2	8	8	8	8	8	8	8	8	8	8	8	8	8	8
	6	7	7	7	7	7	7	7	7	7	7	7	7	7
73.3	9	9	9	9	9	9	9	9	9	9	9	9	9	9
	7	7	7	8	8	8	8	8	8	8	8	8	8	8
73.4	9	9	10	10	10	10	10	10	10	10	10	10	10	10
	8	8	8	8	8	9	9	9	9	9	9	9	9	9
73.5	10	10	10	10	10	11	11	11	11	11	11	11	11	11
	9	9	9	9	9	10	10	10	10	10	10	10	10	10
73.6	11	11	11	11	11	11	12	12	12	12	12	12	12	12
	10	10	10	11	11	11	11	11	11	11	11	11	11	11
73.7	12	12	12	12	12	12	12	13	13	13	13	13	13	13
	11	11	12	12	12	12	12	12	12	12	12	12	12	12
73.8	13	13	13	13	13	13	13	13	14	14	14	14	14	14
	13	13	13	13	13	13	13	13	14	14	14	14	14	14
73.9	14	14	14	14	14	14	14	14	15	15	15	15	15	15
	14	14	14	14	14	15	15	15	15	15	15	15	15	15

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)	
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09		
74	15	15	15	15	15	15	16	16	16	16		
	15	16	16	16	16	16	16	16	17	17		
74.1	16	16	16	16	16	16	17	17	17	17		
	17	17	17	17	17	18	18	18	18	18		
74.2	17	17	17	17	17	18	18	18	18	18		
	19	19	19	19	19	19	20	20	20	20		
74.3	18	18	19	19	19	19	19	19	19	19		
	20	21	21	21	21	21	21	22	22	22		
74.4	20	20	20	20	20	20	20	20	20	21		
	22	22	23	23	23	23	23	24	24	24		
74.5	21	21	21	21	21	21	22	22	22	22		
	24	24	25	25	25	25	26	26	26	26		
74.6	22	22	22	22	23	23	23	23	23	23		
	26	27	27	27	27	28	28	28	28	28		
74.7	23	24	24	24	24	24	24	24	24	25		
	29	29	29	29	29	30	30	30	30	31		
74.8	25	25	25	25	25	26	26	26	26	26		
	31	31	32	32	32	32	33	33	33	33		
74.9	26	26	27	27	27	27	27	27	27	27		
	34	34	34	34	34	35	35	35	36	36		
75	28	28	28	28	28	28	28	28	28	29		
	36	37	37	37	37	38	38	38	38	39		
75.1	29	29	29	29	29	29	29	29	29	30		
	39	39	40	40	40	41	41	41	41	41		
75.2	30	30	30	30	30	30	30	30	30	31		
	42	42	43	43	43	44	44	44	44	45		
75.3	31	31	31	31	31	31	31	32	32	32		
	45	45	46	46	46	47	47	47	47	48		
75.4	32	32	32	32	32	32	33	33	33	33		
	48	49	49	49	50	50	50	51	51	51		
75.5	33	33	33	33	33	34	34	34	34	34		
	51	52	52	52	53	53	53	54	54	54		
75.6	34	34	34	34	34	35	35	35	35	35		
	55	55	56	56	56	57	57	57	58	58		
75.7	35	35	35	36	36	36	36	36	36	36		
	58	59	59	59	60	60	60	61	61	62		
75.8	36	37	37	37	37	37	37	37	37	37		
	62	62	63	63	63	64	64	64	65	65		
75.9	38	38	38	38	38	38	38	38	38	39		
	66	66	66	67	67	67	68	68	69	69		

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)	
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09		
76	39	39	39	39	40	40	40	40	41	41		
	69	70	70	71	71	71	72	72	73	73		
76.1	41	41	41	42	42	42	42	43	43	43		
	73	74	74	75	75	75	76	76	77	77		
76.2	43	44	44	44	44	44	45	45	45	45		
	78	78	78	79	79	80	80	81	81	82		
76.3	46	46	46	46	47	47	47	47	48	48		
	82	83	83	83	84	84	85	85	86	86		
76.4	48	48	49	49	49	49	50	50	50	50		
	87	87	88	88	89	89	90	90	91	91		
76.5	51	51	51	51	52	52	52	52	53	53		
	92	92	93	93	94	94	95	95	96	96		
76.6	53	53	54	54	54	54	55	55	55	56		
	97	97	98	98	99	100	100	101	101	102		
76.7	56	56	56	57	57	57	57	58	58	58		
	102	103	103	104	105	105	106	106	107	107		
76.8	58	59	59	59	60	60	60	60	61	61		
	108	109	109	110	110	111	112	112	113	113		
76.9	61	62	62	62	62	63	63	63	63	64		
	114	115	115	116	116	117	118	118	119	120		
77	64	65	65	66	67	68	68	69	70	71		
	120	121	122	122	123	124	124	125	126	126		
77.1	71	72	73	74	74	75	76	77	78	78		
	127	128	129	129	130	131	131	132	133	134		
77.2	79	80	81	82	82	83	84	85	86	87		
	135	135	136	137	138	139	139	140	141	142		
77.3	87	88	89	90	91	92	92	93	94	95		
	143	144	145	146	146	147	148	149	150	151		
77.4	96	97	98	99	99	100	101	102	103	104		
	152	153	154	155	156	157	158	159	160	161		
77.5	105	106	107	108	109	110	110	111	112	113		
	162	163	164	165	166	167	168	170	171	172		
77.6	114	115	116	117	118	119	120	121	122	123		
	173	174	175	177	178	179	180	181	183	184		
77.7	124	125	126	127	128	129	130	131	132	133		
	185	186	187	189	190	191	193	194	195	197		
77.8	134	135	136	137	138	139	141	142	143	144		
	198	199	201	202	203	205	206	208	209	210		
77.9	145	146	147	148	149	150	151	152	154	155		
	212	213	215	216	218	219	221	222	224	225		

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
78	156	156	157	157	158	159	159	160	160	161	161
	227	228	230	232	233	235	236	238	240	241	241
78.1	161	162	162	163	163	164	165	165	166	166	166
	243	244	246	248	249	251	252	254	256	257	257
78.2	167	167	168	169	169	170	170	171	171	172	172
	259	261	262	264	266	268	269	271	273	274	274
78.3	173	173	174	174	175	175	176	177	177	178	178
	276	278	280	281	283	285	287	288	290	292	292
78.4	178	179	179	180	181	181	182	182	183	184	184
	294	295	297	299	301	303	304	306	308	310	310
78.5	184	185	185	186	187	187	188	188	189	190	190
	312	314	315	317	319	321	323	325	327	329	329
78.6	190	191	191	192	193	193	194	194	195	196	196
	330	332	334	336	338	340	342	344	346	348	348
78.7	196	197	197	198	199	199	200	200	201	202	202
	350	352	354	356	358	360	362	364	366	368	368
78.8	202	203	204	204	205	205	206	207	207	208	208
	370	372	374	376	378	380	382	384	386	388	388
78.9	209	209	210	210	211	212	212	213	214	214	214
	390	392	394	397	399	401	403	405	407	409	409
79	215	216	217	218	219	221	222	223	224	225	225
	411	414	416	418	420	422	425	427	429	431	431
79.1	226	227	229	230	231	232	233	234	236	237	237
	433	436	438	440	443	445	447	450	452	454	454
79.2	238	239	240	241	243	244	245	246	247	249	249
	457	459	461	464	466	469	471	474	476	479	479
79.3	250	251	252	254	255	256	257	258	260	261	261
	481	484	486	489	491	494	496	499	501	504	504
79.4	262	263	265	266	267	268	270	271	272	273	273
	507	509	512	515	517	520	523	525	528	531	531
79.5	275	276	277	278	280	281	282	284	285	286	286
	533	536	539	542	545	547	550	553	556	559	559
79.6	287	289	290	291	293	294	295	297	298	299	299
	562	564	567	570	573	576	579	582	585	588	588
79.7	301	302	303	305	306	307	309	310	311	313	313
	591	594	597	600	603	606	609	612	615	619	619
79.8	314	315	317	318	319	321	322	324	325	326	326
	622	625	628	631	634	638	641	644	647	651	651
79.9	328	329	331	332	333	335	336	338	339	340	340
	654	657	660	664	667	670	674	677	680	684	684

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
80	342	343	344	345	346	347	348	350	351	352	352
	687	691	694	698	701	704	708	711	715	718	718
80.1	353	354	355	356	357	359	360	361	362	363	363
	722	726	729	733	736	740	743	747	751	754	754
80.2	364	365	366	368	369	370	371	372	373	375	375
	758	762	765	769	773	776	780	784	787	791	791
80.3	376	377	378	379	380	382	383	384	385	386	386
	795	799	802	806	810	814	818	821	825	829	829
80.4	387	389	390	391	392	393	394	396	397	398	398
	833	837	841	845	849	853	856	860	864	868	868
80.5	399	400	402	403	404	405	406	408	409	410	410
	872	876	880	884	888	892	897	901	905	909	909
80.6	411	413	414	415	416	417	419	420	421	422	422
	913	917	921	925	929	934	938	942	946	950	950
80.7	424	425	426	427	428	430	431	432	433	435	435
	955	959	963	967	972	976	980	985	989	993	993
80.8	436	437	438	440	441	442	443	445	446	447	447
	998	1,002	1,006	1,011	1,015	1,020	1,024	1,028	1,033	1,037	1,037
80.9	448	450	451	452	454	455	456	457	459	460	460
	1,042	1,046	1,051	1,055	1,060	1,064	1,069	1,073	1,078	1,083	1,083
81	461	464	467	469	472	475	478	480	483	486	486
	1,087	1,092	1,097	1,101	1,106	1,111	1,115	1,120	1,125	1,130	1,130
81.1	489	492	494	497	500	503	506	509	511	514	514
	1,135	1,140	1,145	1,150	1,155	1,160	1,165	1,170	1,175	1,180	1,180
81.2	517	520	523	526	529	532	535	538	540	543	543
	1,185	1,190	1,195	1,201	1,206	1,211	1,217	1,222	1,227	1,233	1,233
81.3	546	549	552	555	558	561	564	567	570	573	573
	1,238	1,244	1,249	1,255	1,260	1,266	1,272	1,277	1,283	1,289	1,289
81.4	576	579	582	586	589	592	595	598	601	604	604
	1,294	1,300	1,306	1,312	1,318	1,324	1,329	1,335	1,341	1,347	1,347
81.5	607	610	613	617	620	623	626	629	632	636	636
	1,354	1,360	1,366	1,372	1,378	1,384	1,391	1,397	1,403	1,409	1,409
81.6	639	642	645	648	652	655	658	661	665	668	668
	1,416	1,422	1,429	1,435	1,442	1,448	1,455	1,461	1,468	1,475	1,475
81.7	671	674	678	681	684	688	691	694	698	701	701
	1,481	1,488	1,495	1,502	1,508	1,515	1,522	1,529	1,536	1,543	1,543
81.8	704	708	711	714	718	721	725	728	731	735	735
	1,550	1,557	1,564	1,571	1,579	1,586	1,593	1,600	1,608	1,615	1,615
81.9	738	742	745	749	752	756	759	763	766	770	770
	1,622	1,630	1,637	1,645	1,652	1,660	1,667	1,675	1,682	1,690	1,690

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
82	773	777	780	784	787	791	794	798	802	805	
	1,698	1,706	1,713	1,721	1,729	1,737	1,745	1,753	1,761	1,769	
82.1	809	812	816	820	823	827	831	834	838	842	
	1,777	1,785	1,793	1,801	1,810	1,818	1,826	1,834	1,843	1,851	
82.2	845	849	853	856	860	864	868	871	875	879	
	1,860	1,868	1,877	1,885	1,894	1,902	1,911	1,920	1,928	1,937	
82.3	883	886	890	894	898	902	905	909	913	917	
	1,946	1,955	1,964	1,973	1,982	1,991	2,000	2,009	2,018	2,027	
82.4	921	925	928	932	936	940	944	948	952	956	
	2,036	2,045	2,055	2,064	2,073	2,083	2,092	2,102	2,111	2,121	
82.5	960	964	967	971	975	979	983	987	991	995	
	2,130	2,140	2,149	2,159	2,169	2,179	2,188	2,198	2,208	2,218	
82.6	999	1,003	1,007	1,011	1,015	1,019	1,023	1,028	1,032	1,036	
	2,228	2,238	2,248	2,258	2,268	2,279	2,289	2,299	2,309	2,320	
82.7	1,040	1,044	1,048	1,052	1,056	1,060	1,064	1,069	1,073	1,077	
	2,330	2,340	2,351	2,361	2,372	2,383	2,393	2,404	2,414	2,425	
82.8	1,081	1,085	1,089	1,094	1,098	1,102	1,106	1,110	1,115	1,119	
	2,436	2,447	2,458	2,469	2,480	2,491	2,502	2,513	2,524	2,535	
82.9	1,123	1,127	1,132	1,136	1,140	1,145	1,149	1,153	1,157	1,162	
	2,546	2,557	2,569	2,580	2,592	2,603	2,614	2,626	2,637	2,649	
83	1,166	1,171	1,176	1,181	1,186	1,191	1,196	1,201	1,206	1,211	
	2,661	2,672	2,684	2,696	2,708	2,720	2,732	2,744	2,756	2,768	
83.1	1,216	1,221	1,226	1,231	1,236	1,242	1,247	1,252	1,257	1,262	
	2,780	2,792	2,804	2,817	2,829	2,841	2,854	2,866	2,879	2,891	
83.2	1,267	1,272	1,278	1,283	1,288	1,293	1,298	1,304	1,309	1,314	
	2,904	2,917	2,929	2,942	2,955	2,968	2,981	2,994	3,007	3,020	
83.3	1,319	1,325	1,330	1,335	1,340	1,346	1,351	1,356	1,362	1,367	
	3,033	3,046	3,060	3,073	3,086	3,100	3,113	3,127	3,141	3,154	
83.4	1,372	1,378	1,383	1,389	1,394	1,399	1,405	1,410	1,416	1,421	
	3,168	3,182	3,195	3,209	3,223	3,237	3,251	3,265	3,279	3,294	
83.5	1,427	1,432	1,438	1,443	1,449	1,454	1,460	1,465	1,471	1,476	
	3,308	3,322	3,336	3,351	3,365	3,380	3,394	3,409	3,424	3,438	
83.6	1,482	1,487	1,493	1,499	1,504	1,510	1,516	1,521	1,527	1,533	
	3,453	3,468	3,483	3,498	3,513	3,528	3,543	3,558	3,574	3,589	
83.7	1,538	1,544	1,550	1,555	1,561	1,567	1,572	1,578	1,584	1,590	
	3,604	3,620	3,635	3,651	3,666	3,682	3,698	3,713	3,729	3,745	
83.8	1,596	1,601	1,607	1,613	1,619	1,625	1,630	1,636	1,642	1,648	
	3,761	3,777	3,793	3,809	3,825	3,841	3,858	3,874	3,890	3,907	
83.9	1,654	1,660	1,666	1,672	1,678	1,684	1,689	1,695	1,701	1,707	
	3,923	3,940	3,957	3,973	3,990	4,007	4,024	4,041	4,058	4,075	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
84	1,713	1,719	1,724	1,729	1,734	1,740	1,745	1,750	1,756	1,761	
	4,092	4,109	4,126	4,143	4,161	4,178	4,195	4,213	4,230	4,248	
84.1	1,766	1,772	1,777	1,782	1,788	1,793	1,798	1,804	1,809	1,815	
	4,266	4,283	4,301	4,319	4,337	4,355	4,373	4,391	4,409	4,427	
84.2	1,820	1,825	1,831	1,836	1,842	1,847	1,853	1,858	1,864	1,869	
	4,445	4,463	4,482	4,500	4,518	4,537	4,555	4,574	4,592	4,611	
84.3	1,874	1,880	1,885	1,891	1,897	1,902	1,908	1,913	1,919	1,924	
	4,630	4,648	4,667	4,686	4,705	4,724	4,743	4,762	4,781	4,801	
84.4	1,930	1,935	1,941	1,947	1,952	1,958	1,963	1,969	1,975	1,980	
	4,820	4,839	4,859	4,878	4,898	4,917	4,937	4,956	4,976	4,996	
84.5	1,986	1,992	1,997	2,003	2,009	2,014	2,020	2,026	2,031	2,037	
	5,016	5,036	5,056	5,076	5,096	5,116	5,136	5,156	5,176	5,197	
84.6	2,043	2,049	2,054	2,060	2,066	2,072	2,077	2,083	2,089	2,095	
	5,217	5,238	5,258	5,279	5,299	5,320	5,341	5,362	5,382	5,403	
84.7	2,101	2,106	2,112	2,118	2,124	2,130	2,136	2,141	2,147	2,153	
	5,424	5,445	5,466	5,488	5,509	5,530	5,551	5,573	5,594	5,616	
84.8	2,159	2,165	2,171	2,177	2,183	2,189	2,195	2,200	2,206	2,212	
	5,637	5,659	5,681	5,702	5,724	5,746	5,768	5,790	5,812	5,834	
84.9	2,218	2,224	2,230	2,236	2,242	2,248	2,254	2,260	2,266	2,272	
	5,856	5,878	5,901	5,923	5,945	5,968	5,990	6,013	6,036	6,058	
85	2,279	2,285	2,291	2,298	2,304	2,311	2,317	2,323	2,330	2,336	
	6,081	6,104	6,127	6,150	6,173	6,196	6,219	6,242	6,265	6,289	
85.1	2,343	2,349	2,356	2,362	2,369	2,375	2,382	2,388	2,395	2,401	
	6,312	6,335	6,359	6,383	6,406	6,430	6,454	6,478	6,502	6,525	
85.2	2,408	2,414	2,421	2,428	2,434	2,441	2,447	2,454	2,461	2,467	
	6,550	6,574	6,598	6,622	6,646	6,671	6,695	6,720	6,744	6,769	
85.3	2,474	2,480	2,487	2,494	2,500	2,507	2,514	2,521	2,527	2,534	
	6,794	6,818	6,843	6,868	6,893	6,918	6,943	6,968	6,994	7,019	
85.4	2,541	2,547	2,554	2,561	2,568	2,575	2,581	2,588	2,595	2,602	
	7,044	7,070	7,095	7,121	7,146	7,172	7,198	7,224	7,250	7,276	
85.5	2,609	2,615	2,622	2,629	2,636	2,643	2,650	2,656	2,663	2,670	
	7,302	7,328	7,354	7,380	7,407	7,433	7,460	7,486	7,513	7,539	
85.6	2,677	2,684	2,691	2,698	2,705	2,712	2,719	2,726	2,733	2,740	
	7,566	7,593	7,620	7,647	7,674	7,701	7,728	7,755	7,782	7,810	
85.7	2,747	2,754	2,761	2,768	2,775	2,782	2,789	2,796	2,803	2,810	
	7,837	7,865	7,892	7,920	7,948	7,975	8,003	8,031	8,059	8,087	
85.8	2,817	2,824	2,831	2,839	2,846	2,853	2,860	2,867	2,874	2,881	
	8,115	8,144	8,172	8,200	8,229	8,257	8,286	8,314	8,343	8,372	
85.9	2,889	2,896	2,903	2,910	2,917	2,925	2,932	2,939	2,946	2,954	
	8,401	8,430	8,459	8,488	8,517	8,546	8,575	8,605	8,634	8,664	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
86	2,961	2,968	2,975	2,982	2,988	2,995	3,002	3,009	3,016	3,023	
	8,693	8,723	8,753	8,782	8,812	8,842	8,872	8,902	8,932	8,962	
86.1	3,030	3,037	3,044	3,051	3,058	3,065	3,072	3,079	3,086	3,093	
	8,993	9,023	9,053	9,084	9,114	9,145	9,176	9,207	9,237	9,268	
86.2	3,100	3,107	3,114	3,121	3,128	3,136	3,143	3,150	3,157	3,164	
	9,299	9,330	9,361	9,393	9,424	9,455	9,487	9,518	9,550	9,581	
86.3	3,171	3,178	3,185	3,193	3,200	3,207	3,214	3,221	3,228	3,236	
	9,613	9,645	9,676	9,708	9,740	9,772	9,804	9,837	9,869	9,901	
86.4	3,243	3,250	3,257	3,264	3,272	3,279	3,286	3,293	3,301	3,308	
	9,933	9,966	9,998	10,031	10,064	10,097	10,129	10,162	10,195	10,228	
86.5	3,315	3,323	3,330	3,337	3,345	3,352	3,359	3,367	3,374	3,381	
	10,261	10,295	10,328	10,361	10,395	10,428	10,462	10,495	10,529	10,563	
86.6	3,389	3,396	3,403	3,411	3,418	3,426	3,433	3,440	3,448	3,455	
	10,597	10,631	10,665	10,699	10,733	10,767	10,801	10,836	10,870	10,905	
86.7	3,463	3,470	3,478	3,485	3,493	3,500	3,508	3,515	3,523	3,530	
	10,939	10,974	11,009	11,043	11,078	11,113	11,148	11,183	11,219	11,254	
86.8	3,538	3,545	3,553	3,560	3,568	3,575	3,583	3,591	3,598	3,606	
	11,289	11,325	11,360	11,396	11,431	11,467	11,503	11,539	11,575	11,611	
86.9	3,613	3,621	3,629	3,636	3,644	3,651	3,659	3,667	3,674	3,682	
	11,647	11,683	11,719	11,755	11,792	11,828	11,865	11,901	11,938	11,975	
87	3,690	3,699	3,708	3,717	3,727	3,736	3,745	3,754	3,764	3,773	
	12,012	12,049	12,086	12,123	12,160	12,197	12,235	12,272	12,310	12,348	
87.1	3,782	3,792	3,801	3,810	3,820	3,829	3,838	3,848	3,857	3,867	
	12,385	12,423	12,461	12,499	12,537	12,576	12,614	12,652	12,691	12,730	
87.2	3,876	3,885	3,895	3,904	3,914	3,923	3,933	3,942	3,952	3,961	
	12,768	12,807	12,846	12,885	12,924	12,963	13,003	13,042	13,081	13,121	
87.3	3,971	3,980	3,990	3,999	4,009	4,019	4,028	4,038	4,047	4,057	
	13,161	13,200	13,240	13,280	13,320	13,360	13,401	13,441	13,481	13,522	
87.4	4,067	4,076	4,086	4,096	4,105	4,115	4,125	4,135	4,144	4,154	
	13,563	13,603	13,644	13,685	13,726	13,767	13,808	13,850	13,891	13,932	
87.5	4,164	4,174	4,183	4,193	4,203	4,213	4,223	4,232	4,242	4,252	
	13,974	14,016	14,058	14,099	14,141	14,183	14,226	14,268	14,310	14,353	
87.6	4,262	4,272	4,282	4,292	4,302	4,312	4,321	4,331	4,341	4,351	
	14,395	14,438	14,481	14,524	14,567	14,610	14,653	14,696	14,739	14,783	
87.7	4,361	4,371	4,381	4,391	4,401	4,411	4,422	4,432	4,442	4,452	
	14,826	14,870	14,914	14,958	15,002	15,046	15,090	15,134	15,179	15,223	
87.8	4,462	4,472	4,482	4,492	4,502	4,513	4,523	4,533	4,543	4,553	
	15,268	15,312	15,357	15,402	15,447	15,492	15,537	15,582	15,628	15,673	
87.9	4,564	4,574	4,584	4,594	4,605	4,615	4,625	4,635	4,646	4,656	
	15,719	15,765	15,810	15,856	15,902	15,948	15,995	16,041	16,087	16,134	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
88	4,666	4,678	4,690	4,702	4,714	4,726	4,738	4,750	4,762	4,774	
	16,180	16,227	16,274	16,321	16,368	16,415	16,463	16,510	16,558	16,605	
88.1	4,786	4,798	4,811	4,823	4,835	4,847	4,859	4,871	4,883	4,896	
	16,653	16,701	16,749	16,797	16,845	16,894	16,942	16,991	17,040	17,089	
88.2	4,908	4,920	4,932	4,945	4,957	4,969	4,981	4,994	5,006	5,018	
	17,138	17,187	17,236	17,286	17,335	17,385	17,434	17,484	17,534	17,584	
88.3	5,031	5,043	5,056	5,068	5,080	5,093	5,105	5,118	5,130	5,143	
	17,635	17,685	17,736	17,786	17,837	17,888	17,939	17,990	18,041	18,092	
88.4	5,155	5,168	5,180	5,193	5,206	5,218	5,231	5,243	5,256	5,269	
	18,144	18,196	18,247	18,299	18,351	18,403	18,456	18,508	18,560	18,613	
88.5	5,281	5,294	5,307	5,320	5,332	5,345	5,358	5,371	5,383	5,396	
	18,666	18,719	18,772	18,825	18,878	18,931	18,985	19,039	19,092	19,146	
88.6	5,409	5,422	5,435	5,448	5,461	5,473	5,486	5,499	5,512	5,525	
	19,200	19,254	19,309	19,363	19,418	19,472	19,527	19,582	19,637	19,692	
88.7	5,538	5,551	5,564	5,577	5,590	5,603	5,616	5,629	5,643	5,656	
	19,748	19,803	19,859	19,914	19,970	20,026	20,082	20,138	20,195	20,251	
88.8	5,669	5,682	5,695	5,708	5,721	5,735	5,748	5,761	5,774	5,788	
	20,308	20,365	20,422	20,479	20,536	20,593	20,650	20,708	20,766	20,823	
88.9	5,801	5,814	5,828	5,841	5,854	5,868	5,881	5,894	5,908	5,921	
	20,881	20,940	20,998	21,056	21,115	21,173	21,232	21,291	21,350	21,409	
89	5,935	5,958	5,982	6,006	6,030	6,053	6,077	6,101	6,125	6,149	
	21,468	21,528	21,587	21,647	21,707	21,768	21,829	21,889	21,951	22,012	
89.1	6,174	6,198	6,222	6,246	6,270	6,295	6,319	6,344	6,368	6,393	
	22,074	22,135	22,198	22,260	22,322	22,385	22,448	22,512	22,575	22,639	
89.2	6,417	6,442	6,466	6,491	6,516	6,541	6,566	6,590	6,615	6,640	
	22,703	22,767	22,832	22,897	22,962	23,027	23,093	23,158	23,224	23,291	
89.3	6,665	6,691	6,716	6,741	6,766	6,791	6,817	6,842	6,867	6,893	
	23,357	23,424	23,491	23,558	23,626	23,694	23,762	23,830	23,898	23,967	
89.4	6,918	6,944	6,970	6,995	7,021	7,047	7,073	7,098	7,124	7,150	
	24,036	24,106	24,175	24,245	24,315	24,385	24,456	24,527	24,598	24,669	
89.5	7,176	7,202	7,228	7,254	7,281	7,307	7,333	7,359	7,386	7,412	
	24,741	24,813	24,885	24,957	25,030	25,103	25,176	25,250	25,323	25,397	
89.6	7,439	7,465	7,492	7,518	7,545	7,572	7,598	7,625	7,652	7,679	
	25,472	25,546	25,621	25,696	25,771	25,847	25,923	25,999	26,075	26,152	
89.7	7,706	7,733	7,760	7,787	7,814	7,841	7,868	7,896	7,923	7,950	
	26,229	26,306	26,384	26,461	26,539	26,618	26,696	26,775	26,854	26,933	
89.8	7,978	8,005	8,033	8,060	8,088	8,115	8,143	8,171	8,199	8,226	
	27,013	27,093	27,173	27,254	27,334	27,415	27,497	27,578	27,660	27,742	
89.9	8,254	8,282	8,310	8,338	8,366	8,394	8,423	8,451	8,479	8,507	
	27,825	27,907	27,990	28,073	28,157	28,241	28,325	28,409	28,494	28,579	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
90	8,536	8,552	8,568	8,584	8,600	8,616	8,632	8,649	8,665	8,681	8,681
	28,664	28,749	28,835	28,921	29,007	29,093	29,179	29,265	29,352	29,439	29,439
90.1	8,697	8,714	8,730	8,746	8,762	8,779	8,795	8,811	8,828	8,844	8,844
	29,526	29,613	29,700	29,787	29,875	29,963	30,050	30,138	30,227	30,315	30,315
90.2	8,861	8,877	8,893	8,910	8,926	8,943	8,959	8,976	8,992	9,009	9,009
	30,404	30,492	30,581	30,670	30,759	30,849	30,938	31,028	31,118	31,208	31,208
90.3	9,025	9,042	9,058	9,075	9,092	9,108	9,125	9,141	9,158	9,175	9,175
	31,298	31,388	31,479	31,569	31,660	31,751	31,842	31,934	32,025	32,117	32,117
90.4	9,191	9,208	9,225	9,242	9,258	9,275	9,292	9,309	9,326	9,342	9,342
	32,209	32,301	32,393	32,485	32,578	32,670	32,763	32,856	32,949	33,043	33,043
90.5	9,359	9,376	9,393	9,410	9,427	9,444	9,461	9,478	9,495	9,511	9,511
	33,136	33,230	33,324	33,418	33,512	33,606	33,701	33,795	33,890	33,985	33,985
90.6	9,526	9,546	9,563	9,580	9,597	9,614	9,631	9,648	9,665	9,682	9,682
	34,081	34,176	34,271	34,367	34,463	34,559	34,655	34,752	34,848	34,945	34,945
90.7	9,699	9,716	9,734	9,751	9,768	9,785	9,802	9,820	9,837	9,854	9,854
	35,042	35,139	35,236	35,334	35,431	35,529	35,627	35,725	35,823	35,922	35,922
90.8	9,872	9,889	9,906	9,924	9,941	9,958	9,976	9,993	10,011	10,028	10,028
	36,020	36,119	36,218	36,317	36,417	36,516	36,616	36,716	36,816	36,916	36,916
90.9	10,045	10,063	10,080	10,098	10,115	10,133	10,150	10,168	10,186	10,203	10,203
	37,016	37,117	37,218	37,318	37,420	37,521	37,622	37,724	37,826	37,927	37,927
91	10,221	10,227	10,233	10,239	10,245	10,251	10,257	10,263	10,269	10,275	10,275
	38,030	38,132	38,234	38,336	38,439	38,541	38,644	38,747	38,849	38,952	38,952
91.1	10,281	10,287	10,293	10,299	10,305	10,311	10,317	10,323	10,329	10,335	10,335
	39,055	39,157	39,260	39,363	39,466	39,569	39,673	39,776	39,879	39,982	39,982
91.2	10,341	10,347	10,353	10,359	10,365	10,371	10,377	10,383	10,389	10,395	10,395
	40,086	40,189	40,293	40,396	40,500	40,604	40,707	40,811	40,915	41,019	41,019
91.3	10,401	10,407	10,413	10,419	10,425	10,431	10,437	10,444	10,450	10,456	10,456
	41,123	41,227	41,331	41,435	41,539	41,644	41,748	41,852	41,957	42,061	42,061
91.4	10,462	10,468	10,474	10,480	10,486	10,492	10,498	10,504	10,510	10,516	10,516
	42,166	42,271	42,375	42,480	42,585	42,690	42,795	42,900	43,005	43,110	43,110
91.5	10,522	10,528	10,535	10,541	10,547	10,553	10,559	10,565	10,571	10,577	10,577
	43,215	43,320	43,426	43,531	43,637	43,742	43,848	43,953	44,059	44,165	44,165
91.6	10,583	10,589	10,595	10,602	10,608	10,614	10,620	10,626	10,632	10,638	10,638
	44,270	44,376	44,482	44,588	44,694	44,800	44,907	45,013	45,119	45,225	45,225
91.7	10,644	10,650	10,657	10,663	10,669	10,675	10,681	10,687	10,693	10,699	10,699
	45,332	45,438	45,545	45,651	45,758	45,865	45,972	46,078	46,185	46,292	46,292
91.8	10,705	10,712	10,718	10,724	10,730	10,736	10,742	10,748	10,755	10,761	10,761
	46,399	46,506	46,614	46,721	46,828	46,935	47,043	47,150	47,258	47,365	47,365
91.9	10,767	10,773	10,779	10,785	10,791	10,798	10,804	10,810	10,816	10,822	10,822
	47,473	47,581	47,688	47,796	47,904	48,012	48,120	48,228	48,336	48,444	48,444

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
92	10,828	10,834	10,839	10,844	10,849	10,854	10,859	10,864	10,869	10,874	10,874
	48,553	48,661	48,769	48,878	48,986	49,095	49,203	49,312	49,421	49,529	49,529
92.1	10,879	10,885	10,890	10,895	10,900	10,905	10,910	10,915	10,920	10,925	10,925
	49,638	49,747	49,856	49,965	50,074	50,183	50,292	50,401	50,510	50,619	50,619
92.2	10,931	10,936	10,941	10,946	10,951	10,956	10,961	10,966	10,972	10,977	10,977
	50,729	50,838	50,947	51,057	51,166	51,276	51,385	51,495	51,605	51,714	51,714
92.3	10,982	10,987	10,992	10,997	11,002	11,008	11,013	11,018	11,023	11,028	11,028
	51,824	51,934	52,044	52,154	52,264	52,374	52,484	52,594	52,704	52,815	52,815
92.4	11,033	11,038	11,044	11,049	11,054	11,059	11,064	11,069	11,074	11,080	11,080
	52,925	53,035	53,146	53,256	53,367	53,477	53,588	53,699	53,809	53,920	53,920
92.5	11,085	11,090	11,095	11,100	11,105	11,111	11,116	11,121	11,126	11,131	11,131
	54,031	54,142	54,253	54,364	54,475	54,586	54,697	54,808	54,919	55,031	55,031
92.6	11,136	11,142	11,147	11,152	11,157	11,162	11,167	11,173	11,178	11,183	11,183
	55,142	55,253	55,365	55,476	55,588	55,699	55,811	55,923	56,034	56,146	56,146
92.7	11,188	11,193	11,198	11,204	11,209	11,214	11,219	11,224	11,230	11,235	11,235
	56,258	56,370	56,482	56,594	56,706	56,818	56,930	57,043	57,155	57,267	57,267
92.8	11,240	11,245	11,250	11,256	11,261	11,266	11,271	11,276	11,282	11,287	11,287
	57,380	57,492	57,604	57,717	57,830	57,942	58,055	58,168	58,280	58,393	58,393
92.9	11,292	11,297	11,302	11,308	11,313	11,318	11,323	11,328	11,334	11,339	11,339
	58,506	58,619	58,732	58,845	58,958	59,071	59,185	59,298	59,411	59,525	59,525
93	11,344	11,347	11,349	11,352	11,354	11,356	11,359	11,361	11,364	11,366	11,366
	59,638	59,751	59,865	59,978	60,092	60,205	60,319	60,433	60,546	60,660	60,660
93.1	11,369	11,371	11,374	11,376	11,379	11,381	11,384	11,386	11,389	11,391	11,391
	60,774	60,887	61,001	61,115	61,229	61,342	61,456	61,570	61,684	61,798	61,798
93.2	11,394	11,396	11,399	11,401	11,404	11,406	11,409	11,411	11,414	11,416	11,416
	61,912	62,026	62,140	62,254	62,368	62,482	62,596	62,710	62,824	62,938	62,938
93.3	11,419	11,421	11,424	11,426	11,429	11,431	11,434	11,436	11,439	11,441	11,441
	63,052	63,167	63,281	63,395	63,509	63,624	63,738	63,852	63,967	64,081	64,081
93.4	11,444	11,446	11,449	11,451	11,454	11,456	11,459	11,461	11,464	11,466	11,466
	64,195	64,310	64,424	64,539	64,653	64,768	64,883	64,997	65,112	65,226	65,226
93.5	11,469	11,471	11,474	11,476	11,479	11,481	11,484	11,486	11,489	11,491	11,491
	65,341	65,456	65,571	65,685	65,800	65,915	66,030	66,144	66,259	66,374	66,374
93.6	11,494	11,496	11,499	11,501	11,504	11,506	11,509	11,511	11,514	11,516	11,516
	66,489	66,604	66,719	66,834	66,949	67,064	67,179	67,294	67,409	67,525	67,525
93.7	11,519	11,521	11,524	11,526	11,529	11,531	11,534	11,536	11,539	11,541	11,541
	67,640	67,755	67,870	67,985	68,101	68,216	68,331	68,447	68,562	68,677	68,677
93.8	11,544	11,546	11,549	11,551	11,554	11,556	11,559	11,561	11,564	11,566	11,566
	68,793	68,908	69,024	69,139	69,255	69,370	69,486	69,602	69,717	69,833	69,833
93.9	11,569	11,571	11,574	11,576	11,579	11,581	11,584	11,586	11,589	11,591	11,591
	69,945	70,064	70,180	70,296	70,411	70,527	70,643	70,759	70,875	70,991	70,991

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
94	11,594	11,598	11,603	11,607	11,611	11,616	11,620	11,624	11,629	11,633	
	71,107	71,223	71,339	71,455	71,571	71,687	71,803	71,919	72,036	72,152	
94.1	11,638	11,642	11,646	11,651	11,655	11,660	11,664	11,668	11,673	11,677	
	72,268	72,385	72,501	72,618	72,734	72,851	72,967	73,084	73,201	73,317	
94.2	11,682	11,686	11,690	11,695	11,699	11,704	11,708	11,712	11,717	11,721	
	73,434	73,551	73,668	73,785	73,902	74,019	74,136	74,253	74,370	74,487	
94.3	11,726	11,730	11,734	11,739	11,743	11,748	11,752	11,756	11,761	11,765	
	74,605	74,722	74,839	74,956	75,074	75,191	75,309	75,426	75,544	75,662	
94.4	11,770	11,774	11,778	11,783	11,787	11,792	11,796	11,800	11,805	11,809	
	75,779	75,897	76,015	76,133	76,250	76,368	76,486	76,604	76,722	76,840	
94.5	11,814	11,818	11,823	11,827	11,831	11,836	11,840	11,845	11,849	11,854	
	76,958	77,077	77,195	77,313	77,431	77,550	77,668	77,786	77,905	78,023	
94.6	11,858	11,862	11,867	11,871	11,876	11,880	11,885	11,889	11,893	11,898	
	78,142	78,261	78,379	78,498	78,617	78,735	78,854	78,973	79,092	79,211	
94.7	11,902	11,907	11,911	11,916	11,920	11,924	11,929	11,933	11,938	11,942	
	79,330	79,449	79,568	79,687	79,806	79,926	80,045	80,164	80,284	80,403	
94.8	11,947	11,951	11,956	11,960	11,964	11,969	11,973	11,978	11,982	11,987	
	80,522	80,642	80,762	80,881	81,001	81,120	81,240	81,360	81,480	81,599	
94.9	11,991	11,996	12,000	12,005	12,009	12,013	12,018	12,022	12,027	12,031	
	81,719	81,839	81,959	82,079	82,199	82,319	82,440	82,560	82,680	82,800	
95	12,036	12,038	12,040	12,042	12,045	12,047	12,049	12,052	12,054	12,056	
	82,921	83,041	83,161	83,282	83,402	83,523	83,643	83,764	83,884	84,005	
95.1	12,058	12,061	12,063	12,065	12,067	12,070	12,072	12,074	12,076	12,079	
	84,125	84,246	84,367	84,487	84,608	84,729	84,849	84,970	85,091	85,212	
95.2	12,081	12,083	12,085	12,088	12,090	12,092	12,094	12,097	12,099	12,101	
	85,332	85,453	85,574	85,695	85,816	85,937	86,058	86,179	86,300	86,421	
95.3	12,103	12,106	12,108	12,110	12,113	12,115	12,117	12,119	12,122	12,124	
	86,542	86,663	86,784	86,905	87,026	87,147	87,268	87,389	87,511	87,632	
95.4	12,126	12,128	12,131	12,133	12,135	12,137	12,140	12,142	12,144	12,147	
	87,753	87,874	87,996	88,117	88,238	88,360	88,481	88,602	88,724	88,845	
95.5	12,149	12,151	12,153	12,156	12,158	12,160	12,162	12,165	12,167	12,169	
	88,967	89,088	89,210	89,331	89,453	89,575	89,696	89,818	89,939	90,061	
95.6	12,171	12,174	12,176	12,178	12,181	12,183	12,185	12,187	12,190	12,192	
	90,183	90,305	90,426	90,548	90,670	90,792	90,914	91,035	91,157	91,279	
95.7	12,194	12,196	12,199	12,201	12,203	12,206	12,208	12,210	12,212	12,215	
	91,401	91,523	91,645	91,767	91,889	92,011	92,133	92,255	92,377	92,500	
95.8	12,217	12,219	12,221	12,224	12,226	12,228	12,231	12,233	12,235	12,237	
	92,622	92,744	92,866	92,988	93,111	93,233	93,355	93,477	93,600	93,722	
95.9	12,240	12,242	12,244	12,246	12,249	12,251	12,253	12,256	12,258	12,260	
	93,844	93,967	94,089	94,212	94,334	94,457	94,579	94,702	94,824	94,947	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
96	12,262	12,266	12,269	12,272	12,275	12,278	12,281	12,284	12,287	12,291	12,291
	95,070	95,192	95,315	95,438	95,560	95,683	95,806	95,929	96,052	96,174	96,174
96.1	12,294	12,297	12,300	12,303	12,306	12,309	12,312	12,316	12,319	12,322	12,322
	96,297	96,420	96,543	96,666	96,789	96,912	97,036	97,159	97,282	97,405	97,405
96.2	12,325	12,328	12,331	12,334	12,338	12,341	12,344	12,347	12,350	12,353	12,353
	97,528	97,652	97,775	97,898	98,022	98,145	98,268	98,392	98,515	98,639	98,639
96.3	12,356	12,359	12,363	12,366	12,369	12,372	12,375	12,378	12,381	12,385	12,385
	98,762	98,886	99,010	99,133	99,257	99,381	99,504	99,628	99,752	99,876	99,876
96.4	12,388	12,391	12,394	12,397	12,400	12,403	12,407	12,410	12,413	12,416	12,416
	100,000	100,123	100,247	100,371	100,495	100,619	100,743	100,868	100,992	101,116	101,116
96.5	12,419	12,422	12,425	12,429	12,432	12,435	12,438	12,441	12,444	12,447	12,447
	101,240	101,364	101,488	101,613	101,737	101,861	101,986	102,110	102,234	102,359	102,359
96.6	12,451	12,454	12,457	12,460	12,463	12,466	12,470	12,473	12,476	12,479	12,479
	102,483	102,608	102,733	102,857	102,982	103,106	103,231	103,356	103,480	103,605	103,605
96.7	12,482	12,485	12,488	12,492	12,495	12,498	12,501	12,504	12,507	12,511	12,511
	103,730	103,855	103,980	104,105	104,230	104,355	104,480	104,605	104,730	104,855	104,855
96.8	12,514	12,517	12,520	12,523	12,526	12,530	12,533	12,536	12,539	12,542	12,542
	104,980	105,105	105,230	105,355	105,481	105,606	105,731	105,857	105,982	106,107	106,107
96.9	12,545	12,548	12,552	12,555	12,558	12,561	12,564	12,567	12,571	12,574	12,574
	106,233	106,358	106,484	106,609	106,735	106,860	106,986	107,112	107,237	107,363	107,363
97	12,577	12,583	12,589	12,595	12,601	12,608	12,614	12,620	12,626	12,632	12,632
	107,489	107,615	107,741	107,867	107,992	108,119	108,245	108,371	108,497	108,623	108,623
97.1	12,638	12,645	12,651	12,657	12,663	12,669	12,675	12,681	12,688	12,694	12,694
	108,750	108,876	109,003	109,129	109,256	109,382	109,509	109,636	109,763	109,890	109,890
97.2	12,700	12,706	12,712	12,718	12,725	12,731	12,737	12,743	12,749	12,755	12,755
	110,017	110,144	110,271	110,398	110,525	110,652	110,780	110,907	111,035	111,162	111,162
97.3	12,762	12,768	12,774	12,780	12,786	12,793	12,799	12,805	12,811	12,817	12,817
	111,290	111,417	111,545	111,673	111,801	111,929	112,056	112,185	112,313	112,441	112,441
97.4	12,823	12,830	12,836	12,842	12,848	12,854	12,861	12,867	12,873	12,879	12,879
	112,569	112,697	112,826	112,954	113,082	113,211	113,339	113,468	113,597	113,726	113,726
97.5	12,885	12,892	12,898	12,904	12,910	12,917	12,923	12,929	12,935	12,941	12,941
	113,854	113,983	114,112	114,241	114,370	114,499	114,629	114,758	114,887	115,017	115,017
97.6	12,948	12,954	12,960	12,966	12,973	12,979	12,985	12,991	12,997	13,004	13,004
	115,146	115,276	115,405	115,535	115,664	115,794	115,924	116,054	116,184	116,314	116,314
97.7	13,010	13,016	13,022	13,029	13,035	13,041	13,047	13,054	13,060	13,066	13,066
	116,444	116,574	116,704	116,834	116,965	117,095	117,226	117,356	117,487	117,617	117,617
97.8	13,072	13,079	13,085	13,091	13,097	13,104	13,110	13,116	13,122	13,129	13,129
	117,748	117,879	118,010	118,140	118,271	118,402	118,533	118,665	118,796	118,927	118,927
97.9	13,135	13,141	13,148	13,154	13,160	13,166	13,173	13,179	13,185	13,191	13,191
	119,058	119,190	119,321	119,453	119,584	119,716	119,848	119,979	120,111	120,243	120,243

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
98	13,198	13,204	13,210	13,216	13,222	13,228	13,234	13,240	13,246	13,253	13,259
	120,375	120,507	120,639	120,771	120,903	121,036	121,168	121,300	121,433	121,565	121,698
98.1	13,259	13,265	13,271	13,277	13,283	13,289	13,295	13,301	13,307	13,314	13,320
	121,698	121,830	121,963	122,096	122,229	122,362	122,494	122,627	122,760	122,894	123,027
98.2	13,320	13,326	13,332	13,338	13,344	13,350	13,356	13,362	13,369	13,375	13,381
	123,027	123,160	123,293	123,427	123,560	123,694	123,827	123,961	124,094	124,228	124,362
98.3	13,381	13,387	13,393	13,399	13,405	13,411	13,418	13,424	13,430	13,436	13,442
	124,362	124,496	124,630	124,763	124,898	125,032	125,166	125,300	125,434	125,569	125,703
98.4	13,442	13,448	13,454	13,461	13,467	13,473	13,479	13,485	13,491	13,497	13,504
	125,703	125,837	125,972	126,106	126,241	126,376	126,511	126,645	126,780	126,915	127,050
98.5	13,504	13,510	13,516	13,522	13,528	13,534	13,541	13,547	13,553	13,559	13,565
	127,050	127,185	127,320	127,456	127,591	127,726	127,862	127,997	128,132	128,268	128,404
98.6	13,565	13,571	13,577	13,584	13,590	13,596	13,602	13,608	13,615	13,621	13,627
	128,404	128,539	128,675	128,811	128,947	129,083	129,219	129,355	129,491	129,627	129,763
98.7	13,627	13,633	13,639	13,645	13,652	13,658	13,664	13,670	13,676	13,683	13,689
	129,763	129,900	130,036	130,172	130,309	130,445	130,582	130,719	130,855	130,992	131,129
98.8	13,689	13,695	13,701	13,707	13,714	13,720	13,726	13,732	13,738	13,745	13,751
	131,129	131,266	131,403	131,540	131,677	131,814	131,951	132,089	132,226	132,364	132,501
98.9	13,751	13,757	13,763	13,769	13,776	13,782	13,788	13,794	13,800	13,807	13,813
	132,501	132,639	132,776	132,914	133,052	133,189	133,327	133,465	133,603	133,741	133,879
99	13,813	13,818	13,823	13,828	13,833	13,839	13,844	13,849	13,854	13,859	13,864
	133,879	134,017	134,156	134,294	134,432	134,570	134,709	134,847	134,986	135,124	135,263
99.1	13,864	13,870	13,875	13,880	13,885	13,890	13,895	13,901	13,906	13,911	13,916
	135,263	135,402	135,540	135,679	135,818	135,957	136,096	136,235	136,374	136,513	136,652
99.2	13,916	13,921	13,926	13,932	13,937	13,942	13,947	13,952	13,957	13,963	13,968
	136,652	136,791	136,931	137,070	137,209	137,349	137,488	137,627	137,767	137,907	138,046
99.3	13,968	13,973	13,978	13,983	13,989	13,994	13,999	14,004	14,009	14,014	13,968
	138,046	138,186	138,326	138,466	138,605	138,745	138,885	139,025	139,165	139,305	139,446
99.4	14,020	14,025	14,030	14,035	14,040	14,046	14,051	14,056	14,061	14,066	14,072
	139,446	139,586	139,726	139,866	140,007	140,147	140,288	140,428	140,569	140,710	140,850
99.5	14,072	14,077	14,082	14,087	14,092	14,098	14,103	14,108	14,113	14,118	14,124
	140,850	140,991	141,132	141,273	141,413	141,554	141,695	141,836	141,978	142,119	142,260
99.6	14,124	14,129	14,134	14,139	14,144	14,150	14,155	14,160	14,165	14,170	14,176
	142,260	142,401	142,543	142,684	142,825	142,967	143,108	143,250	143,392	143,533	143,675
99.7	14,176	14,181	14,186	14,191	14,197	14,202	14,207	14,212	14,217	14,223	14,228
	143,675	143,817	143,959	144,100	144,242	144,384	144,526	144,668	144,811	144,953	145,095
99.8	14,228	14,233	14,238	14,244	14,249	14,254	14,259	14,264	14,270	14,275	14,280
	145,095	145,237	145,380	145,522	145,665	145,807	145,950	146,092	146,235	146,378	146,520
99.9	14,280	14,285	14,291	14,296	14,301	14,306	14,312	14,317	14,322	14,327	14,332
	146,520	146,663	146,806	146,949	147,092	147,235	147,378	147,521	147,665	147,808	147,951

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
100	14,333	14,338	14,343	14,348	14,353	14,358	14,363	14,369	14,374	14,379	
	147,951	148,094	148,238	148,381	148,525	148,668	148,812	148,956	149,099	149,243	
100.1	14,384	14,389	14,394	14,399	14,404	14,410	14,415	14,420	14,425	14,430	
	149,387	149,531	149,675	149,819	149,963	150,107	150,251	150,395	150,539	150,684	
100.2	14,435	14,441	14,446	14,451	14,456	14,461	14,466	14,471	14,477	14,482	
	150,828	150,972	151,117	151,261	151,406	151,550	151,695	151,840	151,984	152,129	
100.3	14,487	14,492	14,497	14,502	14,508	14,513	14,518	14,523	14,528	14,533	
	152,274	152,419	152,564	152,709	152,854	152,999	153,144	153,289	153,435	153,580	
100.4	14,539	14,544	14,549	14,554	14,559	14,564	14,570	14,575	14,580	14,585	
	153,725	153,871	154,016	154,162	154,307	154,453	154,599	154,744	154,890	155,036	
100.5	14,590	14,595	14,601	14,606	14,611	14,616	14,621	14,627	14,632	14,637	
	155,182	155,328	155,474	155,620	155,766	155,912	156,058	156,204	156,351	156,497	
100.6	14,642	14,647	14,652	14,658	14,663	14,668	14,673	14,678	14,684	14,689	
	156,643	156,790	156,936	157,083	157,229	157,376	157,523	157,670	157,816	157,963	
100.7	14,694	14,699	14,704	14,710	14,715	14,720	14,725	14,730	14,736	14,741	
	158,110	158,257	158,404	158,551	158,698	158,846	158,993	159,140	159,287	159,435	
100.8	14,746	14,751	14,756	14,762	14,767	14,772	14,777	14,783	14,788	14,793	
	159,582	159,730	159,877	160,025	160,172	160,320	160,468	160,616	160,764	160,911	
100.9	14,798	14,803	14,809	14,814	14,819	14,824	14,829	14,835	14,840	14,845	
	161,059	161,207	161,355	161,504	161,652	161,800	161,948	162,097	162,245	162,393	
101	14,850	14,856	14,861	14,866	14,872	14,877	14,882	14,888	14,893	14,898	
	162,542	162,690	162,839	162,988	163,136	163,285	163,434	163,583	163,732	163,880	
101.1	14,903	14,909	14,914	14,919	14,925	14,930	14,935	14,941	14,946	14,951	
	164,029	164,179	164,328	164,477	164,626	164,775	164,925	165,074	165,223	165,373	
101.2	14,957	14,962	14,967	14,973	14,978	14,983	14,989	14,994	14,999	15,005	
	165,523	165,672	165,822	165,971	166,121	166,271	166,421	166,571	166,721	166,871	
101.3	15,010	15,015	15,021	15,026	15,031	15,037	15,042	15,047	15,053	15,058	
	167,021	167,171	167,321	167,471	167,622	167,772	167,922	168,073	168,223	168,374	
101.4	15,063	15,069	15,074	15,079	15,085	15,090	15,095	15,101	15,106	15,112	
	168,524	168,675	168,826	168,977	169,127	169,278	169,429	169,580	169,731	169,882	
101.5	15,117	15,122	15,128	15,133	15,138	15,144	15,149	15,154	15,160	15,165	
	170,034	170,185	170,336	170,487	170,639	170,790	170,941	171,093	171,245	171,396	
101.6	15,170	15,176	15,181	15,187	15,192	15,197	15,203	15,208	15,213	15,219	
	171,548	171,700	171,851	172,003	172,155	172,307	172,459	172,611	172,763	172,915	
101.7	15,224	15,230	15,235	15,240	15,246	15,251	15,256	15,262	15,267	15,273	
	173,068	173,220	173,372	173,525	173,677	173,829	173,982	174,135	174,287	174,440	
101.8	15,278	15,283	15,289	15,294	15,299	15,305	15,310	15,316	15,321	15,326	
	174,593	174,746	174,898	175,051	175,204	175,357	175,510	175,663	175,817	175,970	
101.9	15,332	15,337	15,343	15,348	15,353	15,359	15,364	15,370	15,375	15,380	
	176,123	176,277	176,430	176,583	176,737	176,890	177,044	177,198	177,351	177,505	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
102	15,386	15,392	15,397	15,403	15,409	15,415	15,421	15,426	15,432	15,438	
	177,659	177,813	177,967	178,121	178,275	178,429	178,583	178,737	178,892	179,046	
102.1	15,444	15,450	15,455	15,461	15,467	15,473	15,479	15,484	15,490	15,496	
	179,201	179,355	179,510	179,664	179,819	179,973	180,128	180,283	180,438	180,593	
102.2	15,502	15,508	15,513	15,519	15,525	15,531	15,537	15,542	15,548	15,554	
	180,748	180,903	181,058	181,213	181,368	181,524	181,679	181,834	181,990	182,145	
102.3	15,560	15,566	15,572	15,577	15,583	15,589	15,595	15,601	15,606	15,612	
	182,301	182,457	182,612	182,768	182,924	183,080	183,236	183,392	183,548	183,704	
102.4	15,618	15,624	15,630	15,636	15,641	15,647	15,653	15,659	15,665	15,671	
	183,860	184,016	184,172	184,329	184,485	184,641	184,798	184,954	185,111	185,268	
102.5	15,676	15,682	15,688	15,694	15,700	15,706	15,712	15,717	15,723	15,729	
	185,425	185,581	185,738	185,895	186,052	186,209	186,366	186,523	186,681	186,838	
102.6	15,735	15,741	15,747	15,753	15,758	15,764	15,770	15,776	15,782	15,788	
	186,995	187,152	187,310	187,467	187,625	187,783	187,940	188,098	188,256	188,414	
102.7	15,794	15,799	15,805	15,811	15,817	15,823	15,829	15,835	15,840	15,846	
	188,572	188,729	188,888	189,046	189,204	189,362	189,520	189,679	189,837	189,995	
102.8	15,852	15,858	15,864	15,870	15,876	15,882	15,887	15,893	15,899	15,905	
	190,154	190,312	190,471	190,630	190,788	190,947	191,106	191,265	191,424	191,583	
102.9	15,911	15,917	15,923	15,929	15,935	15,940	15,946	15,952	15,958	15,964	
	191,742	191,901	192,060	192,220	192,379	192,539	192,698	192,857	193,017	193,176	
103	15,970	15,976	15,981	15,987	15,993	15,998	16,004	16,010	16,015	16,021	
	193,336	193,496	193,656	193,815	193,975	194,135	194,295	194,455	194,615	194,776	
103.1	16,027	16,032	16,038	16,044	16,050	16,055	16,061	16,067	16,072	16,078	
	194,936	195,096	195,257	195,417	195,577	195,738	195,898	196,059	196,220	196,381	
103.2	16,084	16,089	16,095	16,101	16,106	16,112	16,118	16,124	16,129	16,135	
	196,541	196,702	196,863	197,024	197,185	197,346	197,507	197,669	197,830	197,991	
103.3	16,141	16,146	16,152	16,158	16,164	16,169	16,175	16,181	16,186	16,192	
	198,153	198,314	198,476	198,637	198,799	198,961	199,122	199,284	199,446	199,608	
103.4	16,198	16,204	16,209	16,215	16,221	16,226	16,232	16,238	16,244	16,249	
	199,770	199,932	200,094	200,256	200,418	200,580	200,742	200,905	201,067	201,230	
103.5	16,255	16,261	16,267	16,272	16,278	16,284	16,289	16,295	16,301	16,307	
	201,392	201,555	201,717	201,880	202,043	202,206	202,369	202,531	202,694	202,857	
103.6	16,312	16,318	16,324	16,330	16,335	16,341	16,347	16,353	16,358	16,364	
	203,021	203,184	203,347	203,510	203,674	203,837	204,000	204,164	204,327	204,491	
103.7	16,370	16,376	16,381	16,387	16,393	16,399	16,404	16,410	16,416	16,422	
	204,655	204,818	204,982	205,146	205,310	205,474	205,638	205,802	205,966	206,130	
103.8	16,427	16,433	16,439	16,445	16,450	16,456	16,462	16,468	16,474	16,479	
	206,295	206,459	206,623	206,788	206,952	207,117	207,281	207,446	207,611	207,775	
103.9	16,485	16,491	16,497	16,502	16,508	16,514	16,520	16,525	16,531	16,537	
	207,940	208,105	208,270	208,435	208,600	208,765	208,930	209,096	209,261	209,426	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
104	16,543	16,549	16,556	16,562	16,569	16,575	16,582	16,588	16,594	16,601	
	209,592	209,757	209,923	210,088	210,254	210,419	210,585	210,751	210,917	211,083	
104.1	16,607	16,614	16,620	16,627	16,633	16,640	16,646	16,653	16,659	16,666	
	211,249	211,415	211,581	211,748	211,914	212,080	212,247	212,413	212,580	212,746	
104.2	16,672	16,679	16,685	16,692	16,698	16,705	16,711	16,718	16,724	16,730	
	212,913	213,080	213,247	213,413	213,580	213,747	213,915	214,082	214,249	214,416	
104.3	16,737	16,743	16,750	16,756	16,763	16,769	16,776	16,782	16,789	16,795	
	214,583	214,751	214,918	215,086	215,253	215,421	215,589	215,757	215,925	216,092	
104.4	16,802	16,808	16,815	16,821	16,828	16,834	16,841	16,848	16,854	16,861	
	216,260	216,428	216,597	216,765	216,933	217,101	217,270	217,438	217,607	217,775	
104.5	16,867	16,874	16,880	16,887	16,893	16,900	16,906	16,913	16,919	16,926	
	217,944	218,113	218,281	218,450	218,619	218,788	218,957	219,126	219,295	219,465	
104.6	16,932	16,939	16,945	16,952	16,958	16,965	16,971	16,978	16,985	16,991	
	219,634	219,803	219,973	220,142	220,312	220,481	220,651	220,821	220,991	221,160	
104.7	16,998	17,004	17,011	17,017	17,024	17,030	17,037	17,043	17,050	17,057	
	221,330	221,500	221,670	221,841	222,011	222,181	222,351	222,522	222,692	222,863	
104.8	17,063	17,070	17,076	17,083	17,089	17,096	17,102	17,109	17,116	17,122	
	223,033	223,204	223,375	223,546	223,716	223,887	224,058	224,229	224,401	224,572	
104.9	17,129	17,135	17,142	17,148	17,155	17,162	17,168	17,175	17,181	17,188	
	224,743	224,914	225,086	225,257	225,429	225,600	225,772	225,944	226,115	226,287	
105	17,194	17,202	17,209	17,216	17,223	17,231	17,238	17,245	17,253	17,260	
	226,459	226,631	226,803	226,975	227,147	227,320	227,492	227,665	227,837	228,010	
105.1	17,267	17,274	17,282	17,289	17,296	17,303	17,311	17,318	17,325	17,332	
	228,182	228,355	228,528	228,701	228,873	229,046	229,220	229,393	229,566	229,739	
105.2	17,340	17,347	17,354	17,362	17,369	17,376	17,383	17,391	17,398	17,405	
	229,913	230,086	230,259	230,433	230,607	230,780	230,954	231,128	231,302	231,476	
105.3	17,413	17,420	17,427	17,435	17,442	17,449	17,456	17,464	17,471	17,478	
	231,650	231,824	231,999	232,173	232,347	232,522	232,696	232,871	233,046	233,220	
105.4	17,486	17,493	17,500	17,508	17,515	17,522	17,530	17,537	17,544	17,552	
	233,395	233,570	233,745	233,920	234,095	234,270	234,446	234,621	234,796	234,972	
105.5	17,559	17,566	17,574	17,581	17,588	17,596	17,603	17,610	17,618	17,625	
	235,147	235,323	235,499	235,674	235,850	236,026	236,202	236,378	236,554	236,731	
105.6	17,632	17,640	17,647	17,654	17,662	17,669	17,676	17,684	17,691	17,698	
	236,907	237,083	237,260	237,436	237,613	237,789	237,966	238,143	238,320	238,497	
105.7	17,706	17,713	17,720	17,728	17,735	17,743	17,750	17,757	17,765	17,772	
	238,674	238,851	239,028	239,205	239,383	239,560	239,737	239,915	240,093	240,270	
105.8	17,779	17,787	17,794	17,801	17,809	17,816	17,824	17,831	17,838	17,846	
	240,448	240,626	240,804	240,982	241,160	241,338	241,516	241,694	241,873	242,051	
105.9	17,853	17,861	17,868	17,875	17,883	17,890	17,898	17,905	17,912	17,920	
	242,230	242,408	242,587	242,766	242,944	243,123	243,302	243,481	243,660	243,839	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	0.09
106	17,927	17,934	17,941	17,948	17,955	17,962	17,968	17,975	17,982	17,989	17,989
	244,019	244,198	244,377	244,557	244,736	244,916	245,096	245,275	245,455	245,635	245,635
106.1	17,996	18,003	18,010	18,017	18,024	18,031	18,037	18,044	18,051	18,058	18,058
	245,815	245,995	246,175	246,355	246,535	246,715	246,896	247,076	247,257	247,437	247,437
106.2	18,065	18,072	18,079	18,086	18,093	18,100	18,107	18,113	18,120	18,127	18,127
	247,618	247,799	247,979	248,160	248,341	248,522	248,703	248,884	249,065	249,247	249,247
106.3	18,134	18,141	18,148	18,155	18,162	18,169	18,176	18,183	18,190	18,197	18,197
	249,428	249,609	249,791	249,972	250,154	250,335	250,517	250,699	250,881	251,063	251,063
106.4	18,204	18,210	18,217	18,224	18,231	18,238	18,245	18,252	18,259	18,266	18,266
	251,245	251,427	251,609	251,791	251,973	252,156	252,338	252,521	252,703	252,886	252,886
106.5	18,273	18,280	18,287	18,294	18,301	18,308	18,315	18,322	18,329	18,336	18,336
	253,069	253,251	253,434	253,617	253,800	253,983	254,166	254,349	254,533	254,716	254,716
106.6	18,343	18,350	18,356	18,363	18,370	18,377	18,384	18,391	18,398	18,405	18,405
	254,899	255,083	255,266	255,450	255,634	255,817	256,001	256,185	256,369	256,553	256,553
106.7	18,412	18,419	18,426	18,433	18,440	18,447	18,454	18,461	18,468	18,475	18,475
	256,737	256,921	257,105	257,290	257,474	257,659	257,843	258,028	258,212	258,397	258,397
106.8	18,482	18,489	18,496	18,503	18,510	18,517	18,524	18,531	18,538	18,545	18,545
	258,582	258,767	258,952	259,137	259,322	259,507	259,692	259,877	260,063	260,248	260,248
106.9	18,552	18,559	18,566	18,573	18,580	18,587	18,594	18,601	18,608	18,615	18,615
	260,433	260,619	260,805	260,990	261,176	261,362	261,548	261,734	261,920	262,106	262,106
107	18,622	18,629	18,636	18,643	18,650	18,657	18,664	18,671	18,678	18,685	18,685
	262,292	262,478	262,665	262,851	263,038	263,224	263,411	263,597	263,784	263,971	263,971
107.1	18,692	18,699	18,706	18,713	18,720	18,728	18,735	18,742	18,749	18,756	18,756
	264,158	264,345	264,532	264,719	264,906	265,093	265,281	265,468	265,656	265,843	265,843
107.2	18,763	18,770	18,777	18,784	18,791	18,798	18,805	18,812	18,819	18,826	18,826
	266,031	266,218	266,406	266,594	266,782	266,970	267,158	267,346	267,534	267,722	267,722
107.3	18,833	18,840	18,847	18,854	18,861	18,869	18,876	18,883	18,890	18,897	18,897
	267,910	268,099	268,287	268,476	268,664	268,853	269,042	269,230	269,419	269,608	269,608
107.4	18,904	18,911	18,918	18,925	18,932	18,939	18,946	18,953	18,960	18,968	18,968
	269,797	269,986	270,176	270,365	270,554	270,743	270,933	271,122	271,312	271,502	271,502
107.5	18,975	18,982	18,989	18,996	19,003	19,010	19,017	19,024	19,031	19,038	19,038
	271,691	271,881	272,071	272,261	272,451	272,641	272,831	273,021	273,211	273,402	273,402
107.6	19,045	19,053	19,060	19,067	19,074	19,081	19,088	19,095	19,102	19,109	19,109
	273,592	273,783	273,973	274,164	274,355	274,545	274,736	274,927	275,118	275,309	275,309
107.7	19,116	19,124	19,131	19,138	19,145	19,152	19,159	19,166	19,173	19,181	19,181
	275,500	275,692	275,883	276,074	276,266	276,457	276,649	276,840	277,032	277,224	277,224
107.8	19,188	19,195	19,202	19,209	19,216	19,223	19,230	19,238	19,245	19,252	19,252
	277,416	277,607	277,799	277,991	278,184	278,376	278,568	278,760	278,953	279,145	279,145
107.9	19,259	19,266	19,273	19,280	19,287	19,295	19,302	19,309	19,316	19,323	19,323
	279,338	279,530	279,723	279,916	280,109	280,302	280,495	280,688	280,881	281,074	281,074

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)	Area (ft ²)
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09	
108	19,330	19,333	19,336	19,339	19,342	19,345	19,348	19,351	19,354	19,357	
	281,267	281,461	281,654	281,847	282,041	282,234	282,428	282,621	282,815	283,008	
108.1	19,360	19,363	19,365	19,368	19,371	19,374	19,377	19,380	19,383	19,386	
	283,202	283,395	283,589	283,783	283,976	284,170	284,364	284,558	284,752	284,945	
108.2	19,389	19,392	19,395	19,398	19,401	19,403	19,406	19,409	19,412	19,415	
	285,139	285,333	285,527	285,721	285,915	286,109	286,303	286,497	286,691	286,885	
108.3	19,418	19,421	19,424	19,427	19,430	19,433	19,436	19,439	19,442	19,445	
	287,080	287,274	287,468	287,662	287,857	288,051	288,245	288,440	288,634	288,828	
108.4	19,447	19,450	19,453	19,456	19,459	19,462	19,465	19,468	19,471	19,474	
	289,023	289,217	289,412	289,606	289,801	289,996	290,190	290,385	290,580	290,774	
108.5	19,477	19,480	19,483	19,486	19,489	19,491	19,494	19,497	19,500	19,503	
	290,969	291,164	291,359	291,553	291,748	291,943	292,138	292,333	292,528	292,723	
108.6	19,506	19,509	19,512	19,515	19,518	19,521	19,524	19,527	19,530	19,533	
	292,918	293,113	293,308	293,504	293,699	293,894	294,089	294,284	294,480	294,675	
108.7	19,536	19,538	19,541	19,544	19,547	19,550	19,553	19,556	19,559	19,562	
	294,870	295,066	295,261	295,456	295,652	295,847	296,043	296,239	296,434	296,630	
108.8	19,565	19,568	19,571	19,574	19,577	19,580	19,583	19,586	19,588	19,591	
	296,825	297,021	297,217	297,412	297,608	297,804	298,000	298,196	298,391	298,587	
108.9	19,594	19,597	19,600	19,603	19,606	19,609	19,612	19,615	19,618	19,621	
	298,783	298,979	299,175	299,371	299,567	299,763	299,959	300,156	300,352	300,548	
109	19,624	19,629	19,634	19,640	19,645	19,651	19,656	19,661	19,667	19,672	
	300,744	300,940	301,137	301,333	301,530	301,726	301,923	302,119	302,316	302,512	
109.1	19,677	19,683	19,688	19,693	19,699	19,704	19,709	19,715	19,720	19,726	
	302,709	302,906	303,103	303,300	303,497	303,694	303,891	304,088	304,285	304,482	
109.2	19,731	19,736	19,742	19,747	19,752	19,758	19,763	19,768	19,774	19,779	
	304,680	304,877	305,074	305,272	305,469	305,667	305,864	306,062	306,260	306,458	
109.3	19,785	19,790	19,795	19,801	19,806	19,811	19,817	19,822	19,827	19,833	
	306,655	306,853	307,051	307,249	307,447	307,645	307,843	308,042	308,240	308,438	
109.4	19,838	19,844	19,849	19,854	19,860	19,865	19,870	19,876	19,881	19,887	
	308,637	308,835	309,033	309,232	309,431	309,629	309,828	310,027	310,225	310,424	
109.5	19,892	19,897	19,903	19,908	19,914	19,919	19,924	19,930	19,935	19,940	
	310,623	310,822	311,021	311,220	311,419	311,618	311,818	312,017	312,216	312,416	
109.6	19,946	19,951	19,957	19,962	19,967	19,973	19,978	19,984	19,989	19,994	
	312,615	312,814	313,014	313,214	313,413	313,613	313,813	314,012	314,212	314,412	
109.7	20,000	20,005	20,011	20,016	20,021	20,027	20,032	20,038	20,043	20,048	
	314,612	314,812	315,012	315,212	315,413	315,613	315,813	316,014	316,214	316,414	
109.8	20,054	20,059	20,065	20,070	20,075	20,081	20,086	20,092	20,097	20,103	
	316,615	316,815	317,016	317,217	317,418	317,618	317,819	318,020	318,221	318,422	
109.9	20,108	20,113	20,119	20,124	20,130	20,135	20,140	20,146	20,151	20,157	
	318,623	318,824	319,025	319,226	319,428	319,629	319,830	320,032	320,233	320,435	

Table 7-02

Elevation-Area/Capacity Table - Barker Reservoir

Elevation (ft) NAVD 1988	Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)		Area (ft ²)	
	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)	Capacity (Ac-ft)
	0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09		
110	20,162	20,165	20,168	20,171	20,174	20,177	20,180	20,183	20,186	20,189		
	320,637	320,838	321,040	321,242	321,443	321,645	321,847	322,049	322,250	322,452		
110.1	20,192	20,195	20,198	20,201	20,204	20,207	20,210	20,213	20,216	20,219		
	322,654	322,856	323,058	323,260	323,462	323,664	323,866	324,068	324,271	324,473		
110.2	20,222	20,225	20,228	20,231	20,234	20,237	20,240	20,243	20,246	20,249		
	324,675	324,877	325,079	325,282	325,484	325,686	325,889	326,091	326,294	326,496		
110.3	20,252	20,255	20,258	20,261	20,264	20,267	20,270	20,273	20,276	20,279		
	326,699	326,901	327,104	327,306	327,509	327,712	327,914	328,117	328,320	328,522		
110.4	20,282	20,285	20,288	20,291	20,294	20,297	20,300	20,303	20,306	20,309		
	328,725	328,928	329,131	329,334	329,537	329,740	329,943	330,146	330,349	330,552		
110.5	20,312	20,315	20,318	20,321	20,324	20,327	20,330	20,333	20,336	20,339		
	330,755	330,958	331,161	331,364	331,568	331,771	331,974	332,178	332,381	332,584		
110.6	20,342	20,345	20,348	20,351	20,354	20,357	20,360	20,363	20,366	20,369		
	332,788	332,991	333,195	333,398	333,602	333,805	334,009	334,212	334,416	334,620		
110.7	20,372	20,375	20,378	20,381	20,384	20,387	20,390	20,393	20,396	20,399		
	334,823	335,027	335,231	335,435	335,638	335,842	336,046	336,250	336,454	336,658		
110.8	20,402	20,405	20,408	20,411	20,414	20,417	20,420	20,423	20,426	20,429		
	336,862	337,066	337,270	337,474	337,678	337,882	338,087	338,291	338,495	338,699		
110.9	20,432	20,435	20,438	20,441	20,444	20,447	20,450	20,453	20,456	20,459		
	338,904	339,108	339,312	339,517	339,721	339,926	340,130	340,335	340,539	340,744		

EXHIBIT A
SUPPLEMENTARY PERTINENT DATA

EXHIBIT A
SUPPLEMENTARY PERTINENT DATA

GENERAL INFORMATION

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Location	Addicks - South Mayde Creek, approximately 1.4 miles upstream from Buffalo Bayou Barker - Buffalo Bayou, approximately 1.2 miles upstream from South Mayde Creek
Type of Project	Detention - Type Reservoir
Objectives of regulation	Primary purpose is flood control
Project owner	U.S. Army Corps of Engineers
Operating agency	U.S. Army Corps of Engineers
Regulating agency	U.S. Army Corps of Engineers
Hydropower	None
Water supply contracts	None
Other formal agreements	None
Water rights	Riparian
Project cost	\$4,000,000
Closure Date	Addicks - 08 Jun 1948 Barker - 25 Aug 1945

RESERVOIRS

ITEM	DESCRIPTION OR QUANTITY AND UNITS		
Feature	Elevation (ft, NAVD)	Surface Area (acres)	Storage Capacity (ac-ft)
<u>ADDICKS RESERVOIR</u>			
Conduit Invert	67.5	7	35
Limits of Government Land	103.0	13,016	127,591
100-Year Flood	100.3	11,397	94,500
Standard Project Flood	107.6	15,886	193,956
Natural Ground at End of Dam	108.0	16,199	199,643
Top of Dam	121.0		-
<u>BARKER RESERVOIR</u>			
Conduit Invert	70.2	0	0
Limits of Government Land	95.0	12,036	82,921
100-Year Flood	97.0	12,577	107,489
Standard Project Flood	98.3	13,412	125,061
Natural Ground at End of Dam	104.0	16,543	209,600
Top of Dam	113.1		-

Length of embankment	Addicks - 61,166 feet Barker - 71,900 feet
Initial real estate taking	Addicks - 12,460 acres Barker - 12,060 acres
Range of clearing	Not applicable

HYDROLOGY

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Drainage area (total)	Addicks - 136 square miles Barker - 130 square miles
1" runoff equals	Addicks - 7,253 acre-feet Barker - 6,933 acre-feet
Standard Project Flood	Addicks – 193,956 acre-feet Barker – 125,061 acre-feet
Spillway Design Flood	Addicks – 462,145 acre-feet Barker – 279,072 acre-feet
Maximum flood of record	Addicks – 65,264 acre-feet (March 1992) Barker - 66,489 acre-feet (March 1992)
Minimum daily flow	Addicks – 35 cfs Barker – 23 cfs
Average flows	(see Table 4-03)
Hydrometeorologic data	A real-time flood forecasting model was developed by the Hydrologic Engineering Center (HEC). This system is used to predict the inflow into the reservoirs. The forecasting system consists of PRECIP and HEC-HMS models. Both models use a one-hour time interval. Precipitation estimates are available from three main sources: precipitation gages, radar, and satellite.

EMBANKMENTS

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Purpose	To complete impoundment structure to high ground and provide for access road
Type	Overflow and Non-Overflow
Type of Fill	Rolled earth fill, soil-cement protection on overflow sections
Length	Addicks - 61,166 feet Barker - 71,900 feet
Top Elevation	Addicks – 121.0 (non-overflow) Barker – 113.1 (non-overflow)

SPILLWAY

None

OUTLET FACILITIES

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Location	Addicks - Main Channel of South Mayde Creek Barker - Main Channel of Buffalo Bayou
Type	Addicks - Gated Concrete Box Culvert Barker - Gated Concrete Box Culvert
Number and Size of Conduits	Addicks - 5-8' x 6' Barker - 5-9' x 7'
Length of Conduits	Addicks - 252 feet Barker - 190.5 feet

OUTLET FACILITIES CONTINUED

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Upstream Invert Elevation	Addicks – 67.5 feet Barker - 70.2 feet
Energy Dissipator	Addicks - 43.5' Convex Spillway and 40' long, 60' wide longitudinal stilling basin with baffle blocks and end sill Barker - 55.5' convex spillway and 50' long, 60' wide longitudinal stilling basin with baffle blocks and end sill

HYDROELECTRIC POWER FACILITIES

None

LOCK

None

CONTROL STATION

ITEM	DESCRIPTION OR QUANTITY AND UNITS
Location	Buffalo Bayou at Piney Point streamgage approximately 10.2 miles downstream from Barker Dam
Target Flow Rates	2,000 cfs
Monitoring Provisions	The station is equipped with a water stage recorder and a data collection platform for transmission of hourly data via GOES satellite at 4-hour intervals.

EXHIBIT B
STANDING INSTRUCTIONS TO DAM TENDER

EXHIBIT B

STANDING INSTRUCTION TO DAM TENDER

ADDICKS AND BARKER RESERVOIRS, BUFFALO BAYOU, TEXAS

1. Responsibility the Operations Division, through the Chief of Project Operations Branch, is responsible for the maintenance and operation of the Addicks and Barker Reservoirs. The Engineering-Construction Division, through the Hydrology and Hydraulics/Water Control (H&H/WC) Branch Sub-Section is responsible for the preparation and issuance of the reservoir regulation instructions. The Acting Natural Resource Manager or alternate member of the field office organization will serve as Dam Tender for both reservoirs. The responsibility of the Dam Tender is to insure that discharges from the reservoirs are as instructed by the District Hydrologist or in accordance with the plan of regulation set forth in Chapter 7 of the Reservoir Regulation Manual. The principle duties of the Dam Tender are given in section 7-04 of the Water Control Manual and in the supplemental manual "Initial and Emergency Instructions to Dam Tender". The following instructions for the regulation of the reservoirs will be observed by the Dam Tender.

2. INSTRUCTIONS The Acting Natural Resource Manager will act as the Dam Tender for reservoir operations. Detailed instructions to the Dam Tender for Addicks and Barker Reservoirs are presented below.
 - a. OPERATION During flood periods, the reservoir will be operated in accordance with the normal regulation for flood control as described in Chapter VII of the Addicks and Barker Reservoir Regulation Manual or Paragraph 3,4 or 5 of this exhibit. Instructions for the storage and discharge of flood waters will be issued by the Hydrology and Hydraulics/Water Control (H&H/WC) Branch . In the event that communication with the Galveston District Office is disrupted, the reservoir will be regulated in accordance with the schedule of emergency regulation for flood control (see Chapter 7 of the Addicks and Barker Reservoir Regulation Manual or Paragraph 3,4 or 5 of this exhibit). In addition, the Dam Tender will make every effort to re-establish communications with the Galveston District Office.

 - b. REPORTS TO DISTRICT OFFICE The Dam Tender is to observe and be cognizant of all available hydrologic/meteorological data and project activities that are pertinent to the operation of the projects. These data, when requested by the Hydrology and Hydraulics/Water Control (H&H/WC) Branch, will be reported by e-mail, telephone or radio.

3. NORMAL OPERATION

a. Normal conditions - Set two conduit gates at an opening of 1.0 foot for passage of 100-250 cfs (normal flow at the dam).

b. If 1 inch of rainfall, in 24 hours or less occurs, over the watershed below the reservoirs or when flooding is predicted downstream, the Hydrology and Hydraulics/Water Control (H&H/WC) Branch will be contacted. If an unwarranted delay will ensue, the Dam Tender will proceed to the reservoir, close the gates, and then contact the Hydrology and Hydraulics/Water Control (H&H/WC) Branch.

c. When releases are being made and one-half inch of rainfall, in 24 hours or less, occurs over the watershed below the reservoirs or when flooding is predicted downstream, the Hydrology and Hydraulics/Water Control (H&H/WC) Branch will be contacted. If an unwarranted delay will ensue, the Dam Tender will proceed to the reservoirs, close the gates, and then contact the Hydrology and Hydraulics/Water Control (H&H/WC) Branch.


4. INDUCED SURCHARGE REGULATION

a. Induced Surcharge conditions at Addicks and Barker Reservoirs are defined to exist at any time the reservoir pool equals or exceeds 101 feet NAVD 1988 at Addicks (about 45 percent of storage) and 95.7 feet NAVD 1988 at Barker (about 40 percent of storage) on the reservoir gages. If inflow and pool elevation conditions dictate the use of the induced surcharge regulation schedule, the Hydrology and Hydraulics/Water Control (H&H/WC) Branch will be contacted and instructions will be provided. Advance information will be given the public by the District Engineer or in his absence by the Officer-in-Charge through the media of the U.S. National Weather Service, other agencies, telephone, radio, television and newspapers.

b. Emergency Conditions (Loss of Communications). If the Hydrology and Hydraulics/Water Control (H&H/WC) Branch cannot be contacted and communications are lost emergency conditions exist. Releases will be made independently by the Dam Tender in accordance with the induced surcharge regulation schedules shown on plates 7-03 and 7-04. Inflow and pool elevation conditions dictate the use of the induced surcharge regulation schedule in either reservoir, they will be made regardless of channel capacity downstream. Every effort should be made to provide advance

information to the public by the Dam Tender or in his absence by the alternate through the media of the U.S. National Weather Service, Civil Defense, radio, television and newspapers. The gates should remain at the maximum opening attained from the induced surcharge operation schedules until reservoir levels fall to elevation 101 feet NAVD 1988 in Addicks and 94.9 feet NAVD 1988 in Barker. Then, if the out-flow from both reservoirs when combined with the uncontrolled runoff downstream is greater than channel capacity, adjust the gates until the total discharges do not exceed channel capacity and follow the normal operating procedures in section 7-05, paragraph a, sub-section 4 of the Addicks and Barker Water Control Manual.


PLATES



Legend

Watersheds


- Addicks Reservoir
- Barker Reservoir
- Cypress Creek
- Addicks Reservoir
- Barker Reservoir
- Gaging Stations



**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**

**ADDICKS RESERVOIR
VICINITY MAP**

**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-02**




Legend

- Gaging Stations
- Addicks Reservoir
- Barker Reservoir

Watersheds


- Addicks Reservoir
- Barker Reservoir
- Cypress Creek



**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**


**BARKER RESERVOIR
VICINITY MAP**

**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-03**



TYPICAL SECTION - DAM


N.T.S.




TYPICAL SECTION - SPILLWAY

N.T.S.

ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS
DAM AND SPILLWAYS TYPICAL SECTIONS ADDICKS RESERVOIR
GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 2-04



TYPICAL SECTION - DAM
N.T.S.




TYPICAL SECTION - SPILLWAY
N.T.S.


ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

DAM AND SPILLWAY
TYPICAL SECTIONS
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-05



PLAN VIEW - OUTLET WORKS




PROFILE VIEW - OUTLET WORKS


ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

OUTLET WORKS
PLAN AND PROFILE
ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-06



PLAN VIEW - OUTLET WORKS




PROFILE VIEW - OUTLET WORKS

ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

OUTLET WORKS
PLAN AND PROFILE
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-07



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

PUBLIC FACILITIES
ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-08



0 0.5 1 2 Miles



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS


PUBLIC FACILITIES
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 2-09

Buffalo Bayou

Watersurface Profiles from TSARP HEC-RAS


TSARP Stations 105,000' thru 175,000'



NOTE: ELEVATIONS ARE NAVD 1988

ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS
WATER SURFACE PROFILES AND FLOOR ELEVATIONS BUFFALO BAYOU
GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 3-01


Buffalo Bayou
Watersurface Profiles from TSARP HEC-RAS
TSARP Stations 175,000' thru 250,000'



NOTE: ELEVATIONS ARE NAVD 1988


<p align="center">ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS</p>
<p align="center">WATER SURFACE PROFILES AND FLOOR ELEVATIONS BUFFALO BAYOU</p>
<p align="center">GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 3-02</p>

DISCHARGE RATING CURVE - BUFFALO BAYOU AT PINEY POINT



NOTE: ELEVATIONS ARE NAVD 1988


ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS
DISCHARGE RATING CURVE BUFFALO BAYOU AT PINEY POINT, TEXAS
GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 4-02



USGS STATION NUMBER	NATIONAL WEATHER SERVICE (NWS) ID	DESCRIPTION
8073500	ADBT2	BUFFALO BAYOU NR ADDICKS, TX
8073000	ADDT2	ADDICKS RES NR ADDICKS, TX
8072600	BAHT2	BUFFALO BAYOU AT STATE HWY 6 NR ADDICKS, TX
8072500	BAKT2	BARKER RES NR ADDICKS, TX
8072730	BBAT2	BEAR CK NR BARKER, TX
8072300	BBKT2	BUFFALO BAYOU NR KATY, TX
8074000	BBST2	BUFFALO BAYOU AT HOUSTON, TX
8068740	HCHT2	CYPRESS CK AT HOUSE-HAHL RD NR CYPRESS, TX
8068700	HOCT2	CYPRESS CK AT SHARP ROAD NR HOCKLEY, TX
8068720	KHOT2	CYPRESS CK AT KATY-HOCKLEY RD NR HOCKLEY, TX
8072760	LLYT2	LANGHAM CK AT WLITTLE YORK RD NR ADDICKS, TX
8073700	PPTT2	BUFFALO BAYOU AT PINEY POINT, TX
8072700	SMAT2	S MAYDE CREEK NR ADDICKS, TX
8073600	WSBT2	BUFFALO BAYOU AT WBELT DR, AT HOUSTON, TX
8072800	LCAT2	LANGHAM CK NR ADDICKS, TX

Legend


- Addicks Reservoir
- Barker Reservoir
- ▲ Gaging Stations



**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**

STREAM GAGE LOCATIONS


**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-01**



**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**

**INUNDATION
MAPS**


**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-02**




ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

INUNDATION
MAPS

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-03






ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

INUNDATION
MAPS


GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-05



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

INUNDATION
MAPS


GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-06



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

**INUNDATION
MAPS**

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-07



**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**

**INUNDATION
MAPS**

**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-08**

ADDICKS RESERVOIR

BARKER RESERVOIR

BUFFALO BAYOU
FLOOD INFORMATION
HOUSTON, TEXAS
SHEPHERD DR. TO BARKER DAM

SCALE IN FEET
0 3000 6000

LEGEND



FLOOD PLAIN FROM
HYPOTHETICAL BREACH
IN ADDICKS DAM

STREAM MILES ABOVE
SHEPHERD DRIVE

**BUFFALO BAYOU, TEXAS
FLOOD INFORMATION
HOUSTON, TEXAS
SHEPHERD DR. TO BARKER DAM
FLOOD PLAIN FROM
HYPOTHETICAL BREACH
IN ADDICKS DAM**

OFFICE OF THE DISTRICT ENGINEER
U. S. ARMY ENGINEER DISTRICT, GALVESTON
CORPS OF ENGINEERS
GALVESTON, TEXAS


MAY 1977

**ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS**


**INUNDATION
MAPS**

**GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 5-09**

Area Curve for Addicks Reservoir



Capacity Curve for Addicks Reservoir





NOTE: ELEVATIONS ARE NAVD 1988

ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

AREA AND CAPACITY CURVES
ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 7-01




NOTE: ELEVATIONS ARE NAVD 1988

ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

AREA AND CAPACITY CURVES
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 7-02




NOTE: RATE OF RISE IS IN FEET/HOUR

EXAMPLE OF HOW TO READ GRAPH: IF YOU ARE AT ELEVATION 102.8 FT WITH A RATE OF RISE OF .35 OPEN FIVE CONDUITS IN UNISON 1.5' OPENING, TO DISCHARGE 2000 CFS

ADDICKS AND BARKER RESERVOIR
 WATER CONTROL MANUAL
 BUFFALO BAYOU BASIN, TEXAS

INDUCED SURCHARGE
 OPERATIONS SCHEDULE
 ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
 PLATE 7-03



NOTE: RATE OF RISE IS IN FEET/HOUR


EXAMPLE OF HOW TO READ GRAPH: IF YOU ARE AT ELEVATION 100.4 FT WITH A RATE OF RISE OF .15 OPEN FIVE CONDUITS IN UNISON 1' OPENING, TO DISCHARGE 1400 CFS

ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

INDUCED SURCHARGE
REGULATION SCHEDULE
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 7-04


Addicks Reservoir Rating Curve



NOTE: FIVE CONDUITS AVAILABLE


<p>ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS</p>
<p>OUTLET WORKS RATING CURVES ADDICKS RESERVOIR</p>
<p>GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 7-05</p>

Barker Reservoir Rating Curve



NOTE: FIVE CONDUITS AVAILABLE


ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS
OUTLET WORKS RATING CURVES BARKER RESERVOIR
GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 7-06



ADDICKS AND BARKER RESERVOIR
 WATER CONTROL MANUAL
 BUFFALO BAYOU BASIN, TEXAS

1977 SPILLWAY DESIGN FLOOD
 ADDICKS RESERVOIR


GALVESTON DISTRICT, CORPS OF ENGINEERS
 PLATE 8-01



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

1977 SPILLWAY DESIGN FLOOD
BARKER RESERVOIR


GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 8-02



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

1977 STANDARD PROJECT FLOOD
ADDICKS RESERVOIR


GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 8-03



ACCUMULATED RUNOFF IN THOUSAND ACRE-FEET

ADDICKS AND BARKER RESERVOIR WATER CONTROL MANUAL BUFFALO BAYOU BASIN, TEXAS
1977 STANDARD PROJECT FLOOD BARKER RESERVOIR
GALVESTON DISTRICT, CORPS OF ENGINEERS PLATE 8-04

Addicks Pool Frequency Curve




ADDICKS AND BARKER RESERVOIR
 WATER CONTROL MANUAL
 BUFFALO BAYOU BASIN, TEXAS

POOL ELEVATION
 FREQUENCY CURVE
 ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
 PLATE 8-05

Barker Pool Frequency Curve




ADDICKS AND BARKER RESERVOIR
 WATER CONTROL MANUAL
 BUFFALO BAYOU BASIN, TEXAS

POOL ELEVATION
 FREQUENCY CURVE
 BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
 PLATE 8-06

Duration Analysis Plot for Addicks Reservoir




ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

POOL ELEVATION
DURATION CURVE
ADDICKS RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 8-07

Duration Analysis Plot for Barker Reservoir




ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

POOL ELEVATION
DURATION CURVE
BARKER RESERVOIR

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 8-08

ADDICKS AND BARKER RESERVOIRS
ORGANIZATION AND COMMUNICATIONS CHART
FOR WATER MANAGEMENT



ADDICKS AND BARKER RESERVOIR
WATER CONTROL MANUAL
BUFFALO BAYOU BASIN, TEXAS

ORGANIZATION AND
COMMUNICATION CHART
FOR WATER MANAGEMENT

GALVESTON DISTRICT, CORPS OF ENGINEERS
PLATE 9-01